



**ADDENDUM NO. 2
INVITATION FOR BID 2026-016
KITSAP COUNTY**

TO: All Respondents

FROM: Glen McNeill. Purchasing Supervisor

CLOSING DATE: Wednesday **05/15/2026 @2:00 pm (CHANGED)**

REF NO.: **2026-016 IFB DYES INLET BULKHEAD REMOVAL AND SHORELINE RESTORATION**

DATE: 05/06/2026

This second addendum to RFP 2026-016 IFB DYES INLET BULKHEAD REMOVAL AND SHORELINE RESTORATION answers questions that were received at the mandatory site visit and updates documents accordingly. Updated documents to be uploaded separately.

1. Questions and Answers:

1. What are clarifications about TESC/SWPP Plan?
 - **See revised TESC/SWPP plan. Brown property access was deleted and the Best property access added. A 3rd potential stockpiling area near the Friedman-Brown property line is added. Refueling area was changed. It is also noted in the revised TESC/SWPPP plan that "THE PROJECT LIMIT AND CG AREA SHOWN ARE OUTDATED. THESE SHALL BE EXTENDED TO INCLUDE LANDSCAPING/PLANTING AREAS. REFER TO CONTRACT PLANS INCLUDING PLANTING PLANS FOR THE UPDATED PROJECT AND CG LIMITS".**
2. Where does the project start at north-western end?
 - **The project area is shown on design plans. It starts on the Crista Shores property- about 10' west of the property line.**
3. Are disposing of slope soils the contractor's responsibility?
 - **Yes**
4. Can Gazebo be moved in one piece?

- **Yes, if it can be lifted in one piece and safely moved to another location on property. If the contractor damages it, the cost to replace it is the contractor's responsibility.**
5. On the plans, the 30-foot reference line from the OHWM back on the Friedman/Brown property line appears close to blue shed and apple tree. How does the contractor get correct distance?
- **The measurements are design benchmarks, and the engineer will check and approve flagged layout before excavation, and record as-built measurements.**
6. Do contractors need to deal with the water spigot closest to water?
- **No, this waterline is not pressurized (unconnected). It can be removed. The bid Item 6, "WATER SPIGOT RELOCATION", is now removed in the updated Bid Schedule.**
7. Clarify work windows during tidal cycles.
- **Any work done below the OHWM must be done at low tide when dry, or, for the bottom portion of the bulkhead, when the tide is below the lagoon inlet water level (at approximately ELEV. 6-7 FT NAVD88). Kitsap County is currently checking with agencies about working in the wet. Any additional mitigation measures or other new permit requirements will be included in the follow-up Addendum. A draft permit modification will be issued by May 8.**
8. Where is the central road shop where rock material will be taken to?
- **1971 Seabeck Hwy NW, Bremerton 98312**
9. How will rock material be measured at PW road shop?
- **There is no scale and quantities will be measured by truck load records, including trip number, date and time, estimated quantity in CY, and photos of truck load for each load). The total stockpile volume will be estimated by KCPW/Engineer at PW rock shop as a verification. This work will be covered by revised Bid Item 12B paid for by unit price per CY. Rock material if disapproved for stockpiling by the PW or the Engineer will be treated as rubble or debris, which will be covered by Bid Item 12C or considered as field debris covered by Bid Item 13, both requiring disposed of offsite. Bid Item 12C and 13 are revised to be paid for by unit price per TON based on truck weight tickets.**
10. Will Public Works sort and stack rock once it is dumped by contractor at PW road shop yard?

- **Yes. Stacking and sorting rock at the road shop is not the contractor's responsibility. The Contractor shall follow PW staff's direction to unload rock at the destined locations.**
11. Does rock material need to be sorted by similar type in truck loads?
- **Yes**
12. What types of rock will PW road shop take?
- **Angular rock and quarry spalls.**
13. Does dune grass on Friedman's property need to be saved and put in a safe staging place prior to bulkhead removal?
- **Yes, this is covered by Bid Item 9.**
14. Is a light tower ok to use?
- **Yes**
15. What time does work need to stop?
- **7pm. Summer months with long daylight low-tide windows are preferred for construction.**
16. Will the contractor need to submit a work plan that outlines construction sequencing for approval?
- **Yes. This work plan shall be submitted after contracting at least two weeks prior to the planned start date of construction (the Special Provision is revised to be consistent with this requirement). However, the contractor is asked to submit the planned/committed work window together with the bid schedule.**

END OF ADDENDUM NO. 2