

## BID SCHEDULE

Bid Item	Item Description	Specs	Qty	Units	Unit Price	Total Price
<b>SITE PREP &amp; TESC/SWPPP</b>						
1	MOBILIZATION (10% CONSTRUCTION COST)	1-09.7	1	LS	\$	\$
2	CONSTRUCTION SURVEYING AND STAKING	3.3	1	LS	\$	\$
3	CONSTRUCTION PREPARATION: ACCESS, STAGING AND STOCKPIILING AREAS	3.4	1	LS	\$	\$
4	EROSION CONTROL AND WATER POLLUTION PREVENTION	3.5	1	LS	\$	\$
5	'GAZEBO RELOCATION (1#)	3.6	1	LS	\$	\$
7	'TREE/PLANT PROTECTION	3.7	1	LS	\$	\$
9	CLEARING AND GRUBBING, INCLUDING PLANTING AREAS (~40,000SF)	3.8	1	LS	\$	\$
10	SITE RESTORATION	3.9	1	LS	\$	\$
<b>REMOVAL OF SHORE ARMOR</b>						
11	DETERIORATED PILE (14#) & WOOD LAGGING REMOVAL (UNTREATED WOOD), HAUL AND DISPOSAL	4.1	1	LS	\$	\$
12A	ROCK ARMOR REMOVAL, SALVAGING FOR REUSE ONSITE (EST. 50CY ROCK, 25CY SPALLS, REUSE FOR WALLS)	4.2	1	LS	\$	\$
12B	ROCK ARMOR REMOVAL, SALVAGING AND HAUL TO STOCKPILE SITE (EST. 200 CY STOCKPILE SITE ~6 MILES AWAY)	4.2	200	CY	\$	\$
12C	ROCK ARMOR REMOVAL, HAUL, DISPOSAL (EST. 75 TON)	4.2	75	TN	\$	\$
12D	TWO ROCK SILL REFORMATION	4.2	1	LS	\$	\$
13	CONC. RUBBLE, SPALLS, WOOD LAGGING, AND DEBRIS REMOVAL, HAUL, DISPOSAL (EST. TOTAL 260 CY)	4.3	1	LS	\$	\$
<b>BANK / INLAND EXCAVATION AND GRADING</b>						
14	BANK / INLAND EXCAVATION & GRADING, INCL OVER EX., HAUL (EST. TOTAL 1200 CY, SALVAGING QUANTITY UP TO 100 CY FIELD VERIFY)	5.1-5.3	1	LS	\$	\$
15	'STORMWATER OUTFALL PIPE SAWCUT AND STABILIZATION	5.4	4	EA	\$	\$
16	OUTFALL PIPE RECONNECTION (OPTIONAL, FIELD VERIFY)	5.4	1	EA	\$	\$
<b>BEACH NOURISHMENT PLACEMENT</b>						
17	PIT-RUN GRAVEL-SAND	6.4	150	CY	\$	\$
18	COARSE SAND (60%) MIXED WITH PIT-RUN GRAVEL-SAND (40%)	6.3	80	CY	\$	\$
19	COBBLE TOE (IMPORTED COBBLE MIXED WITH 20% SALVAGED SEDIMENT)	6.2	180	CY	\$	\$
<b>ROCK WALLS</b>						
20	RETAINING WALL, SALVAGED ROCK & SPALLS (EST. 56 CY ROCK)	7.0	1	LS	\$	\$
21	RETURN WALL & SPOT REPAIR, SALVAGED ROCK & SPALLS (EST. 19 CY ROCK)	7.0	1	LS	\$	\$
<b>MATERIAL IMPORT</b>						
22	PIT-RUN GRAVEL-SAND MIX (OR MIX WITH NATIVE SEDIMENT - IMPORT QUANTITY FIELD VERIFY)	2.6	265	TON	\$	\$
23	COARSE SAND	2.6	80	TON	\$	\$
24	'1.5"-4" SIZE STREAMBED COBBLE	2.5	200	TON	\$	\$
25	GEOTEXTILE, MIRAFI™ 1100N or EQUIVALENT (FOR WALLS)	2.4	120	SY	\$	\$
26	WOOD CHIP MULCH (MATERIAL ONLY, IMPORT AND STOCKPILE ONSITE)	2.8	256	CY	\$	\$
<b>LANDSCAPING AND PLANTING BED PREPARATION (MATERIAL AND LABOR)</b>						
27	MULCH COVERED PEDESTRIAN PATHS (669 SF, 4" DEPTH) USING SALVAGED MULCH FROM TESC FOR CONSTRUCTION ACCESS	2.7, 8.1	1	LS	\$	\$
28	SOIL AMENDMENT & PLANTING BED PREPARATION (RIP COMPOST & TILL)	2.9, 8.2	270	CY	\$	\$
29	HABITAT LOGS (INCLUDING PLACEMENT), OPTIONAL	2.8, 8.3	4	EA	\$	\$
<b>CONSTRUCTION TOTAL:</b>						
TAX (9.2%):						
<b>BASE BID TOTAL</b>						

NOTE: BID ITEM NUMBERS 6 AND 8 ARE PURPOSELY OMITTED