

KITSAP COUNTY PUBLIC WORKS WASTEWATER DIVISION

SILVERDALE PUMP STATIONS 19 AND 31 UPGRADES

APRIL 2021

BID SET



Volume 2 of 3

Funded in Part by the Washington State Public Works Trust Fund

BACK OF COVER
THIS PAGE INTENTIONALLY LEFT BLANK

APPENDICES – VOLUME 2 OF 3

Appendix A – Washington State Prevailing Wage Rates for Public Works Contracts

Appendix B – Geotechnical Engineering Report

Appendix C – Storm Water Pollution Prevention Plan

Appendix D – PSE Utility Power Design

Appendix E – Manufacturer's "Not to Exceed" Price for Submersible Wastewater Pumps

Appendix F – Contracting Agency-Furnished Permits

Appendix G – Addenda (Not Included)

THIS PAGE INTENTIONALLY LEFT BLANK

APPENDIX A

WASHINGTON STATE PREVAILING WAGE RATES FOR PUBLIC WORKS CONTRACTS

THIS PAGE INTENTIONALLY LEFT BLANK

State of Washington
Department of Labor & Industries
Prevailing Wage Section - Telephone 360-902-5335
PO Box 44540, Olympia, WA 98504-4540

Washington State Prevailing Wage

The PREVAILING WAGES listed here include both the hourly wage rate and the hourly rate of fringe benefits. On public works projects, worker's wage and benefit rates must add to not less than this total. A brief description of overtime calculation requirements are provided on the Benefit Code Key.

Journey Level Prevailing Wage Rates for the Effective Date: 4/28/2021

<u>County</u>	<u>Trade</u>	<u>Job Classification</u>	<u>Wage</u>	<u>Holiday</u>	<u>Overtime</u>	<u>Note</u>	<u>*Risk Class</u>
Kitsap	Asbestos Abatement Workers	Journey Level	\$52.39	<u>5D</u>	<u>1H</u>		View
Kitsap	Boilermakers	Journey Level	\$70.79	<u>5N</u>	<u>1C</u>		View
Kitsap	Brick Mason	Journey Level	\$60.57	<u>7E</u>	<u>1N</u>		View
Kitsap	Brick Mason	Pointer-Caulker-Cleaner	\$60.57	<u>7E</u>	<u>1N</u>		View
Kitsap	Building Service Employees	Janitor	\$13.69		<u>1</u>		View
Kitsap	Building Service Employees	Shampooer	\$13.69		<u>1</u>		View
Kitsap	Building Service Employees	Waxer	\$13.69		<u>1</u>		View
Kitsap	Building Service Employees	Window Cleaner	\$13.69		<u>1</u>		View
Kitsap	Cabinet Makers (In Shop)	Journey Level	\$23.72		<u>1</u>		View
Kitsap	Carpenters	Acoustical Worker	\$64.94	<u>7A</u>	<u>4C</u>		View
Kitsap	Carpenters	Carpenter	\$64.94	<u>7A</u>	<u>4C</u>		View
Kitsap	Carpenters	Carpenters on Stationary Tools	\$65.07	<u>7A</u>	<u>4C</u>		View
Kitsap	Carpenters	Creosoted Material	\$65.07	<u>7A</u>	<u>4C</u>		View
Kitsap	Carpenters	Floor Finisher	\$64.94	<u>7A</u>	<u>4C</u>		View
Kitsap	Carpenters	Floor Layer	\$64.94	<u>7A</u>	<u>4C</u>		View
Kitsap	Carpenters	Scaffold Erector	\$64.94	<u>7A</u>	<u>4C</u>		View
Kitsap	Cement Masons	Application of all Composition Mastic	\$64.84	<u>7A</u>	<u>4U</u>		View
Kitsap	Cement Masons	Application of all Epoxy Material	\$64.34	<u>7A</u>	<u>4U</u>		View
Kitsap	Cement Masons	Application of all Plastic Material	\$64.84	<u>7A</u>	<u>4U</u>		View
Kitsap	Cement Masons	Application of Sealing Compound	\$64.34	<u>7A</u>	<u>4U</u>		View
Kitsap	Cement Masons	Application of Underlayment	\$64.84	<u>7A</u>	<u>4U</u>		View
Kitsap	Cement Masons	Building General	\$64.34	<u>7A</u>	<u>4U</u>		View
Kitsap	Cement Masons	Composition or Kalman Floors	\$64.84	<u>7A</u>	<u>4U</u>		View
Kitsap	Cement Masons	Concrete Paving	\$64.34	<u>7A</u>	<u>4U</u>		View
Kitsap	Cement Masons	Curb & Gutter Machine	\$64.84	<u>7A</u>	<u>4U</u>		View
Kitsap	Cement Masons	Curb & Gutter, Sidewalks	\$64.34	<u>7A</u>	<u>4U</u>		View
Kitsap	Cement Masons	Curing Concrete	\$64.34	<u>7A</u>	<u>4U</u>		View

Kitsap	Cement Masons	Finish Colored Concrete	\$64.84	7A	4U		View
Kitsap	Cement Masons	Floor Grinding	\$64.84	7A	4U		View
Kitsap	Cement Masons	Floor Grinding/Polisher	\$64.34	7A	4U		View
Kitsap	Cement Masons	Green Concrete Saw, self-powered	\$64.84	7A	4U		View
Kitsap	Cement Masons	Grouting of all Plates	\$64.34	7A	4U		View
Kitsap	Cement Masons	Grouting of all Tilt-up Panels	\$64.34	7A	4U		View
Kitsap	Cement Masons	Guniting Nozzleman	\$64.84	7A	4U		View
Kitsap	Cement Masons	Hand Powered Grinder	\$64.84	7A	4U		View
Kitsap	Cement Masons	Journey Level	\$64.34	7A	4U		View
Kitsap	Cement Masons	Patching Concrete	\$64.34	7A	4U		View
Kitsap	Cement Masons	Pneumatic Power Tools	\$64.84	7A	4U		View
Kitsap	Cement Masons	Power Chipping & Brushing	\$64.84	7A	4U		View
Kitsap	Cement Masons	Sand Blasting Architectural Finish	\$64.84	7A	4U		View
Kitsap	Cement Masons	Screed & Rodding Machine	\$64.84	7A	4U		View
Kitsap	Cement Masons	Spackling or Skim Coat Concrete	\$64.34	7A	4U		View
Kitsap	Cement Masons	Troweling Machine Operator	\$64.84	7A	4U		View
Kitsap	Cement Masons	Troweling Machine Operator on Colored Slabs	\$64.84	7A	4U		View
Kitsap	Cement Masons	Tunnel Workers	\$64.84	7A	4U		View
Kitsap	Divers & Tenders	Bell/Vehicle or Submersible Operator (Not Under Pressure)	\$118.80	7A	4C		View
Kitsap	Divers & Tenders	Dive Supervisor/Master	\$81.98	7A	4C		View
Kitsap	Divers & Tenders	Diver	\$118.80	7A	4C	8V	View
Kitsap	Divers & Tenders	Diver On Standby	\$76.98	7A	4C		View
Kitsap	Divers & Tenders	Diver Tender	\$69.91	7A	4C		View
Kitsap	Divers & Tenders	Manifold Operator	\$69.91	7A	4C		View
Kitsap	Divers & Tenders	Manifold Operator Mixed Gas	\$74.91	7A	4C		View
Kitsap	Divers & Tenders	Remote Operated Vehicle Operator/Technician	\$69.91	7A	4C		View
Kitsap	Divers & Tenders	Remote Operated Vehicle Tender	\$65.19	7A	4C		View
Kitsap	Dredge Workers	Assistant Engineer	\$70.62	5D	3F		View
Kitsap	Dredge Workers	Assistant Mate (Deckhand)	\$70.07	5D	3F		View
Kitsap	Dredge Workers	Boatmen	\$70.62	5D	3F		View
Kitsap	Dredge Workers	Engineer Welder	\$71.97	5D	3F		View
Kitsap	Dredge Workers	Leverman, Hydraulic	\$73.41	5D	3F		View
Kitsap	Dredge Workers	Mates	\$70.62	5D	3F		View
Kitsap	Dredge Workers	Oiler	\$70.07	5D	3F		View
Kitsap	Drywall Applicator	Journey Level	\$64.94	5D	1H		View
Kitsap	Drywall Tapers	Journey Level	\$65.31	5P	1E		View
Kitsap	Electrical Fixture Maintenance Workers	Journey Level	\$31.99	5L	1E		View
Kitsap	Electricians - Inside	Cable Splicer	\$92.57	7C	4E		View
Kitsap	Electricians - Inside	Cable Splicer (tunnel)	\$99.46	7C	4E		View
Kitsap	Electricians - Inside	Certified Welder	\$89.44	7C	4E		View

Kitsap	Electricians - Inside	Certified Welder (tunnel)	\$96.02	7C	4E		View
Kitsap	Electricians - Inside	Construction Stock Person	\$44.78	7C	4E		View
Kitsap	Electricians - Inside	Journey Level	\$86.30	7C	4E		View
Kitsap	Electricians - Inside	Journey Level (tunnel)	\$92.57	7C	4E		View
Kitsap	Electricians - Motor Shop	Craftsman	\$15.37		1		View
Kitsap	Electricians - Motor Shop	Journey Level	\$14.69		1		View
Kitsap	Electricians - Powerline Construction	Cable Splicer	\$82.39	5A	4D		View
Kitsap	Electricians - Powerline Construction	Certified Line Welder	\$75.64	5A	4D		View
Kitsap	Electricians - Powerline Construction	Groundperson	\$49.17	5A	4D		View
Kitsap	Electricians - Powerline Construction	Heavy Line Equipment Operator	\$75.64	5A	4D		View
Kitsap	Electricians - Powerline Construction	Journey Level Lineperson	\$75.64	5A	4D		View
Kitsap	Electricians - Powerline Construction	Line Equipment Operator	\$64.54	5A	4D		View
Kitsap	Electricians - Powerline Construction	Meter Installer	\$49.17	5A	4D	8W	View
Kitsap	Electricians - Powerline Construction	Pole Sprayer	\$75.64	5A	4D		View
Kitsap	Electricians - Powerline Construction	Powderperson	\$56.49	5A	4D		View
Kitsap	Electronic Technicians	Journey Level	\$53.57	7E	1E		View
Kitsap	Elevator Constructors	Mechanic	\$100.51	7D	4A		View
Kitsap	Elevator Constructors	Mechanic In Charge	\$108.53	7D	4A		View
Kitsap	Fabricated Precast Concrete Products	Journey Level	\$13.69		1		View
Kitsap	Fabricated Precast Concrete Products	Journey Level - In-Factory Work Only	\$13.69		1		View
Kitsap	Fence Erectors	Fence Erector	\$44.40	7A	4V	8Y	View
Kitsap	Fence Erectors	Fence Laborer	\$44.40	7A	4V	8Y	View
Kitsap	Flaggers	Journey Level	\$44.40	7A	4V	8Y	View
Kitsap	Glaziers	Journey Level	\$69.26	7L	1Y		View
Kitsap	Heat & Frost Insulators And Asbestos Workers	Journeyman	\$79.43	5J	4H		View
Kitsap	Heating Equipment Mechanics	Journey Level	\$89.61	7F	1E		View
Kitsap	Hod Carriers & Mason Tenders	Journey Level	\$54.01	7A	4V	8Y	View
Kitsap	Industrial Power Vacuum Cleaner	Journey Level	\$29.89		1		View
Kitsap	Inland Boatmen	Boat Operator	\$61.41	5B	1K		View
Kitsap	Inland Boatmen	Cook	\$56.48	5B	1K		View
Kitsap	Inland Boatmen	Deckhand	\$57.48	5B	1K		View
Kitsap	Inland Boatmen	Deckhand Engineer	\$58.81	5B	1K		View
Kitsap	Inland Boatmen	Launch Operator	\$58.89	5B	1K		View
Kitsap	Inland Boatmen	Mate	\$57.31	5B	1K		View
Kitsap	Inspection/Cleaning/Sealing Of Sewer & Water Systems By Remote Control	Cleaner Operator, Foamer Operator	\$13.69		1		View

Kitsap	Inspection/Cleaning/Sealing Of Sewer & Water Systems By Remote Control	Grout Truck Operator	\$13.69		1		View
Kitsap	Inspection/Cleaning/Sealing Of Sewer & Water Systems By Remote Control	Head Operator	\$13.69		1		View
Kitsap	Inspection/Cleaning/Sealing Of Sewer & Water Systems By Remote Control	Tv Truck Operator	\$24.17		1		View
Kitsap	Insulation Applicators	Journey Level	\$64.94	7A	4C		View
Kitsap	Ironworkers	Journeyman	\$76.78	7N	10		View
Kitsap	Laborers	Air, Gas Or Electric Vibrating Screed	\$52.39	7A	4V	8Y	View
Kitsap	Laborers	Airtrac Drill Operator	\$54.01	7A	4V	8Y	View
Kitsap	Laborers	Ballast Regular Machine	\$52.39	7A	4V	8Y	View
Kitsap	Laborers	Batch Weighman	\$44.40	7A	4V	8Y	View
Kitsap	Laborers	Brick Pavers	\$52.39	7A	4V	8Y	View
Kitsap	Laborers	Brush Cutter	\$52.39	7A	4V	8Y	View
Kitsap	Laborers	Brush Hog Feeder	\$52.39	7A	4V	8Y	View
Kitsap	Laborers	Burner	\$52.39	7A	4V	8Y	View
Kitsap	Laborers	Caisson Worker	\$54.01	7A	4V	8Y	View
Kitsap	Laborers	Carpenter Tender	\$52.39	7A	4V	8Y	View
Kitsap	Laborers	Cement Dumper-paving	\$53.35	7A	4V	8Y	View
Kitsap	Laborers	Cement Finisher Tender	\$52.39	7A	4V	8Y	View
Kitsap	Laborers	Change House Or Dry Shack	\$52.39	7A	4V	8Y	View
Kitsap	Laborers	Chipping Gun (30 Lbs. And Over)	\$53.35	7A	4V	8Y	View
Kitsap	Laborers	Chipping Gun (Under 30 Lbs.)	\$52.39	7A	4V	8Y	View
Kitsap	Laborers	Choker Setter	\$52.39	7A	4V	8Y	View
Kitsap	Laborers	Chuck Tender	\$52.39	7A	4V	8Y	View
Kitsap	Laborers	Clary Power Spreader	\$53.35	7A	4V	8Y	View
Kitsap	Laborers	Clean-up Laborer	\$52.39	7A	4V	8Y	View
Kitsap	Laborers	Concrete Dumper/Chute Operator	\$53.35	7A	4V	8Y	View
Kitsap	Laborers	Concrete Form Stripper	\$52.39	7A	4V	8Y	View
Kitsap	Laborers	Concrete Placement Crew	\$53.35	7A	4V	8Y	View
Kitsap	Laborers	Concrete Saw Operator/Core Driller	\$53.35	7A	4V	8Y	View
Kitsap	Laborers	Crusher Feeder	\$44.40	7A	4V	8Y	View
Kitsap	Laborers	Curing Laborer	\$52.39	7A	4V	8Y	View
Kitsap	Laborers	Demolition: Wrecking & Moving (Incl. Charred Material)	\$52.39	7A	4V	8Y	View
Kitsap	Laborers	Ditch Digger	\$52.39	7A	4V	8Y	View
Kitsap	Laborers	Diver	\$54.01	7A	4V	8Y	View
Kitsap	Laborers	Drill Operator (Hydraulic, Diamond)	\$53.35	7A	4V	8Y	View
Kitsap	Laborers	Dry Stack Walls	\$52.39	7A	4V	8Y	View
Kitsap	Laborers	Dump Person	\$52.39	7A	4V	8Y	View
Kitsap	Laborers	Epoxy Technician	\$52.39	7A	4V	8Y	View

Kitsap	Laborers	Erosion Control Worker	\$52.39	7A	4V	8Y	View
Kitsap	Laborers	Faller & Bucker Chain Saw	\$53.35	7A	4V	8Y	View
Kitsap	Laborers	Fine Graders	\$52.39	7A	4V	8Y	View
Kitsap	Laborers	Firewatch	\$44.40	7A	4V	8Y	View
Kitsap	Laborers	Form Setter	\$52.39	7A	4V	8Y	View
Kitsap	Laborers	Gabian Basket Builders	\$52.39	7A	4V	8Y	View
Kitsap	Laborers	General Laborer	\$52.39	7A	4V	8Y	View
Kitsap	Laborers	Grade Checker & Transit Person	\$54.01	7A	4V	8Y	View
Kitsap	Laborers	Grinders	\$52.39	7A	4V	8Y	View
Kitsap	Laborers	Grout Machine Tender	\$52.39	7A	4V	8Y	View
Kitsap	Laborers	Groutmen (Pressure) Including Post Tension Beams	\$53.35	7A	4V	8Y	View
Kitsap	Laborers	Guardrail Erector	\$52.39	7A	4V	8Y	View
Kitsap	Laborers	Hazardous Waste Worker (Level A)	\$54.01	7A	4V	8Y	View
Kitsap	Laborers	Hazardous Waste Worker (Level B)	\$53.35	7A	4V	8Y	View
Kitsap	Laborers	Hazardous Waste Worker (Level C)	\$52.39	7A	4V	8Y	View
Kitsap	Laborers	High Scaler	\$54.01	7A	4V	8Y	View
Kitsap	Laborers	Jackhammer	\$53.35	7A	4V	8Y	View
Kitsap	Laborers	Laserbeam Operator	\$53.35	7A	4V	8Y	View
Kitsap	Laborers	Maintenance Person	\$52.39	7A	4V	8Y	View
Kitsap	Laborers	Manhole Builder-Mudman	\$53.35	7A	4V	8Y	View
Kitsap	Laborers	Material Yard Person	\$52.39	7A	4V	8Y	View
Kitsap	Laborers	Motorman-Dinky Locomotive	\$53.35	7A	4V	8Y	View
Kitsap	Laborers	Nozzleman (Concrete Pump, Green Cutter When Using Combination Of High Pressure Air & Water On Concrete & Rock, Sandblast, Gunite, Shotcrete, Water Blaster, Vacuum Blaster)	\$53.35	7A	4V	8Y	View
Kitsap	Laborers	Pavement Breaker	\$53.35	7A	4V	8Y	View
Kitsap	Laborers	Pilot Car	\$44.40	7A	4V	8Y	View
Kitsap	Laborers	Pipe Layer Lead	\$54.01	7A	4V	8Y	View
Kitsap	Laborers	Pipe Layer/Tailor	\$53.35	7A	4V	8Y	View
Kitsap	Laborers	Pipe Pot Tender	\$53.35	7A	4V	8Y	View
Kitsap	Laborers	Pipe Reliner	\$53.35	7A	4V	8Y	View
Kitsap	Laborers	Pipe Wrapper	\$53.35	7A	4V	8Y	View
Kitsap	Laborers	Pot Tender	\$52.39	7A	4V	8Y	View
Kitsap	Laborers	Powderman	\$54.01	7A	4V	8Y	View
Kitsap	Laborers	Powderman's Helper	\$52.39	7A	4V	8Y	View
Kitsap	Laborers	Power Jacks	\$53.35	7A	4V	8Y	View
Kitsap	Laborers	Railroad Spike Puller - Power	\$53.35	7A	4V	8Y	View
Kitsap	Laborers	Raker - Asphalt	\$54.01	7A	4V	8Y	View
Kitsap	Laborers	Re-timberman	\$54.01	7A	4V	8Y	View
Kitsap	Laborers	Remote Equipment Operator	\$53.35	7A	4V	8Y	View
Kitsap	Laborers	Rigger/Signal Person	\$53.35	7A	4V	8Y	View

Kitsap	Laborers	Rip Rap Person	\$52.39	7A	4V	8Y	View
Kitsap	Laborers	Rivet Buster	\$53.35	7A	4V	8Y	View
Kitsap	Laborers	Rodder	\$53.35	7A	4V	8Y	View
Kitsap	Laborers	Scaffold Erector	\$52.39	7A	4V	8Y	View
Kitsap	Laborers	Scale Person	\$52.39	7A	4V	8Y	View
Kitsap	Laborers	Sloper (Over 20")	\$53.35	7A	4V	8Y	View
Kitsap	Laborers	Sloper Sprayer	\$52.39	7A	4V	8Y	View
Kitsap	Laborers	Spreader (Concrete)	\$53.35	7A	4V	8Y	View
Kitsap	Laborers	Stake Hopper	\$52.39	7A	4V	8Y	View
Kitsap	Laborers	Stock Piler	\$52.39	7A	4V	8Y	View
Kitsap	Laborers	Swinging Stage/Boatswain Chair	\$44.40	7A	4V	8Y	View
Kitsap	Laborers	Tamper & Similar Electric, Air & Gas Operated Tools	\$53.35	7A	4V	8Y	View
Kitsap	Laborers	Tamper (Multiple & Self-propelled)	\$53.35	7A	4V	8Y	View
Kitsap	Laborers	Timber Person - Sewer (Lagger, Shorer & Cribber)	\$53.35	7A	4V	8Y	View
Kitsap	Laborers	Toolroom Person (at Jobsite)	\$52.39	7A	4V	8Y	View
Kitsap	Laborers	Topper	\$52.39	7A	4V	8Y	View
Kitsap	Laborers	Track Laborer	\$52.39	7A	4V	8Y	View
Kitsap	Laborers	Track Liner (Power)	\$53.35	7A	4V	8Y	View
Kitsap	Laborers	Traffic Control Laborer	\$47.48	7A	4V	9C	View
Kitsap	Laborers	Traffic Control Supervisor	\$50.31	7A	4V	9C	View
Kitsap	Laborers	Truck Spotter	\$52.39	7A	4V	8Y	View
Kitsap	Laborers	Tugger Operator	\$53.35	7A	4V	8Y	View
Kitsap	Laborers	Tunnel Work-Compressed Air Worker 0-30 psi	\$129.67	7A	4V	9B	View
Kitsap	Laborers	Tunnel Work-Compressed Air Worker 30.01-44.00 psi	\$134.70	7A	4V	9B	View
Kitsap	Laborers	Tunnel Work-Compressed Air Worker 44.01-54.00 psi	\$138.38	7A	4V	9B	View
Kitsap	Laborers	Tunnel Work-Compressed Air Worker 54.01-60.00 psi	\$144.08	7A	4V	9B	View
Kitsap	Laborers	Tunnel Work-Compressed Air Worker 60.01-64.00 psi	\$146.20	7A	4V	9B	View
Kitsap	Laborers	Tunnel Work-Compressed Air Worker 64.01-68.00 psi	\$151.30	7A	4V	9B	View
Kitsap	Laborers	Tunnel Work-Compressed Air Worker 68.01-70.00 psi	\$153.20	7A	4V	9B	View
Kitsap	Laborers	Tunnel Work-Compressed Air Worker 70.01-72.00 psi	\$155.20	7A	4V	9B	View
Kitsap	Laborers	Tunnel Work-Compressed Air Worker 72.01-74.00 psi	\$157.20	7A	4V	9B	View
Kitsap	Laborers	Tunnel Work-Guage and Lock Tender	\$54.11	7A	4V	8Y	View
Kitsap	Laborers	Tunnel Work-Miner	\$54.11	7A	4V	8Y	View
Kitsap	Laborers	Vibrator	\$53.35	7A	4V	8Y	View
Kitsap	Laborers	Vinyl Seamer	\$52.39	7A	4V	8Y	View
Kitsap	Laborers	Watchman	\$40.36	7A	4V	8Y	View

Kitsap	Laborers	Welder	\$53.35	7A	4V	8Y	View
Kitsap	Laborers	Well Point Laborer	\$53.35	7A	4V	8Y	View
Kitsap	Laborers	Window Washer/Cleaner	\$40.36	7A	4V	8Y	View
Kitsap	Laborers - Underground Sewer & Water	General Laborer & Topman	\$52.39	7A	4V	8Y	View
Kitsap	Laborers - Underground Sewer & Water	Pipe Layer	\$53.35	7A	4V	8Y	View
Kitsap	Landscape Construction	Landscape Construction/Landscaping Or Planting Laborers	\$40.36	7A	4V	8Y	View
Kitsap	Landscape Construction	Landscape Operator	\$69.33	7A	3K	8X	View
Kitsap	Landscape Maintenance	Groundskeeper	\$13.69		1		View
Kitsap	Lathers	Journey Level	\$64.94	5D	1H		View
Kitsap	Marble Setters	Journey Level	\$60.57	7E	1N		View
Kitsap	Metal Fabrication (In Shop)	Fitter	\$26.96		1		View
Kitsap	Metal Fabrication (In Shop)	Laborer	\$13.69		1		View
Kitsap	Metal Fabrication (In Shop)	Machine Operator	\$13.83		1		View
Kitsap	Metal Fabrication (In Shop)	Welder	\$13.83		1		View
Kitsap	Millwright	Journey Level	\$66.44	7A	4C		View
Kitsap	Modular Buildings	Cabinet Assembly	\$13.69		1		View
Kitsap	Modular Buildings	Electrician	\$13.69		1		View
Kitsap	Modular Buildings	Equipment Maintenance	\$13.69		1		View
Kitsap	Modular Buildings	Plumber	\$13.69		1		View
Kitsap	Modular Buildings	Production Worker	\$13.69		1		View
Kitsap	Modular Buildings	Tool Maintenance	\$13.69		1		View
Kitsap	Modular Buildings	Utility Person	\$13.69		1		View
Kitsap	Modular Buildings	Welder	\$13.69		1		View
Kitsap	Painters	Journey Level	\$45.40	6Z	2B		View
Kitsap	Pile Driver	Crew Tender	\$69.91	7A	4C		View
Kitsap	Pile Driver	Crew Tender/Technician	\$69.91	7A	4C		View
Kitsap	Pile Driver	Hyperbaric Worker - Compressed Air Worker 0-30.00 PSI	\$80.76	7A	4C		View
Kitsap	Pile Driver	Hyperbaric Worker - Compressed Air Worker 30.01 - 44.00 PSI	\$85.76	7A	4C		View
Kitsap	Pile Driver	Hyperbaric Worker - Compressed Air Worker 44.01 - 54.00 PSI	\$89.76	7A	4C		View
Kitsap	Pile Driver	Hyperbaric Worker - Compressed Air Worker 54.01 - 60.00 PSI	\$94.76	7A	4C		View
Kitsap	Pile Driver	Hyperbaric Worker - Compressed Air Worker 60.01 - 64.00 PSI	\$97.26	7A	4C		View
Kitsap	Pile Driver	Hyperbaric Worker - Compressed Air Worker 64.01 - 68.00 PSI	\$102.26	7A	4C		View
Kitsap	Pile Driver	Hyperbaric Worker - Compressed Air Worker 68.01 - 70.00 PSI	\$104.26	7A	4C		View

Kitsap	Pile Driver	Hyperbaric Worker - Compressed Air Worker 70.01 - 72.00 PSI	\$106.26	7A	4C		View
Kitsap	Pile Driver	Hyperbaric Worker - Compressed Air Worker 72.01 - 74.00 PSI	\$108.26	7A	4C		View
Kitsap	Pile Driver	Journey Level	\$65.19	7A	4C		View
Kitsap	Plasterers	Journey Level	\$61.67	7Q	1R		View
Kitsap	Playground & Park Equipment Installers	Journey Level	\$13.69		1		View
Kitsap	Plumbers & Pipefitters	Journey Level	\$79.47	5A	1G		View
Kitsap	Power Equipment Operators	Asphalt Plant Operators	\$70.49	7A	3K	8X	View
Kitsap	Power Equipment Operators	Assistant Engineer	\$66.30	7A	3K	8X	View
Kitsap	Power Equipment Operators	Barrier Machine (zipper)	\$69.87	7A	3K	8X	View
Kitsap	Power Equipment Operators	Batch Plant Operator: concrete	\$69.87	7A	3K	8X	View
Kitsap	Power Equipment Operators	Bobcat	\$66.30	7A	3K	8X	View
Kitsap	Power Equipment Operators	Brokk - Remote Demolition Equipment	\$66.30	7A	3K	8X	View
Kitsap	Power Equipment Operators	Brooms	\$66.30	7A	3K	8X	View
Kitsap	Power Equipment Operators	Bump Cutter	\$69.87	7A	3K	8X	View
Kitsap	Power Equipment Operators	Cableways	\$70.49	7A	3K	8X	View
Kitsap	Power Equipment Operators	Chipper	\$69.87	7A	3K	8X	View
Kitsap	Power Equipment Operators	Compressor	\$66.30	7A	3K	8X	View
Kitsap	Power Equipment Operators	Concrete Finish Machine - Laser Screed	\$66.30	7A	3K	8X	View
Kitsap	Power Equipment Operators	Concrete Pump - Mounted Or Trailer High Pressure Line Pump, Pump High Pressure	\$69.33	7A	3K	8X	View
Kitsap	Power Equipment Operators	Concrete Pump: Truck Mount With Boom Attachment Over 42 M	\$70.49	7A	3K	8X	View
Kitsap	Power Equipment Operators	Concrete Pump: Truck Mount With Boom Attachment Up To 42m	\$69.87	7A	3K	8X	View
Kitsap	Power Equipment Operators	Conveyors	\$69.33	7A	3K	8X	View
Kitsap	Power Equipment Operators	Cranes friction: 200 tons and over	\$72.63	7A	3K	8X	View
Kitsap	Power Equipment Operators	Cranes: 100 tons through 199 tons, or 150' of boom (including jib with attachments)	\$71.20	7A	3K	8X	View
Kitsap	Power Equipment Operators	Cranes: 20 Tons Through 44 Tons With Attachments	\$69.87	7A	3K	8X	View
Kitsap	Power Equipment Operators	Cranes: 200 tons- 299 tons, or 250' of boom including jib with attachments	\$71.93	7A	3K	8X	View
Kitsap	Power Equipment Operators	Cranes: 300 tons and over or 300' of boom including jib with attachments	\$72.63	7A	3K	8X	View
Kitsap	Power Equipment Operators	Cranes: 45 Tons Through 99 Tons, Under 150' Of Boom	\$70.49	7A	3K	8X	View

		(including Jib With Attachments)					
Kitsap	Power Equipment Operators	Cranes: A-frame - 10 Tons And Under	\$66.30	7A	3K	8X	View
Kitsap	Power Equipment Operators	Cranes: Friction cranes through 199 tons	\$71.93	7A	3K	8X	View
Kitsap	Power Equipment Operators	Cranes: through 19 tons with attachments, A-frame over 10 tons	\$69.33	7A	3K	8X	View
Kitsap	Power Equipment Operators	Crusher	\$69.87	7A	3K	8X	View
Kitsap	Power Equipment Operators	Deck Engineer/Deck Winches (power)	\$69.87	7A	3K	8X	View
Kitsap	Power Equipment Operators	Derricks, On Building Work	\$70.49	7A	3K	8X	View
Kitsap	Power Equipment Operators	Dozers D-9 & Under	\$69.33	7A	3K	8X	View
Kitsap	Power Equipment Operators	Drill Oilers: Auger Type, Truck Or Crane Mount	\$69.33	7A	3K	8X	View
Kitsap	Power Equipment Operators	Drilling Machine	\$71.20	7A	3K	8X	View
Kitsap	Power Equipment Operators	Elevator And Man-lift: Permanent And Shaft Type	\$66.30	7A	3K	8X	View
Kitsap	Power Equipment Operators	Finishing Machine, Bidwell And Gamaco & Similar Equipment	\$69.87	7A	3K	8X	View
Kitsap	Power Equipment Operators	Forklift: 3000 Lbs And Over With Attachments	\$69.33	7A	3K	8X	View
Kitsap	Power Equipment Operators	Forklifts: Under 3000 Lbs. With Attachments	\$66.30	7A	3K	8X	View
Kitsap	Power Equipment Operators	Grade Engineer: Using Blue Prints, Cut Sheets, Etc	\$69.87	7A	3K	8X	View
Kitsap	Power Equipment Operators	Gradechecker/Stakeman	\$66.30	7A	3K	8X	View
Kitsap	Power Equipment Operators	Guardrail Punch	\$69.87	7A	3K	8X	View
Kitsap	Power Equipment Operators	Hard Tail End Dump Articulating Off- Road Equipment 45 Yards. & Over	\$70.49	7A	3K	8X	View
Kitsap	Power Equipment Operators	Hard Tail End Dump Articulating Off-road Equipment Under 45 Yards	\$69.87	7A	3K	8X	View
Kitsap	Power Equipment Operators	Horizontal/Directional Drill Locator	\$69.33	7A	3K	8X	View
Kitsap	Power Equipment Operators	Horizontal/Directional Drill Operator	\$69.87	7A	3K	8X	View
Kitsap	Power Equipment Operators	Hydralifts/Boom Trucks Over 10 Tons	\$69.33	7A	3K	8X	View
Kitsap	Power Equipment Operators	Hydralifts/Boom Trucks, 10 Tons And Under	\$66.30	7A	3K	8X	View
Kitsap	Power Equipment Operators	Loader, Overhead 8 Yards. & Over	\$71.20	7A	3K	8X	View
Kitsap	Power Equipment Operators	Loader, Overhead, 6 Yards. But Not Including 8 Yards	\$70.49	7A	3K	8X	View
Kitsap	Power Equipment Operators	Loaders, Overhead Under 6 Yards	\$69.87	7A	3K	8X	View
Kitsap	Power Equipment Operators	Loaders, Plant Feed	\$69.87	7A	3K	8X	View
Kitsap	Power Equipment Operators	Loaders: Elevating Type Belt	\$69.33	7A	3K	8X	View
Kitsap	Power Equipment Operators	Locomotives, All	\$69.87	7A	3K	8X	View

Kitsap	Power Equipment Operators	Material Transfer Device	\$69.87	7A	3K	8X	View
Kitsap	Power Equipment Operators	Mechanics, All (leadmen - \$0.50 Per Hour Over Mechanic)	\$71.20	7A	3K	8X	View
Kitsap	Power Equipment Operators	Motor Patrol Graders	\$70.49	7A	3K	8X	View
Kitsap	Power Equipment Operators	Mucking Machine, Mole, Tunnel Drill, Boring, Road Header And/or Shield	\$70.49	7A	3K	8X	View
Kitsap	Power Equipment Operators	Oil Distributors, Blower Distribution & Mulch Seeding Operator	\$66.30	7A	3K	8X	View
Kitsap	Power Equipment Operators	Outside Hoists (Elevators And Manlifts), Air Tuggers, Strato	\$69.33	7A	3K	8X	View
Kitsap	Power Equipment Operators	Overhead, Bridge Type Crane: 20 Tons Through 44 Tons	\$69.87	7A	3K	8X	View
Kitsap	Power Equipment Operators	Overhead, Bridge Type: 100 Tons And Over	\$71.20	7A	3K	8X	View
Kitsap	Power Equipment Operators	Overhead, Bridge Type: 45 Tons Through 99 Tons	\$70.49	7A	3K	8X	View
Kitsap	Power Equipment Operators	Pavement Breaker	\$66.30	7A	3K	8X	View
Kitsap	Power Equipment Operators	Pile Driver (other Than Crane Mount)	\$69.87	7A	3K	8X	View
Kitsap	Power Equipment Operators	Plant Oiler - Asphalt, Crusher	\$69.33	7A	3K	8X	View
Kitsap	Power Equipment Operators	Posthole Digger, Mechanical	\$66.30	7A	3K	8X	View
Kitsap	Power Equipment Operators	Power Plant	\$66.30	7A	3K	8X	View
Kitsap	Power Equipment Operators	Pumps - Water	\$66.30	7A	3K	8X	View
Kitsap	Power Equipment Operators	Quad 9, Hd 41, D10 And Over	\$70.49	7A	3K	8X	View
Kitsap	Power Equipment Operators	Quick Tower - No Cab, Under 100 Feet In Height Based To Boom	\$66.30	7A	3K	8X	View
Kitsap	Power Equipment Operators	Remote Control Operator On Rubber Tired Earth Moving Equipment	\$70.49	7A	3K	8X	View
Kitsap	Power Equipment Operators	Rigger and Bellman	\$66.30	7A	3K	8X	View
Kitsap	Power Equipment Operators	Rigger/Signal Person, Bellman (Certified)	\$69.33	7A	3K	8X	View
Kitsap	Power Equipment Operators	Rollagon	\$70.49	7A	3K	8X	View
Kitsap	Power Equipment Operators	Roller, Other Than Plant Mix	\$66.30	7A	3K	8X	View
Kitsap	Power Equipment Operators	Roller, Plant Mix Or Multi-lift Materials	\$69.33	7A	3K	8X	View
Kitsap	Power Equipment Operators	Roto-mill, Roto-grinder	\$69.87	7A	3K	8X	View
Kitsap	Power Equipment Operators	Saws - Concrete	\$69.33	7A	3K	8X	View
Kitsap	Power Equipment Operators	Scraper, Self Propelled Under 45 Yards	\$69.87	7A	3K	8X	View
Kitsap	Power Equipment Operators	Scrapers - Concrete & Carry All	\$69.33	7A	3K	8X	View
Kitsap	Power Equipment Operators	Scrapers, Self-propelled: 45 Yards And Over	\$70.49	7A	3K	8X	View
Kitsap	Power Equipment Operators	Service Engineers - Equipment	\$69.33	7A	3K	8X	View
Kitsap	Power Equipment Operators	Shotcrete/Gunite Equipment	\$66.30	7A	3K	8X	View
Kitsap	Power Equipment Operators	Shovel, Excavator, Backhoe, Tractors Under 15 Metric Tons	\$69.33	7A	3K	8X	View
Kitsap	Power Equipment Operators	Shovel, Excavator, Backhoe:	\$70.49	7A	3K	8X	View

		Over 30 Metric Tons To 50 Metric Tons					
Kitsap	Power Equipment Operators	Shovel, Excavator, Backhoes, Tractors: 15 To 30 Metric Tons	\$69.87	7A	3K	8X	View
Kitsap	Power Equipment Operators	Shovel, Excavator, Backhoes: Over 50 Metric Tons To 90 Metric Tons	\$71.20	7A	3K	8X	View
Kitsap	Power Equipment Operators	Shovel, Excavator, Backhoes: Over 90 Metric Tons	\$71.93	7A	3K	8X	View
Kitsap	Power Equipment Operators	Slipform Pavers	\$70.49	7A	3K	8X	View
Kitsap	Power Equipment Operators	Spreader, Topsider & Screedman	\$70.49	7A	3K	8X	View
Kitsap	Power Equipment Operators	Subgrader Trimmer	\$69.87	7A	3K	8X	View
Kitsap	Power Equipment Operators	Tower Bucket Elevators	\$69.33	7A	3K	8X	View
Kitsap	Power Equipment Operators	Tower Crane Up To 175' In Height Base To Boom	\$71.20	7A	3K	8X	View
Kitsap	Power Equipment Operators	Tower Crane: over 175' through 250' in height, base to boom	\$71.93	7A	3K	8X	View
Kitsap	Power Equipment Operators	Tower Cranes: over 250' in height from base to boom	\$72.63	7A	3K	8X	View
Kitsap	Power Equipment Operators	Transporters, All Track Or Truck Type	\$70.49	7A	3K	8X	View
Kitsap	Power Equipment Operators	Trenching Machines	\$69.33	7A	3K	8X	View
Kitsap	Power Equipment Operators	Truck Crane Oiler/driver - 100 Tons And Over	\$69.87	7A	3K	8X	View
Kitsap	Power Equipment Operators	Truck Crane Oiler/Driver Under 100 Tons	\$69.33	7A	3K	8X	View
Kitsap	Power Equipment Operators	Truck Mount Portable Conveyor	\$69.87	7A	3K	8X	View
Kitsap	Power Equipment Operators	Welder	\$70.49	7A	3K	8X	View
Kitsap	Power Equipment Operators	Wheel Tractors, Farmall Type	\$66.30	7A	3K	8X	View
Kitsap	Power Equipment Operators	Yo Yo Pay Dozer	\$69.87	7A	3K	8X	View
Kitsap	Power Equipment Operators-Underground Sewer & Water	Asphalt Plant Operators	\$70.49	7A	3K	8X	View
Kitsap	Power Equipment Operators-Underground Sewer & Water	Assistant Engineer	\$66.30	7A	3K	8X	View
Kitsap	Power Equipment Operators-Underground Sewer & Water	Barrier Machine (zipper)	\$69.87	7A	3K	8X	View
Kitsap	Power Equipment Operators-Underground Sewer & Water	Batch Plant Operator, Concrete	\$69.87	7A	3K	8X	View
Kitsap	Power Equipment Operators-Underground Sewer & Water	Bobcat	\$66.30	7A	3K	8X	View
Kitsap	Power Equipment Operators-Underground Sewer & Water	Brokk - Remote Demolition Equipment	\$66.30	7A	3K	8X	View
Kitsap	Power Equipment Operators-Underground Sewer & Water	Brooms	\$66.30	7A	3K	8X	View
Kitsap	Power Equipment Operators-Underground Sewer & Water	Bump Cutter	\$69.87	7A	3K	8X	View
Kitsap	Power Equipment Operators-Underground Sewer & Water	Cableways	\$70.49	7A	3K	8X	View
Kitsap	Power Equipment Operators-Underground Sewer & Water	Chipper	\$69.87	7A	3K	8X	View
Kitsap	Power Equipment Operators-	Compressor	\$66.30	7A	3K	8X	View

	Underground Sewer & Water						
Kitsap	Power Equipment Operators- Underground Sewer & Water	Concrete Finish Machine - Laser Screed	\$66.30	7A	3K	8X	View
Kitsap	Power Equipment Operators- Underground Sewer & Water	Concrete Pump - Mounted Or Trailer High Pressure Line Pump, Pump High Pressure	\$69.33	7A	3K	8X	View
Kitsap	Power Equipment Operators- Underground Sewer & Water	Concrete Pump: Truck Mount With Boom Attachment Over 42 M	\$70.49	7A	3K	8X	View
Kitsap	Power Equipment Operators- Underground Sewer & Water	Concrete Pump: Truck Mount With Boom Attachment Up To 42m	\$69.87	7A	3K	8X	View
Kitsap	Power Equipment Operators- Underground Sewer & Water	Conveyors	\$69.33	7A	3K	8X	View
Kitsap	Power Equipment Operators- Underground Sewer & Water	Cranes friction: 200 tons and over	\$72.63	7A	3K	8X	View
Kitsap	Power Equipment Operators- Underground Sewer & Water	Cranes: 100 tons through 199 tons, or 150' of boom (including jib with attachments)	\$71.20	7A	3K	8X	View
Kitsap	Power Equipment Operators- Underground Sewer & Water	Cranes: 20 Tons Through 44 Tons With Attachments	\$69.87	7A	3K	8X	View
Kitsap	Power Equipment Operators- Underground Sewer & Water	Cranes: 200 tons- 299 tons, or 250' of boom including jib with attachments	\$71.93	7A	3K	8X	View
Kitsap	Power Equipment Operators- Underground Sewer & Water	Cranes: 300 tons and over or 300' of boom including jib with attachments	\$72.63	7A	3K	8X	View
Kitsap	Power Equipment Operators- Underground Sewer & Water	Cranes: 45 Tons Through 99 Tons, Under 150' Of Boom (including Jib With Attachments)	\$70.49	7A	3K	8X	View
Kitsap	Power Equipment Operators- Underground Sewer & Water	Cranes: A-frame - 10 Tons And Under	\$66.30	7A	3K	8X	View
Kitsap	Power Equipment Operators- Underground Sewer & Water	Cranes: Friction cranes through 199 tons	\$71.93	7A	3K	8X	View
Kitsap	Power Equipment Operators- Underground Sewer & Water	Cranes: through 19 tons with attachments, A-frame over 10 tons	\$69.33	7A	3K	8X	View
Kitsap	Power Equipment Operators- Underground Sewer & Water	Crusher	\$69.87	7A	3K	8X	View
Kitsap	Power Equipment Operators- Underground Sewer & Water	Deck Engineer/Deck Winches (power)	\$69.87	7A	3K	8X	View
Kitsap	Power Equipment Operators- Underground Sewer & Water	Derricks, On Building Work	\$70.49	7A	3K	8X	View
Kitsap	Power Equipment Operators- Underground Sewer & Water	Dozers D-9 & Under	\$69.33	7A	3K	8X	View
Kitsap	Power Equipment Operators- Underground Sewer & Water	Drill Oilers: Auger Type, Truck Or Crane Mount	\$69.33	7A	3K	8X	View
Kitsap	Power Equipment Operators- Underground Sewer & Water	Drilling Machine	\$71.20	7A	3K	8X	View
Kitsap	Power Equipment Operators- Underground Sewer & Water	Elevator And Man-lift: Permanent And Shaft Type	\$66.30	7A	3K	8X	View
Kitsap	Power Equipment Operators-	Finishing Machine, Bidwell And	\$69.87	7A	3K	8X	View

	Underground Sewer & Water	Gamaco & Similar Equipment					
Kitsap	Power Equipment Operators- Underground Sewer & Water	Forklift: 3000 Lbs And Over With Attachments	\$69.33	7A	3K	8X	View
Kitsap	Power Equipment Operators- Underground Sewer & Water	Forklifts: Under 3000 Lbs. With Attachments	\$66.30	7A	3K	8X	View
Kitsap	Power Equipment Operators- Underground Sewer & Water	Grade Engineer: Using Blue Prints, Cut Sheets, Etc	\$69.87	7A	3K	8X	View
Kitsap	Power Equipment Operators- Underground Sewer & Water	Gradechecker/Stakeman	\$66.30	7A	3K	8X	View
Kitsap	Power Equipment Operators- Underground Sewer & Water	Guardrail Punch	\$69.87	7A	3K	8X	View
Kitsap	Power Equipment Operators- Underground Sewer & Water	Hard Tail End Dump Articulating Off- Road Equipment 45 Yards. & Over	\$70.49	7A	3K	8X	View
Kitsap	Power Equipment Operators- Underground Sewer & Water	Hard Tail End Dump Articulating Off-road Equipment Under 45 Yards	\$69.87	7A	3K	8X	View
Kitsap	Power Equipment Operators- Underground Sewer & Water	Horizontal/Directional Drill Locator	\$69.33	7A	3K	8X	View
Kitsap	Power Equipment Operators- Underground Sewer & Water	Horizontal/Directional Drill Operator	\$69.87	7A	3K	8X	View
Kitsap	Power Equipment Operators- Underground Sewer & Water	Hydralifts/Boom Trucks Over 10 Tons	\$69.33	7A	3K	8X	View
Kitsap	Power Equipment Operators- Underground Sewer & Water	Hydralifts/Boom Trucks, 10 Tons And Under	\$66.30	7A	3K	8X	View
Kitsap	Power Equipment Operators- Underground Sewer & Water	Loader, Overhead 8 Yards. & Over	\$71.20	7A	3K	8X	View
Kitsap	Power Equipment Operators- Underground Sewer & Water	Loader, Overhead, 6 Yards. But Not Including 8 Yards	\$70.49	7A	3K	8X	View
Kitsap	Power Equipment Operators- Underground Sewer & Water	Loaders, Overhead Under 6 Yards	\$69.87	7A	3K	8X	View
Kitsap	Power Equipment Operators- Underground Sewer & Water	Loaders, Plant Feed	\$69.87	7A	3K	8X	View
Kitsap	Power Equipment Operators- Underground Sewer & Water	Loaders: Elevating Type Belt	\$69.33	7A	3K	8X	View
Kitsap	Power Equipment Operators- Underground Sewer & Water	Locomotives, All	\$69.87	7A	3K	8X	View
Kitsap	Power Equipment Operators- Underground Sewer & Water	Material Transfer Device	\$69.87	7A	3K	8X	View
Kitsap	Power Equipment Operators- Underground Sewer & Water	Mechanics, All (leadmen - \$0.50 Per Hour Over Mechanic)	\$71.20	7A	3K	8X	View
Kitsap	Power Equipment Operators- Underground Sewer & Water	Motor Patrol Graders	\$70.49	7A	3K	8X	View
Kitsap	Power Equipment Operators- Underground Sewer & Water	Mucking Machine, Mole, Tunnel Drill, Boring, Road Header And/or Shield	\$70.49	7A	3K	8X	View
Kitsap	Power Equipment Operators- Underground Sewer & Water	Oil Distributors, Blower Distribution & Mulch Seeding Operator	\$66.30	7A	3K	8X	View
Kitsap	Power Equipment Operators- Underground Sewer & Water	Outside Hoists (Elevators And Manlifts), Air Tuggers, Strato	\$69.33	7A	3K	8X	View
Kitsap	Power Equipment Operators- Underground Sewer & Water	Overhead, Bridge Type Crane: 20 Tons Through 44 Tons	\$69.87	7A	3K	8X	View

Kitsap	Power Equipment Operators-Underground Sewer & Water	Overhead, Bridge Type: 100 Tons And Over	\$71.20	7A	3K	8X	View
Kitsap	Power Equipment Operators-Underground Sewer & Water	Overhead, Bridge Type: 45 Tons Through 99 Tons	\$70.49	7A	3K	8X	View
Kitsap	Power Equipment Operators-Underground Sewer & Water	Pavement Breaker	\$66.30	7A	3K	8X	View
Kitsap	Power Equipment Operators-Underground Sewer & Water	Pile Driver (other Than Crane Mount)	\$69.87	7A	3K	8X	View
Kitsap	Power Equipment Operators-Underground Sewer & Water	Plant Oiler - Asphalt, Crusher	\$69.33	7A	3K	8X	View
Kitsap	Power Equipment Operators-Underground Sewer & Water	Posthole Digger, Mechanical	\$66.30	7A	3K	8X	View
Kitsap	Power Equipment Operators-Underground Sewer & Water	Power Plant	\$66.30	7A	3K	8X	View
Kitsap	Power Equipment Operators-Underground Sewer & Water	Pumps - Water	\$66.30	7A	3K	8X	View
Kitsap	Power Equipment Operators-Underground Sewer & Water	Quad 9, Hd 41, D10 And Over	\$70.49	7A	3K	8X	View
Kitsap	Power Equipment Operators-Underground Sewer & Water	Quick Tower - No Cab, Under 100 Feet In Height Based To Boom	\$66.30	7A	3K	8X	View
Kitsap	Power Equipment Operators-Underground Sewer & Water	Remote Control Operator On Rubber Tired Earth Moving Equipment	\$70.49	7A	3K	8X	View
Kitsap	Power Equipment Operators-Underground Sewer & Water	Rigger and Bellman	\$66.30	7A	3K	8X	View
Kitsap	Power Equipment Operators-Underground Sewer & Water	Rigger/Signal Person, Bellman (Certified)	\$69.33	7A	3K	8X	View
Kitsap	Power Equipment Operators-Underground Sewer & Water	Rollagon	\$70.49	7A	3K	8X	View
Kitsap	Power Equipment Operators-Underground Sewer & Water	Roller, Other Than Plant Mix	\$66.30	7A	3K	8X	View
Kitsap	Power Equipment Operators-Underground Sewer & Water	Roller, Plant Mix Or Multi-lift Materials	\$69.33	7A	3K	8X	View
Kitsap	Power Equipment Operators-Underground Sewer & Water	Roto-mill, Roto-grinder	\$69.87	7A	3K	8X	View
Kitsap	Power Equipment Operators-Underground Sewer & Water	Saws - Concrete	\$69.33	7A	3K	8X	View
Kitsap	Power Equipment Operators-Underground Sewer & Water	Scraper, Self Propelled Under 45 Yards	\$69.87	7A	3K	8X	View
Kitsap	Power Equipment Operators-Underground Sewer & Water	Scrapers - Concrete & Carry All	\$69.33	7A	3K	8X	View
Kitsap	Power Equipment Operators-Underground Sewer & Water	Scrapers, Self-propelled: 45 Yards And Over	\$70.49	7A	3K	8X	View
Kitsap	Power Equipment Operators-Underground Sewer & Water	Service Engineers - Equipment	\$69.33	7A	3K	8X	View
Kitsap	Power Equipment Operators-Underground Sewer & Water	Shotcrete/Gunite Equipment	\$66.30	7A	3K	8X	View
Kitsap	Power Equipment Operators-Underground Sewer & Water	Shovel, Excavator, Backhoe, Tractors Under 15 Metric Tons	\$69.33	7A	3K	8X	View
Kitsap	Power Equipment Operators-Underground Sewer & Water	Shovel, Excavator, Backhoe: Over 30 Metric Tons To 50 Metric Tons	\$70.49	7A	3K	8X	View

Kitsap	Power Equipment Operators-Underground Sewer & Water	Shovel, Excavator, Backhoes, Tractors: 15 To 30 Metric Tons	\$69.87	7A	3K	8X	View
Kitsap	Power Equipment Operators-Underground Sewer & Water	Shovel, Excavator, Backhoes: Over 50 Metric Tons To 90 Metric Tons	\$71.20	7A	3K	8X	View
Kitsap	Power Equipment Operators-Underground Sewer & Water	Shovel, Excavator, Backhoes: Over 90 Metric Tons	\$71.93	7A	3K	8X	View
Kitsap	Power Equipment Operators-Underground Sewer & Water	Slipform Pavers	\$70.49	7A	3K	8X	View
Kitsap	Power Equipment Operators-Underground Sewer & Water	Spreader, Topsider & Screedman	\$70.49	7A	3K	8X	View
Kitsap	Power Equipment Operators-Underground Sewer & Water	Subgrader Trimmer	\$69.87	7A	3K	8X	View
Kitsap	Power Equipment Operators-Underground Sewer & Water	Tower Bucket Elevators	\$69.33	7A	3K	8X	View
Kitsap	Power Equipment Operators-Underground Sewer & Water	Tower Crane Up To 175' In Height Base To Boom	\$71.20	7A	3K	8X	View
Kitsap	Power Equipment Operators-Underground Sewer & Water	Tower Crane: over 175' through 250' in height, base to boom	\$71.93	7A	3K	8X	View
Kitsap	Power Equipment Operators-Underground Sewer & Water	Tower Cranes: over 250' in height from base to boom	\$72.63	7A	3K	8X	View
Kitsap	Power Equipment Operators-Underground Sewer & Water	Transporters, All Track Or Truck Type	\$70.49	7A	3K	8X	View
Kitsap	Power Equipment Operators-Underground Sewer & Water	Trenching Machines	\$69.33	7A	3K	8X	View
Kitsap	Power Equipment Operators-Underground Sewer & Water	Truck Crane Oiler/driver - 100 Tons And Over	\$69.87	7A	3K	8X	View
Kitsap	Power Equipment Operators-Underground Sewer & Water	Truck Crane Oiler/Driver Under 100 Tons	\$69.33	7A	3K	8X	View
Kitsap	Power Equipment Operators-Underground Sewer & Water	Truck Mount Portable Conveyor	\$69.87	7A	3K	8X	View
Kitsap	Power Equipment Operators-Underground Sewer & Water	Welder	\$70.49	7A	3K	8X	View
Kitsap	Power Equipment Operators-Underground Sewer & Water	Wheel Tractors, Farmall Type	\$66.30	7A	3K	8X	View
Kitsap	Power Equipment Operators-Underground Sewer & Water	Yo Yo Pay Dozer	\$69.87	7A	3K	8X	View
Kitsap	Power Line Clearance Tree Trimmers	Journey Level In Charge	\$55.03	5A	4A		View
Kitsap	Power Line Clearance Tree Trimmers	Spray Person	\$52.24	5A	4A		View
Kitsap	Power Line Clearance Tree Trimmers	Tree Equipment Operator	\$55.03	5A	4A		View
Kitsap	Power Line Clearance Tree Trimmers	Tree Trimmer	\$49.21	5A	4A		View
Kitsap	Power Line Clearance Tree Trimmers	Tree Trimmer Groundperson	\$37.47	5A	4A		View
Kitsap	Refrigeration & Air Conditioning Mechanics	Journey Level	\$79.46	5A	1G		View
Kitsap	Residential Brick Mason	Journey Level	\$22.01		1		View
Kitsap	Residential Carpenters	Journey Level	\$26.25		1		View
Kitsap	Residential Cement Masons	Journey Level	\$39.88		1		View

Kitsap	Residential Drywall Applicators	Journey Level	\$48.17	<u>7A</u>	<u>4C</u>	View
Kitsap	Residential Drywall Tapers	Journey Level	\$25.84		<u>1</u>	View
Kitsap	Residential Electricians	Journey Level	\$44.11		<u>1</u>	View
Kitsap	Residential Glaziers	Journey Level	\$47.80	<u>7L</u>	<u>1H</u>	View
Kitsap	Residential Insulation Applicators	Journey Level	\$18.03		<u>1</u>	View
Kitsap	Residential Laborers	Journey Level	\$14.71		<u>1</u>	View
Kitsap	Residential Marble Setters	Journey Level	\$22.01		<u>1</u>	View
Kitsap	Residential Painters	Journey Level	\$20.85		<u>1</u>	View
Kitsap	Residential Plumbers & Pipefitters	Journey Level	\$35.92		<u>1</u>	View
Kitsap	Residential Refrigeration & Air Conditioning Mechanics	Journey Level	\$40.21		<u>1</u>	View
Kitsap	Residential Sheet Metal Workers	Journey Level	\$32.91		<u>1</u>	View
Kitsap	Residential Soft Floor Layers	Journey Level	\$22.03		<u>1</u>	View
Kitsap	Residential Sprinkler Fitters (Fire Protection)	Journey Level	\$31.53		<u>1</u>	View
Kitsap	Residential Stone Masons	Journey Level	\$60.57	<u>7E</u>	<u>1N</u>	View
Kitsap	Residential Terrazzo Workers	Journey Level	\$14.86		<u>1</u>	View
Kitsap	Residential Terrazzo/Tile Finishers	Journey Level	\$39.09		<u>1</u>	View
Kitsap	Residential Tile Setters	Journey Level	\$35.40		<u>1</u>	View
Kitsap	Roofers	Journey Level	\$57.30	<u>5A</u>	<u>3H</u>	View
Kitsap	Roofers	Using Irritable Bituminous Materials	\$60.30	<u>5A</u>	<u>3H</u>	View
Kitsap	Sheet Metal Workers	Journey Level (Field or Shop)	\$89.61	<u>7F</u>	<u>1E</u>	View
Kitsap	Shipbuilding & Ship Repair	New Construction Boilermaker	\$38.54	<u>7V</u>	<u>1</u>	View
Kitsap	Shipbuilding & Ship Repair	New Construction Carpenter	\$38.54	<u>7V</u>	<u>1</u>	View
Kitsap	Shipbuilding & Ship Repair	New Construction Crane Operator	\$38.54	<u>7V</u>	<u>1</u>	View
Kitsap	Shipbuilding & Ship Repair	New Construction Electrician	\$38.54	<u>7V</u>	<u>1</u>	View
Kitsap	Shipbuilding & Ship Repair	New Construction Heat & Frost Insulator	\$79.43	<u>5J</u>	<u>4H</u>	View
Kitsap	Shipbuilding & Ship Repair	New Construction Laborer	\$38.54	<u>7V</u>	<u>1</u>	View
Kitsap	Shipbuilding & Ship Repair	New Construction Machinist	\$38.54	<u>7V</u>	<u>1</u>	View
Kitsap	Shipbuilding & Ship Repair	New Construction Operating Engineer	\$38.54	<u>7V</u>	<u>1</u>	View
Kitsap	Shipbuilding & Ship Repair	New Construction Painter	\$38.54	<u>7V</u>	<u>1</u>	View
Kitsap	Shipbuilding & Ship Repair	New Construction Pipefitter	\$38.54	<u>7V</u>	<u>1</u>	View
Kitsap	Shipbuilding & Ship Repair	New Construction Rigger	\$38.54	<u>7V</u>	<u>1</u>	View
Kitsap	Shipbuilding & Ship Repair	New Construction Sheet Metal	\$38.54	<u>7V</u>	<u>1</u>	View
Kitsap	Shipbuilding & Ship Repair	New Construction Shipfitter	\$38.54	<u>7V</u>	<u>1</u>	View
Kitsap	Shipbuilding & Ship Repair	New Construction Warehouse/Teamster	\$38.54	<u>7V</u>	<u>1</u>	View
Kitsap	Shipbuilding & Ship Repair	New Construction Welder / Burner	\$38.54	<u>7V</u>	<u>1</u>	View
Kitsap	Shipbuilding & Ship Repair	Ship Repair Boilermaker	\$47.35	<u>7X</u>	<u>4J</u>	View
Kitsap	Shipbuilding & Ship Repair	Ship Repair Carpenter	\$47.35	<u>7X</u>	<u>4J</u>	View

Kitsap	Shipbuilding & Ship Repair	Ship Repair Crane Operator	\$45.06	7Y	4K		View
Kitsap	Shipbuilding & Ship Repair	Ship Repair Electrician	\$47.42	7X	4J		View
Kitsap	Shipbuilding & Ship Repair	Ship Repair Heat & Frost Insulator	\$79.43	5J	4H		View
Kitsap	Shipbuilding & Ship Repair	Ship Repair Laborer	\$47.35	7X	4J		View
Kitsap	Shipbuilding & Ship Repair	Ship Repair Machinist	\$47.35	7X	4J		View
Kitsap	Shipbuilding & Ship Repair	Ship Repair Operating Engineer	\$45.06	7Y	4K		View
Kitsap	Shipbuilding & Ship Repair	Ship Repair Painter	\$47.35	7X	4J		View
Kitsap	Shipbuilding & Ship Repair	Ship Repair Pipefitter	\$47.35	7X	4J		View
Kitsap	Shipbuilding & Ship Repair	Ship Repair Rigger	\$47.35	7X	4J		View
Kitsap	Shipbuilding & Ship Repair	Ship Repair Sheet Metal	\$47.35	7X	4J		View
Kitsap	Shipbuilding & Ship Repair	Ship Repair Shipwright	\$47.35	7X	4J		View
Kitsap	Shipbuilding & Ship Repair	Ship Repair Warehouse / Teamster	\$45.06	7Y	4K		View
Kitsap	Sign Makers & Installers (Electrical)	Journey Level	\$51.56	0	1		View
Kitsap	Sign Makers & Installers (Non-Electrical)	Journey Level	\$33.20	0	1		View
Kitsap	Soft Floor Layers	Journey Level	\$51.91	5A	3J		View
Kitsap	Solar Controls For Windows	Journey Level	\$13.69		1		View
Kitsap	Sprinkler Fitters (Fire Protection)	Journey Level	\$85.89	5C	1X		View
Kitsap	Stage Rigging Mechanics (Non Structural)	Journey Level	\$13.69		1		View
Kitsap	Stone Masons	Journey Level	\$60.57	7E	1N		View
Kitsap	Street And Parking Lot Sweeper Workers	Journey Level	\$16.00		1		View
Kitsap	Surveyors	Assistant Construction Site Surveyor	\$69.33	7A	3K	8X	View
Kitsap	Surveyors	Chainman	\$66.30	7A	3K	8X	View
Kitsap	Surveyors	Construction Site Surveyor	\$70.49	7A	3K	8X	View
Kitsap	Telecommunication Technicians	Journey Level	\$53.57	7E	1E		View
Kitsap	Telephone Line Construction - Outside	Cable Splicer	\$37.40	5A	2B		View
Kitsap	Telephone Line Construction - Outside	Hole Digger/Ground Person	\$25.04	5A	2B		View
Kitsap	Telephone Line Construction - Outside	Telephone Equipment Operator (Light)	\$31.22	5A	2B		View
Kitsap	Telephone Line Construction - Outside	Telephone Lineperson	\$35.34	5A	2B		View
Kitsap	Terrazzo Workers	Journey Level	\$55.71	7E	1N		View
Kitsap	Tile Setters	Journey Level	\$55.71	7E	1N		View
Kitsap	Tile, Marble & Terrazzo Finishers	Finisher	\$46.54	7E	1N		View
Kitsap	Traffic Control Stripers	Journey Level	\$49.13	7A	1K		View
Kitsap	Truck Drivers	Asphalt Mix Over 16 Yards	\$63.80	5D	4Y	8L	View
Kitsap	Truck Drivers	Asphalt Mix To 16 Yards	\$62.96	5D	4Y	8L	View
Kitsap	Truck Drivers	Dump Truck	\$62.96	5D	4Y	8L	View
Kitsap	Truck Drivers	Dump Truck & Trailer	\$63.80	5D	4Y	8L	View
Kitsap	Truck Drivers	Other Trucks	\$63.80	5D	4Y	8L	View

Kitsap	Truck Drivers - Ready Mix	Transit Mix	\$63.80	<u>5D</u>	<u>4Y</u>	<u>8L</u>	View
Kitsap	Well Drillers & Irrigation Pump Installers	Irrigation Pump Installer	\$13.69		<u>1</u>		View
Kitsap	Well Drillers & Irrigation Pump Installers	Oiler	\$14.08		<u>1</u>		View
Kitsap	Well Drillers & Irrigation Pump Installers	Well Driller	\$14.40		<u>1</u>		View

APPENDIX B

GEOTECHNICAL ENGINEERING REPORT

THIS PAGE INTENTIONALLY LEFT BLANK

Technical Memorandum

TO: Tony Fisher, PE, PMP, BHC Consultants, LLC
FROM: Benjamin Ford, PE, and Calvin McCaughan, PE
DATE: October 14, 2020
RE: **Geotechnical Engineering Services**
Pump Station 19 Upgrades
Silverdale, Washington
Project No. 1073031.010.011

Introduction

This memorandum summarizes the results of geotechnical engineering services provided by Landau Associates, Inc. (LAI) in support of proposed upgrades to Pump Station 19 (PS-19). The pump station is located approximately 50 feet (ft) northeast of Northwest Bucklin Hill Road and Nels Nelson Road Northwest in Silverdale, Washington (site; Figure 1). Geotechnical services were provided in accordance with the scope outlined in the Subconsultant Services Agreement between LAI and BHC Consultants, LLC (BHC; project civil engineer), effective December 18, 2020.

This memorandum has been prepared with information provided by representatives of BHC and the Kitsap County Wastewater Division (County; project owner), and with data collected during LAI's preliminary design study and field investigation.

Project Understanding

The County plans to replace outdated pumping equipment at PS-19 to satisfy current design standards. The existing control building will be demolished and replaced with a new building that will house check and isolation valves. Other proposed upgrades include the installation of slabs-on-grade and new piping. At the time of this writing, the County does not plan to increase the pumping capacity of PS-19; the existing wet well will be used to house new pumps. Excavations to accommodate tie-in to existing influent/effluent piping will extend approximately 10 ft below ground surface (bgs). Permeable concrete pavers will be used for the driveway. The proposed improvements are shown on Figure 2.

Site Conditions

The site consists of existing PS-19 and an access area, enclosed by a chain-link fence. A grassy field slopes gently down to an asphalt-paved access road that abuts the western boundary of the site. Leakage from a nearby stormwater pond may be contributing to wet conditions in this area of the site. To the east-southeast, site topography continues to slope downward at an approximately 8 percent grade. The site is bounded by Northwest Bucklin Hill Road to the south; a grove of coniferous and deciduous trees separates the site from Highway 303 to the northeast. Existing site features are shown on Figure 2.

Geologic Setting

Geologic information for the site and the surrounding area was obtained from the *Geologic Map of the Seabeck and Poulsbo 7.5-minute Quadrangles, Kitsap and Jefferson Counties, Washington* (Polenz et al. 2013). Surficial deposits in the vicinity of the site are mapped as Vashon lodgment till (Qgt), a mixture of clay, silt, sand, pebbles, cobbles, and isolated boulders. This highly compact unit is deposited and overridden by glacial ice. Lodgment till is typically unsorted and unstratified, and exhibits high shear strength and little to no permeability.

Vashon ice-contact deposits (Qgic), Vashon recessional glacial lake deposits (Qgof), and peat deposits (Qp) are also mapped in the vicinity of the site. Glacial ice-contact deposits have highly variable compositions, but tend to consist of loose to dense, poorly to well-sorted cobbles, gravel, sand, and silt. Discontinuous deposits of ablation, flow, and lodgment till are often observed in glacial ice-contact deposits. Recessional glacial lake deposits generally consist of loose to moderately stiff, moderately to well-sorted silt, sand, and clay. Peat deposits are often found in wetland areas, and include significant organics as well as muck, silt, and clay.

The soils observed in LAI's 2018 and 2020 explorations were consistent with the mapped geology for the site.

Subsurface Conditions

Site subsurface conditions were explored on February 20, 2020 by excavating one test pit (TP-1). County personnel used a vacuum excavator to advance the test pit 9.0 ft bgs. The approximate location of the exploration is shown on Figure 2.

The field exploration was coordinated and monitored by LAI personnel, who also obtained representative soil samples and maintained a detailed record of the subsurface soil and groundwater conditions observed. Each representative soil type was described using the soil classification system shown on Figure 3, in general accordance with ASTM International (ASTM) standard test method D2488, *Standard Practice for Description and Identification of Soils (Visual-Manual Procedures)*. Samples were collected at select intervals and transported to LAI's soils laboratory for further examination. A summary log of the subsurface conditions observed in test pit TP-1 is presented on Figure 4.

On April 18, 2018, LAI completed a field investigation adjacent to the site. During the investigation, LAI advanced a hollow-stem auger boring (B-2) 20.8 ft bgs. The approximate location of the exploration is shown on Figure 2. Subsurface data collected from boring B-2 (Attachment 1) have been used to complete the current study.

Soil and Groundwater Conditions

The soils observed underlying existing surface conditions (i.e., grass/sod) in test pit TP-1 and boring B-2 can be categorized into two general units:

- **Fill:** The fill observed in LAI's explorations extended approximately 5 ft bgs, and consisted of very gravelly to gravelly sand with varying silt content or very sandy gravel with silt. Occasional cobbles were encountered. The fill was in a loose to medium dense, moist to wet condition. Construction debris (i.e., sheet pile, corrugated pipe, concrete) was encountered within the fill in test pit TP-1.
- **Ice-contact deposits:** The ice-contact deposits observed in LAI's explorations consisted of sand with varying gravel and silt content. The ice-contact deposits were observed in a medium dense to very dense, wet condition. Both explorations terminated in this unit.



Photograph 1. Test pit TP-1 at 0 to 4 ft bgs

Boulders were not observed in the explorations, but are often present in glacial deposits, and may be encountered throughout the site. Cobbles should be anticipated in the fill and ice-contact deposits. Additionally, construction debris was observed in the fill. The contractor should be prepared to manage such materials.

During LAI's February 2020 field investigation, moderate groundwater seepage was observed at 2.8 ft bgs and groundwater at 5 ft bgs. The groundwater conditions reported herein are for the specific location and date indicated, and may not be representative of other locations and/or times. Groundwater conditions will vary depending on local subsurface conditions, weather conditions, and other factors. Furthermore, groundwater levels are expected to fluctuate seasonally, with maximum groundwater levels occurring during late winter and early spring.

Conclusions and Recommendations

Based on the results of LAI's geotechnical engineering services, the proposed improvements are feasible from a geotechnical standpoint. The fill and ice-contact deposits encountered in the explorations are anticipated to provide adequate support for the proposed improvements, provided the following recommendations are incorporated into the project plans and specifications:

- **Construction dewatering:** Site soils are water bearing, and the need for construction dewatering should be anticipated.
 - Excavations to accommodate tie-in to existing piping are expected to extend no more than 10 ft bgs; conventional dewatering methods, such as sumps and pumps, should be employed. Substantial pumping may be needed to dewater the excavations. Diversion ditches can be used to dewater excavations in areas of sufficient topographic relief.

Completing construction during the dry season (July through October) will help to limit dewatering efforts.

- **Unsuitable foundation material:** LAI recommends overexcavating soft/unsuitable foundation material. At least 2 ft of unsuitable material should be overexcavated beneath the base of structures that will be founded within 3 ft of ground surface, and 1 ft of material should be overexcavated beneath the base of structures that will be founded more than 3 ft bgs. Excavated material should be replaced with a structural fill bearing pad. One foot of overexcavation and replacement is recommended below slabs-on-grade and at the permeable pavement sub-base reservoir depth.
- **Oversized material:** Boulders and cobbles are typically present in glacially derived soils, and could be encountered throughout the site. Additionally, the construction debris (steel and concrete rubble) observed in test pit TP-1 could be present throughout the site. The contractor should be prepared to manage such oversized material.
- **Excavations:** Excavations may extend to a maximum depth of 10 ft bgs. LAI recommends using trench box or slide rail shoring systems in conjunction with dewatering methods that draw down groundwater. Sheet pile shoring systems are feasible, but installation could be obstructed by construction debris (abandoned shoring material observed in test pit TP-1), cobbles, and boulders.

Seismic Conditions

Seismic design will be completed using 2018 International Building Code standards (ICC 2017). The parameters listed in Table 1 can be used to compute seismic base shear forces.

Table 1. 2018 International Building Code Seismic Design Parameters

Spectral response acceleration at short periods (S_s) = 1.464g
Spectral response acceleration at 1-second periods (S_1) = 0.518g
Site class = C
Site coefficient (F_a) = 1.2
Site coefficient (F_v) = 1.482

g = force of gravity

Medium dense to very dense, glacially consolidated soil was observed in the explorations. In LAI's opinion, site soils have a low risk of seismically induced liquefaction or lateral spreading. Given the distance between the site and the nearest known active crustal faults, the risk of ground rupture due to surface faulting is low.

Foundation Support

The parameters in Table 2 can be used by the structural engineer to design shallow foundations. The parameters should be used in conjunction with the complete recommendations in this memorandum.

Table 2. Summary of Design Parameters

Allowable soil bearing pressure = 3,000 psf
Friction coefficient (factored) = 0.35
Passive resistance (factored) = 300 pcf, 140 pcf (buoyant) below 3 ft bgs
Minimum foundation width = 18 inches (continuous), 24 inches (isolated)
Maximum foundation width (for settlement considerations) = 5 ft (continuous), 10 ft (isolated)

bgs = below ground surface

ft = feet

pcf = pounds per cubic foot

psf = pounds per square foot

Loose to medium dense fill is likely to be exposed at the foundation elevation of the proposed building structure. Dense to very dense ice-contact deposits are anticipated at the foundation elevation of the overflow vault. To provide a firm working surface, LAI recommends overexcavating 2 ft of soil beneath the base of structures that will be founded within 3 ft of existing ground surface. One foot of soil should be overexcavated beneath the base of structures that will be founded more

than 3 ft bgs. Overexcavated material should be replaced with a structural fill bearing pad. The bearing pad should consist of Class A Foundation Material that conforms to the requirements in Section 9-03.12(1)A of the Washington State Department of Transportation's 2020 *Standard Specifications for Road, Bridge, and Municipal Construction (2020 WSDOT Standard Specifications)*.

LAI recommends a net allowable bearing pressure of 3,000 pounds per square foot (psf) for on-grade structures. This bearing pressure includes a factor of safety of at least 3.0 on the calculated ultimate bearing capacity. Less than ½ inch of total settlement is expected to occur as loads are applied. Post-construction settlement is expected to be negligible. The maximum allowable bearing pressure can be increased by one-third for transient loads, such as those induced by wind and seismic forces.

An allowable coefficient of sliding resistance of 0.35, applied to vertical dead loads only, can be used to compute frictional resistance acting on the base of footings. This friction coefficient includes a factor of safety of 1.5 on the calculated ultimate value. The passive resistance of properly compacted structural fill placed against the sides of foundations can be considered equivalent to a fluid with a density of 300 pounds per cubic foot (pcf). A buoyant value of 140 pcf should be used along segments of structures that extend more than 3 ft bgs. The foundation passive earth pressure has been reduced by a factor of 1.5 to limit deflections to less than 2 percent of the embedded depth. The passive earth pressure and friction components can be combined, provided the passive component does not exceed two-thirds of the total. The top foot of soil should be excluded from the calculation, unless the foundation perimeter is covered by slab-on-grade or pavement.

Lateral Earth Pressures

For below-grade walls (i.e., vault structures and manholes), LAI recommends a design groundwater elevation equal to the ground surface elevation. Below-grade walls are expected to be restrained against rotation during backfilling, and should be designed for an equivalent fluid unit weight of 90 pcf. This assumes level backfill and at-rest, undrained soil conditions.

Design of subsurface walls should include appropriate lateral pressures from adjacent surcharge loads. A uniformly distributed lateral pressure, equal to 0.44 times the surcharge pressure, should be added to non-yielding walls. Given their size, wet wells and vaults are expected to move with the ground during a seismic event, and unbalanced, dynamic lateral earth pressures need not be incorporated into the project design.

Uplift Resistance

Buried, tank-like structures, such as vaults or manholes, will experience an upward buoyant force when the groundwater level outside the structure is higher than the fluid level inside the structure. Sidewall soil friction and the weight of the structure will provide resistance against uplift forces caused by buoyancy. Extending the base of the vault foundation beyond its outside perimeter will also

increase uplift resistance. For the below-grade structures, LAI recommends a design groundwater elevation equal to the ground surface elevation (Figure 5).

If an extended base slab is used, the weight of the soil overlying the footing can be calculated with an effective wedge, as described in the Naval Facilities Engineering Command *Design Manual 7.02* (1986). Uplift should be calculated using a soil unit weight of 70 pcf for buoyant conditions.

Alternatively, sidewall soil friction between the outside of the structure and the surrounding backfill can be used to resist uplift forces. To calculate frictional resistance, LAI recommends using a lateral soil earth pressure of 30 pcf and a coefficient of friction ($\tan\delta$) of 0.35 for epoxy-coated structures, 0.57 for cast-in-place structures, and 0.45 for precast concrete structures.

Sidewall soil friction and extended base slabs are alternative methods for resisting uplift forces, and should not be used in conjunction.

Slabs-On-Grade

A 1-ft overexcavation and replacement with structural fill (Class A Foundation Material) is recommended below slabs-on-grade. A modulus of vertical subgrade reaction (subgrade modulus) can be used to design slabs-on-grade for new pump station structures and equipment pad foundations. The subgrade modulus will vary based on the dimensions of the slab and the magnitude of applied loads on the slab surface; slabs with larger dimensions and loads are affected by soils to a greater depth. To design slabs-on-grade, LAI recommends using a subgrade modulus of 150 pounds per cubic inch. This subgrade modulus is for a 1-ft by 1-ft square plate, and is not the overall modulus of a larger area.

Permeable Pavement System

Permeable concrete pavers will be used for the driveway. Soft subgrade conditions are anticipated, and LAI recommends that the open-graded subbase layer has a minimum depth of 1 ft. The subbase layer should consist of permeable ballast that conforms to the requirements in Section 9-03.9(2) of the *2020 WSDOT Standard Specifications*.

Construction Considerations

The following key points should be considered when developing project specifications:

- **Foundation bearing pads:** Moisture-sensitive and/or poorly graded soils are anticipated at the base of shallow foundations. To provide a firm working surface, LAI recommends overexcavating the soils and replacing with a bearing pad that consists of Class A Foundation Material. Class A Foundation Material should conform to the requirements in Section 9-03.12(1)A of the *2020 WSDOT Standard Specifications*. The overexcavation/bearing pad

should extend beyond the width of the foundation element (i.e., shallow foundation, slabs-on-grade).

- **Site soils:** Site soils have a high fines content, and are considered moisture sensitive. Earthwork should be avoided during heavy and/or extended periods of precipitation.
- **Subgrade preparation:** After vegetation has been stripped and the subgrade has been excavated to the proposed elevation, the upper 1 ft of subgrade should be scarified, moisture conditioned, and compacted to a firm, unyielding condition. Accessible subgrade areas should be proof-rolled in the presence of an experienced County representative. Areas of limited access can be evaluated with a steel T-probe. Soft/unsuitable subgrade, identified during proof-rolling or probing, should be overexcavated and replaced with structural fill.
- **Structural fill:** Imported structural fill should meet the requirements for Select Borrow in Section 9-03.14(2) of the *2020 WSDOT Standard Specifications*. If wet weather construction is anticipated, the amount of fines should be less than 5 percent by weight, based on the minus $\frac{3}{4}$ -inch fraction. Site soils should be used for structural fill only if adequate compaction can be achieved.
- **Structural fill placement and compaction:** Structural fill should be placed on an approved subgrade that consists of uniformly firm, unyielding, inorganic native soils or of compacted structural fill extending to such soils. Structural fill should be placed and compacted in accordance with Section 2-03.3(14)C, Method C of the *2020 WSDOT Standard Specifications*. Method A is appropriate for non-structural areas, such as landscaping. Each layer of structural fill should be compacted to at least 95 percent of the maximum dry density (MDD), determined in accordance with Section 2-03.3(14)D of the *2020 WSDOT Standard Specifications*. Alternatively, the MDD can be determined using ASTM standard test method D1557, *Standard Test Methods for Laboratory Compaction Characteristics of Soil Using Modified Effort* ($56,000 \text{ ft-lbf/ft}^3$ ($2,700 \text{ kN=m/m}^3$); i.e., modified Proctor).
- **Utility trench excavation and backfill:** LAI anticipates that utility trenches will be excavated in loose to medium dense fill or ice-contact deposits. A heavy-duty hydraulic excavator should be able to excavate trenches to the required depths. A smooth-bladed bucket should be used to remove loose and/or disturbed soil from the trench bottom. The final trench bottom should be firm and free of roots, topsoil, lumps of silt and clay, and organic and inorganic debris. Unsuitable soil should be overexcavated and replaced with suitable foundation material. Trench backfill above the pipe zone should be placed in loose, horizontal lifts, no more than 8 inches thick. The backfill should be compacted to at least 95 percent of the MDD, determined in accordance with the compaction control tests in Section 2-03.3(14)D of the *2020 WSDOT Standard Specifications*. Alternatively, the MDD can be determined using ASTM standard test method D1557 (i.e., modified Proctor).
- **Construction dewatering:** The stormwater pond at the western site boundary is a likely source of perched groundwater. Construction excavations may cross existing utility trenches that contain perched water. Temporary excavations should be dewatered to allow construction to be completed in the dry. Where groundwater is encountered, the use of sumps and pumps should be sufficient to dewater excavations 10 ft bgs or shallower. Topographic relief and nearby ditches could be used to drain shallow excavations via open channel.

More substantial dewatering systems will be required for excavations extending deeper than 10 ft bgs. Watertight shoring systems, well points, or deep wells will likely be required for excavations that extend beyond 10 ft bgs. The contractor should be responsible for the design, monitoring, and maintenance of any dewatering systems.

- Temporary excavations:** Temporary excavations should be completed in accordance with Section 2-09 of the *2020 WSDOT Standard Specifications*. Actual excavation trench configurations and the maintenance of safe working conditions, including temporary excavation stability, are the responsibilities of the contractor. Temporary excavations in excess of 4 ft should be shored or sloped in accordance with the requirements outlined in Safety Standards for Construction Work, Part N (Chapter 296-155 of the Washington Administrative Code). The soil likely to be exposed in the excavations should be considered Type C, with a maximum allowable excavation inclination of 1½ horizontal to 1 vertical. All applicable local, state, and federal safety codes should be followed. If excavation instability is detected, the contractor should flatten the side slopes or install temporary shoring. If groundwater seepage is present and the excavation is not properly dewatered, the soil may be prone to caving, channeling, and running. Temporary shoring systems should be designed in accordance with the parameters presented in Table 3. Where appropriate, hydrostatic pressure should be added to the values in Table 3.

Table 3. Recommended Soil Parameters for Design of Temporary Shoring

Soil Unit	Moist Unit Weight (pcf)	Submerged Unit Weight (pcf)	Cohesion (psf)	Internal Angle of Friction (degrees)
Fill	125	63	0	34
Ice contact	130	68	0	36

pcf = pounds per cubic foot

psf = pounds per square foot

Use of This Technical Memorandum

Landau Associates, Inc. (LAI) has prepared this technical memorandum for the exclusive use of BHC Consultants, LLC and its client, the Kitsap County Wastewater Division, for specific application to the Silverdale Pump Station 19 Upgrades project in Silverdale, Washington. No other party is entitled to rely on the information, conclusions, and recommendations included in this document without the express written consent of LAI. Reuse of the information, conclusions, and recommendations provided herein for extensions of the project or for any other project, without review and authorization by LAI, shall be at the user's sole risk. LAI warrants that, within the limitations of scope, schedule, and budget, its services have been provided in a manner consistent with that level of skill and care ordinarily exercised by members of the profession currently practicing in the same locality under similar conditions as this project. LAI makes no other warranty, either express or implied.

Closing

We trust that this memorandum provides you with the information needed to proceed. If you have questions or comments, or if we may be of further service, please contact the undersigned at (360) 791-3178.

LANDAU ASSOCIATES, INC.

Ben J Ford

Benjamin Ford, PE
Associate



Calvin McCaughan

Calvin McCaughan, PE
Principal

ALP/BJF/CAM/mcs




[Y:\1073\031.010\R\PS 19\FINAL\PS-19 UPGRADES GEOTECHNICAL REPORT 10.14.2020.DOCX]

Attachments: Figure 1. Vicinity Map
Figure 2. Site and Exploration Plan
Figure 3. Soil Classification System and Key
Figure 4. Log of Test Pit TP-1
Figure 5. Extended Base Buoyancy Calculation
Attachment 1. Subsurface Data for Historical Boring B-2

References

- ASTM. 2017. Annual Book of ASTM Standards. In: *Soil and Rock(I)*. West Conshohocken, PA: ASTM International.
- ICC. 2017. 2018 International Building Code. International Code Council. August 31.
- LAI. 2018. Draft Geotechnical Report: NW Bucklin Hill Road and Nels Nelson Road NW, Intersection Improvements. Landau Associates, Inc. May 11.
- LNI. 2016. Construction Work. Chapter 296-155 WAC; Part N. Excavation, Trenching, and Shoring. Washington State Department of Labor and Industries. May 20.
- NAVFAC. 1986. *Foundations & Earth Structures. Design Manual 7.02*. Naval Facilities Engineering Command. September 1.

- Polenz, M., G.T. Petro, T.A. Contreras, K.A. Stone, G.L. Paulin, and R. Cakir. 2013. *Geologic Map of the Seabeck and Poulsbo 7.5-minute Quadrangles, Kitsap and Jefferson Counties, Washington*. Washington Division of Geology and Earth Resources.
- WSDOT. 2019. *M41-10: Standard Specifications for Road, Bridge, and Municipal Construction*. 2020 Edition. Washington State Department of Transportation.



Data Source: Esri 2012


G:\Projects\1073\02\01\013\F01 VicMap (PS19).mxd 4/30/2018



Kitsap County
Pump Station 19 Upgrades
Silverdale, Washington

Vicinity Map

Figure
1



Soil Classification System

	MAJOR DIVISIONS		USCS GRAPHIC SYMBOL	LETTER SYMBOL ⁽¹⁾	TYPICAL DESCRIPTIONS ⁽²⁾⁽³⁾
COARSE-GRAINED SOIL (More than 50% of material is larger than No. 200 sieve size)	GRAVEL AND GRAVELLY SOIL (More than 50% of coarse fraction retained on No. 4 sieve)	CLEAN GRAVEL (Little or no fines)		GW	Well-graded gravel; gravel/sand mixture(s); little or no fines
		GRAVEL WITH FINES (Appreciable amount of fines)		GP	Poorly graded gravel; gravel/sand mixture(s); little or no fines
				GM	Silty gravel; gravel/sand/silt mixture(s)
	SAND AND SANDY SOIL (More than 50% of coarse fraction passed through No. 4 sieve)	CLEAN SAND (Little or no fines)		SW	Well-graded sand; gravelly sand; little or no fines
		SAND WITH FINES (Appreciable amount of fines)		SP	Poorly graded sand; gravelly sand; little or no fines
				SM	Silty sand; sand/silt mixture(s)
FINE-GRAINED SOIL (More than 50% of material is smaller than No. 200 sieve size)	SILT AND CLAY (Liquid limit less than 50)			SC	Clayey sand; sand/clay mixture(s)
				ML	Inorganic silt and very fine sand; rock flour; silty or clayey fine sand or clayey silt with slight plasticity
				CL	Inorganic clay of low to medium plasticity; gravelly clay; sandy clay; silty clay; lean clay
	SILT AND CLAY (Liquid limit greater than 50)			OL	Organic silt; organic, silty clay of low plasticity
				MH	Inorganic silt; micaceous or diatomaceous fine sand
				CH	Inorganic clay of high plasticity; fat clay
	HIGHLY ORGANIC SOIL			OH	Organic clay of medium to high plasticity; organic silt
				PT	Peat; humus; swamp soil with high organic content


OTHER MATERIALS	USCS GRAPHIC SYMBOL	LETTER SYMBOL	TYPICAL DESCRIPTIONS
PAVEMENT		AC or PC	Asphalt concrete pavement or Portland cement pavement
ROCK		RK	Rock (See Rock Classification)
WOOD		WD	Wood, lumber, wood chips
DEBRIS		DB	Construction debris, garbage

- Notes: 1. USCS letter symbols correspond to symbols used by the Unified Soil Classification System and ASTM classification methods. Dual letter symbols (e.g., SP-SM for sand or gravel) indicate soil with an estimated 5-15% fines. Multiple letter symbols (e.g., ML/CL) indicate borderline or multiple soil classifications.
2. Soil descriptions are based on the general approach presented in the Standard Practice for Description and Identification of Soils (Visual-Manual Procedure), outlined in ASTM D 2488. Where laboratory index testing has been conducted, soil classifications are based on the Standard Test Method for Classification of Soils for Engineering Purposes, as outlined in ASTM D 2487.
3. Soil description terminology is based on visual estimates (in the absence of laboratory test data) of the percentages of each soil type and is defined as follows:

Primary Constituent: > 50% - "GRAVEL," "SAND," "SILT," "CLAY," etc.
 Secondary Constituents: > 30% and ≤ 50% - "very gravelly," "very sandy," "very silty," etc.
 > 15% and ≤ 30% - "gravelly," "sandy," "silty," etc.
 Additional Constituents: > 5% and ≤ 15% - "with gravel," "with sand," "with silt," etc.
 ≤ 5% - "with trace gravel," "with trace sand," "with trace silt," etc., or not noted.

4. Soil density or consistency descriptions are based on judgement using a combination of sampler penetration blow counts, drilling or excavating conditions, field tests, and laboratory tests, as appropriate.

Drilling and Sampling Key			Field and Lab Test Data	
SAMPLER TYPE	SAMPLE NUMBER & INTERVAL		Code	Description
Code	Description			
a	3.25-inch O.D., 2.42-inch I.D. Split Spoon		PP = 1.0	Pocket Penetrometer, tsf
b	2.00-inch O.D., 1.50-inch I.D. Split Spoon		TV = 0.5	Torvane, tsf
c	Shelby Tube		PID = 100	Photoionization Detector VOC screening, ppm
d	Grab Sample		W = 10	Moisture Content, %
e	Single-Tube Core Barrel		D = 120	Dry Density, pcf
f	Double-Tube Core Barrel		-200 = 60	Material smaller than No. 200 sieve, %
g	2.50-inch O.D., 2.00-inch I.D. WSDOT		GS	Grain Size - See separate figure for data
h	3.00-inch O.D., 2.375-inch I.D. Mod. California		AL	Atterberg Limits - See separate figure for data
i	Other - See text if applicable		GT	Other Geotechnical Testing
1	300-lb Hammer, 30-inch Drop		CA	Chemical Analysis
2	140-lb Hammer, 30-inch Drop			
3	Pushed			
4	Vibrocore (Rotasonic/Geoprobe)			
5	Other - See text if applicable			



Sample Identification Number


Recovery Depth Interval


Sample Depth Interval

Portion of Sample Retained for Archive or Analysis

Groundwater	
	Approximate water level at time of drilling (ATD)
	Approximate water level at time after drilling/excavation/well

1073031.01 4/30/20 C:\USERS\MSK\IN\DESKTOP\1073031.010_PS 19.GPJ SINGLE TEST PIT LOG





Legend

W_T = Weight of structure plus weight of soil wedge. Use $\gamma_B = 70$ pounds per cubic foot for buoyant soil weight.

P = Buoyancy force

Factor of Safety = W_T/P

$\Delta = 20^\circ$

∇ = Design groundwater level

Source: Naval Facilities Engineering Command Design Manual 7.2 1986

Subsurface Data for Historical Boring B-2

Soil Classification System

	MAJOR DIVISIONS		USCS GRAPHIC SYMBOL	LETTER SYMBOL ⁽¹⁾	TYPICAL DESCRIPTIONS ⁽²⁾⁽³⁾
COARSE-GRAINED SOIL (More than 50% of material is larger than No. 200 sieve size)	GRAVEL AND GRAVELLY SOIL (More than 50% of coarse fraction retained on No. 4 sieve)	CLEAN GRAVEL (Little or no fines)		GW	Well-graded gravel; gravel/sand mixture(s); little or no fines
		GRAVEL WITH FINES (Appreciable amount of fines)		GP	Poorly graded gravel; gravel/sand mixture(s); little or no fines
				GM	Silty gravel; gravel/sand/silt mixture(s)
	SAND AND SANDY SOIL (More than 50% of coarse fraction passed through No. 4 sieve)	CLEAN SAND (Little or no fines)		GC	Clayey gravel; gravel/sand/clay mixture(s)
				SW	Well-graded sand; gravelly sand; little or no fines
		SAND WITH FINES (Appreciable amount of fines)		SP	Poorly graded sand; gravelly sand; little or no fines
				SM	Silty sand; sand/silt mixture(s)
FINE-GRAINED SOIL (More than 50% of material is smaller than No. 200 sieve size)	SILT AND CLAY (Liquid limit less than 50)			SC	Clayey sand; sand/clay mixture(s)
				ML	Inorganic silt and very fine sand; rock flour; silty or clayey fine sand or clayey silt with slight plasticity
				CL	Inorganic clay of low to medium plasticity; gravelly clay; sandy clay; silty clay; lean clay
	SILT AND CLAY (Liquid limit greater than 50)			OL	Organic silt; organic, silty clay of low plasticity
				MH	Inorganic silt; micaceous or diatomaceous fine sand
				CH	Inorganic clay of high plasticity; fat clay
	HIGHLY ORGANIC SOIL			OH	Organic clay of medium to high plasticity; organic silt
				PT	Peat; humus; swamp soil with high organic content


OTHER MATERIALS	GRAPHIC SYMBOL	LETTER SYMBOL	TYPICAL DESCRIPTIONS
PAVEMENT		AC or PC	Asphalt concrete pavement or Portland cement pavement
ROCK		RK	Rock (See Rock Classification)
WOOD		WD	Wood, lumber, wood chips
DEBRIS		DB	Construction debris, garbage

- Notes: 1. USCS letter symbols correspond to symbols used by the Unified Soil Classification System and ASTM classification methods. Dual letter symbols (e.g., SP-SM for sand or gravel) indicate soil with an estimated 5-15% fines. Multiple letter symbols (e.g., ML/CL) indicate borderline or multiple soil classifications.
2. Soil descriptions are based on the general approach presented in the Standard Practice for Description and Identification of Soils (Visual-Manual Procedure), outlined in ASTM D 2488. Where laboratory index testing has been conducted, soil classifications are based on the Standard Test Method for Classification of Soils for Engineering Purposes, as outlined in ASTM D 2487.
3. Soil description terminology is based on visual estimates (in the absence of laboratory test data) of the percentages of each soil type and is defined as follows:

Primary Constituent: > 50% - "GRAVEL," "SAND," "SILT," "CLAY," etc.
 Secondary Constituents: > 30% and ≤ 50% - "very gravelly," "very sandy," "very silty," etc.
 > 15% and ≤ 30% - "gravelly," "sandy," "silty," etc.
 Additional Constituents: > 5% and ≤ 15% - "with gravel," "with sand," "with silt," etc.
 ≤ 5% - "with trace gravel," "with trace sand," "with trace silt," etc., or not noted.

4. Soil density or consistency descriptions are based on judgement using a combination of sampler penetration blow counts, drilling or excavating conditions, field tests, and laboratory tests, as appropriate.

Drilling and Sampling Key			Field and Lab Test Data	
SAMPLER TYPE	SAMPLE NUMBER & INTERVAL		Code	Description
Code	Description			
a	3.25-inch O.D., 2.42-inch I.D. Split Spoon		PP = 1.0	Pocket Penetrometer, tsf
b	2.00-inch O.D., 1.50-inch I.D. Split Spoon		TV = 0.5	Torvane, tsf
c	Shelby Tube		PID = 100	Photoionization Detector VOC screening, ppm
d	Grab Sample		W = 10	Moisture Content, %
e	Single-Tube Core Barrel		D = 120	Dry Density, pcf
f	Double-Tube Core Barrel		-200 = 60	Material smaller than No. 200 sieve, %
g	2.50-inch O.D., 2.00-inch I.D. WSDOT		GS	Grain Size - See separate figure for data
h	3.00-inch O.D., 2.375-inch I.D. Mod. California		AL	Atterberg Limits - See separate figure for data
i	Other - See text if applicable		GT	Other Geotechnical Testing
1	300-lb Hammer, 30-inch Drop		CA	Chemical Analysis
2	140-lb Hammer, 30-inch Drop			
3	Pushed			
4	Vibrocore (Rotasonic/Geoprobe)			
5	Other - See text if applicable			



Sample Identification Number

Recovery Depth Interval

Sample Depth Interval

Portion of Sample Retained for Archive or Analysis

Groundwater	
	Approximate water level at time of drilling (ATD)
	Approximate water level at time other than ATD


B-2

LAI Project No: 0640030.010

SAMPLE DATA

SOIL PROFILE

Groundwater



Depth (ft)	Elevation (ft)	Sample Number & Interval	Sampler Type	Blows/Foot	Test Data	Graphic Symbol	USCS Symbol	Drilling Method: Hollow-Stem Auger
0	95						AC	Ground Elevation (ft): 95
							GP-GM	Drilled By: Holocene Drilling, Inc.
							GP	Logged By: BJF Date: 04/18/18
		S-1	b2	13				3 inches of asphalt over 9 inches of gravel base
								(ASPHALT)
		S-2	b2	12				Brown, sandy, fine to coarse GRAVEL with silt (medium dense, moist)
								(FILL)
		S-3	b2	69	W = 11 GS		SM	Brown-gray, sandy, fine to coarse GRAVEL (medium dense, moist)
								(ICE CONTACT)
		S-4	b2	50/5"				-Grades to wet
								Gray, very silty, fine to coarse SAND with gravel (very dense, wet)
		S-5	b2	43				-Grades to moist
								-Grades to dense
		S-6	b2	50/4"				-Grades to very dense

Boring Completed 04/18/18
Total Depth of Boring = 20.8 ft.

- Notes:
1. Stratigraphic contacts are based on field interpretations and are approximate.
 2. Reference to the text of this report is necessary for a proper understanding of subsurface conditions.
 3. Refer to "Soil Classification System and Key" figure for explanation of graphics and symbols.

640030.01 5/24/18 Y:\0640030.01\010640030.010\11.GPJ SOIL BORING LOG WITH GRAPH



Cobbles	Gravel		Sand			Silt or Clay
	Coarse	Fine	Coarse	Medium	Fine	

Symbol	Exploration Number	Sample Number	Depth (ft)	Natural Moisture (%)	Soil Description	Unified Soil Classification
●	B-1	S-5	12.5	8	Very silty, gravelly, fine to coarse SAND	SM
⊠	B-2	S-3	8.0	11	Very silty, fine to coarse SAND with gravel	SM
▲	B-4	S-1	3.0	6	Very gravelly, fine to coarse SAND with silt	SP-SM
★	B-4	S-7	15.5	12	Very gravelly, fine to coarse SAND with silt	SP-SM
⊙	B-5	S-5	10.0	21	Fine to coarse SAND with silt	SP-SM

Technical Memorandum

TO: Tony Fisher, PE, PMP, BHC Consultants, LLC
FROM: Benjamin Ford, PE, and Calvin McCaughan, PE
DATE: October 14, 2020
RE: **Geotechnical Engineering Services**
Pump Station 31 Upgrades
Silverdale, Washington
Project No. 1073031.010.018

Introduction

This memorandum summarizes the results of geotechnical engineering services provided by Landau Associates, Inc. (LAI) in support of proposed upgrades to Pump Station 31 (PS-31). The pump station is located near Northeast Clover Blossom Lane in Silverdale, Washington (site; Figure 1). Geotechnical services were provided in accordance with the scope outlined in the Subconsultant Services Agreement between LAI and BHC Consultants, LLC (BHC; project civil engineer), effective December 18, 2020.

This memorandum has been prepared with information provided by representatives of BHC and the Kitsap County Wastewater Division (County; project owner), and with data collected during LAI's preliminary design study and field investigation.

Project Understanding

The County plans to replace outdated pumping equipment at PS-31 to satisfy current design standards. Proposed upgrades include the addition of new retaining walls, electrical and control equipment, a wet well, a valve vault, yard piping, and a force main. The force main will extend approximately 100 feet (ft) south of existing PS-31, along Northeast Clover Blossom Lane. The new wet well will consist of a pre-manufactured pump station structure with an estimated diameter of 9 ft and a depth of 18 ft. The wet well excavation is anticipated to extend 20 ft below ground surface (bgs); the valve vault excavation will likely extend 10 ft bgs. The proposed retaining walls will have a maximum exposed height of approximately 4 ft. The proposed improvements are shown on Figure 2.

Site Conditions

The site is located in a residential neighborhood, and enclosed with a chain-link fence. PS-31 is surfaced with crushed rock, bare soil, and sparse grass. To the north and west, the site is bounded by coniferous and deciduous trees with an understory of vegetation common to the area. Northeast Clover Blossom Lane borders the site to the southeast. The outlet of a storm drain culvert is located near the southeast corner of PS-31. Ground surface settlement/erosion has occurred at the outlet. Site topography is shown on Figure 2.

Geologic Setting

Geologic information for the site and the surrounding area was obtained from the *Geologic Map of the Suquamish 7.5-minute Quadrangle and Part of the Seattle North 7.5'x 15' Quadrangle, Kitsap County, Washington* (Haugerud et al. 2011). Surficial deposits in the vicinity of the site are mapped as Vashon till (Qvt), a material composed of clay, silt, sand, pebbles, cobbles, and isolated boulders. Additionally, Vashon Drift Esperance Sand (Qve) is mapped near the site. This material typically consists of sand with minor gravel or silt in a loose condition.

The soils observed in LAI's 2019 and 2020 explorations were generally consistent with the mapped geology for the site.

Subsurface Conditions

Site subsurface conditions were explored on March 8, 2019 by advancing one hollow-stem auger boring (B-1), and on February 20, 2020 by excavating one test pit exploration (TP-1). Holocene Drilling, Inc., subcontracted by LAI, used a track-mounted drill rig to advance boring B-1 31.5 ft bgs. County personnel used a vacuum excavator to advance test pit TP-1 7.0 ft bgs. The approximate locations of the explorations are shown on Figure 2.

The field investigation was coordinated and monitored by LAI personnel, who also obtained representative soil samples and maintained a detailed record of the subsurface soil and groundwater conditions observed. Each representative soil type was described using the soil classification system shown on Figure 3, in general accordance with ASTM International (ASTM) standard test method D2488, *Standard Practice for Description and Identification of Soils (Visual-Manual Procedures)*. Summary logs of the explorations are presented on Figures 4 and 5. The stratigraphic contacts shown on the logs represent the approximate boundaries between soil types; actual transitions may be more gradual.

Disturbed soil samples were obtained from boring B-1 at frequent intervals using a 1.5-inch-inside-diameter, standard-penetration test split-spoon sampler. A 140-pound automatic hammer, falling a distance of approximately 30 inches, was used to drive the sampler 18 inches (or a portion thereof) into the undisturbed soil. The number of blows required to drive the sampler the final 12 inches (or a portion thereof) of soil penetration is noted on the boring log, adjacent to the appropriate sample notation. Disturbed grab samples were collected from test pit TP-1 at intervals selected by LAI. Samples were transported to LAI's soils laboratory for further examination and testing.

Upon completion of fieldwork, the borehole was decommissioned in general accordance with Washington Administrative Code (WAC) 173-160.

To facilitate soil classification, natural moisture content determinations and grain size analyses were performed on select samples. Natural moisture content is shown as $W = xx$ (i.e., percentage of dry weight) in the “Test Data” column on Figures 4 and 5. Samples selected for grain size analysis are designated with a “GS.” The results of the grain size analyses are presented on Figures 6 through 8.

Soil Conditions

The soils observed underlying existing surface conditions (i.e., topsoil) were categorized into one general unit:

- **Esperance sand:** At the locations explored, the Esperance sand typically consisted of moist to wet, medium dense to very dense sand with occasional cobbles and gravel and variable silt content, or of very sandy silt. Esperance sand in the upper 5 to 10 ft of the explorations was in a medium dense condition, and transitioned to dense to very dense. In boring B-1, mottling was observed at approximately 13 ft bgs. Both explorations terminated in this unit.

Cobbles were observed in LAI’s explorations, and could be present throughout the site. The contractor should be prepared to manage oversized material.

Groundwater Conditions

During the March 2019 field investigation, perched groundwater was observed between 4.5 and 16 ft bgs. Groundwater seepage was observed at 3.0 and 5.0 ft bgs in the February 2020 exploration. The groundwater conditions reported herein are for the specific locations and dates indicated, and may not be representative of other locations and/or times. Groundwater conditions will vary depending on local subsurface conditions, weather conditions, and other factors. Groundwater levels in the project area are expected to fluctuate seasonally, with maximum groundwater levels occurring during late winter and early spring.

Conclusions and Recommendations

Based on the results of LAI’s geotechnical engineering services, subsurface conditions at the site are suitable for the proposed improvements, provided the following recommendations are incorporated into the project design:

- **Construction dewatering:** Site soils are water bearing, and the need for construction dewatering should be anticipated. The contractor should be prepared to control inflow from perched groundwater layers within permeable zones of Esperance sand. If conventional dewatering methods, such as sumps and pumps, are not sufficient to dewater excavations, more substantial methods, such as watertight shoring or well points, may be required.
- **Site soil:** Site soils have a high fines content, and should be considered moisture sensitive. Earthwork should be avoided during heavy and/or extended precipitation events. If reused as structural fill, site soils should be moisture conditioned and screened for constituents greater than 6 inches in diameter.

- **Foundation bearing pads:** Moisture-sensitive and/or poorly graded soils are anticipated at the base of foundation excavations. To provide a firm working surface, LAI recommends overexcavating moisture-sensitive soil and replacing with a structural fill bearing pad. The bearing pad should extend within the limits of the excavation.
- **Buoyancy and uplift:** Below-grade structures (e.g., wet well) will experience an upward buoyant force when groundwater levels outside the structures exceed the fluid levels inside the structures. These structures should be designed to resist uplift from buoyant forces.
- **Oversized material:** Cobbles and boulders are often found in glacial soil deposits, and could be present throughout the site. The contractor should be prepared to handle oversized material encountered within the excavations.
- **Storm drain culvert extension:** LAI recommends that the existing storm drain culvert and outlet are extended beyond PS-31 to limit ground surface settlement/erosion.

Seismic Conditions

Seismic design will be completed using 2018 International Building Code standards (ICC 2017). The parameters listed in Table 1 can be used to compute seismic base shear forces.

Table 1. 2018 International Building Code Seismic Design Parameters

Spectral response acceleration at short periods (S_s) = 1.51g
Spectral response acceleration at 1-second periods (S_1) = 0.533g
Site class = D
Site coefficient (F_a) = 1.0
Site coefficient (F_v) = Site-specific analysis or exception ^(a)

(a) A site-specific ground motion analysis (Chapter 21 of American Society of Civil Engineers 7-16) is required for Site Class D structures with S_1 values greater than or equal to 0.2g. Alternatively, an Equivalent Lateral Force design (or Modal Response Spectrum Analysis), without a site-specific ground motion analysis, is permitted, provided the value of the seismic response coefficient (C_s) is determined using Eq. (12.8-2) for values of $T \leq 1.5T_s$, and taken as equal to 1.5 times the value calculated in accordance with either Eq. (12.8-3) for $T_L \geq T > 1.5T_s$ or Eq. (12.8-4) for $T > T_L$.

F_a , F_v = acceleration (0.2-second period) and velocity (1.0-second period) site coefficients, respectively

g = force of gravity

S_s , S_1 = 0.2-second and 1.0-second period spectral accelerations, respectively

Medium dense to very dense, glacially consolidated soil was observed in boring B-1. In LAI's opinion, site soils have a low risk of seismically induced liquefaction or lateral spreading. Given the distance between the site and the nearest known active crustal faults, the risk of ground rupture due to surface faulting is low.

Foundation Support

The parameters in Table 2 can be used by the structural engineer to design shallow foundations. The parameters should be used in conjunction with the complete recommendations in this memorandum.

Table 2. Summary of Design Parameters

Allowable soil bearing pressure = 3,000 psf
Friction coefficient (factored) = 0.35
Passive resistance (factored) = 300 pcf shallower than 5 ft bgs, 140 pcf (buoyant) below 5 ft bgs
Minimum foundation width = 18 inches (continuous), 24 inches (isolated)
Maximum foundation width (for settlement considerations) = 5 ft (continuous), 10 ft (isolated)

bgs = below ground surface

ft = feet

pcf = pounds per cubic foot

psf = pounds per square foot

Medium dense to very dense Esperance sand is likely to be exposed at the foundation elevation of the proposed structures. Native soils should provide adequate foundation support for on-grade and underground structures, provided the foundation soil remains in a relatively undisturbed condition, and excavations are properly dewatered.

Installation of underground structures is anticipated to result in a zero net increase in bearing pressure. LAI recommends a net allowable bearing pressure of 3,000 pounds per square foot (psf) for on-grade structures. This bearing pressure includes a factor of safety of at least 3.0 on the calculated ultimate bearing capacity. Less than ½ inch of total settlement is expected to occur as loads are applied. Post-construction settlement is expected to be negligible. The maximum allowable bearing pressure can be increased by one-third for transient loads, such as those induced by wind and seismic forces.

An allowable coefficient of sliding resistance of 0.35, applied to vertical dead load only, can be used to compute frictional resistance acting on the base of footings. This friction coefficient includes a factor of safety of 1.5 on the calculated ultimate value. The passive resistance of properly compacted structural fill placed against the sides of the foundations can be considered equivalent to a fluid with a density of 300 pounds per cubic foot (pcf). A buoyant value of 140 pcf should be used along segments of structures that extend more than 5 ft bgs. The foundation passive earth pressure has been reduced by a factor of 1.5 to limit deflections to less than 2 percent of the embedded depth. The passive earth pressure and friction components can be combined, provided the passive component does not exceed two-thirds of the total. The top foot of soil should be excluded from the calculation, unless the foundation perimeter is covered by a slab-on-grade or pavement.

Lateral Earth Pressures

The lateral earth pressures presented in Tables 3 and 4 should be used in conjunction with the complete recommendations in this memorandum.

Table 3. Lateral Earth Pressure Design Parameters for Below-Grade Structures

Parameter	Value
At-rest earth pressure (undrained)	90 pcf
At-rest surcharge coefficient	0.44

pcf = pounds per cubic foot

For below-grade walls (i.e., wet well and valve vault walls), LAI recommends a design groundwater elevation equal to the ground surface elevation. Below-grade walls are expected to be restrained from rotating during backfilling, and should be designed for an equivalent fluid unit weight of 90 pcf. These recommendations are based on the assumption that backfill is level and soil conditions are at-rest and undrained.

Design of below-grade walls should include appropriate lateral pressures from adjacent surcharge loads. A uniformly distributed lateral pressure, equal to 0.44 times the surcharge pressure, should be added to non-yielding walls. Given their size, wet wells and vaults are expected to move with the ground during a seismic event, and dynamic lateral earth pressures need not be incorporated into the wall design.

Table 4. Lateral Earth Pressure Design Parameters for Site Retaining Walls

Parameter	Value
At-rest earth pressure (drained)	55 pcf
Active earth pressure (drained)	35 pcf
At-rest surcharge coefficient	0.44
Active surcharge coefficient	0.28

pcf = pounds per cubic foot

Retaining wall design should account for lateral pressures from adjacent surcharge loads. Design of yielding walls should include a uniformly distributed lateral pressure, 0.28 times the uniform surcharge pressure; design of non-yielding walls should include a uniformly distributed lateral pressure, 0.44 times the uniform surcharge pressure.

Wall drainage systems should be installed to collect water and prevent buildup of hydrostatic pressure. A zone of free-draining backfill, at least 18 inches wide, should be included at the back of walls. Free-draining backfill should meet the requirements for Gravel Backfill for Walls in

Section 9-03.12(2) of the Washington State Department of Transportation's 2020 *Standard Specifications for Road, Bridge, and Municipal Construction (2020 WSDOT Standard Specifications)*. The free-draining backfill zone should extend from the base of the wall to within 1 ft of the top of the wall.

When preparing parameters for wall design, LAI assumed that backfill within the structural excavation zone would consist of Select Borrow conforming to the requirements in Section 9-03.14(2) of the 2020 *WSDOT Standard Specifications*. LAI also assumed that the Select Borrow would be compacted to at least 95 percent of its maximum dry density.

Uplift Resistance

A buried, tank-like structure, such as the proposed wet well, will experience an upward buoyant force when the groundwater level outside the structure is higher than the fluid level inside the structure. Sidewall soil friction and the weight of the structure will provide resistance against uplift forces caused by buoyancy. Extending the base of the vault foundation beyond its outside perimeter will also increase the uplift resistance of the structure. LAI recommends a design groundwater elevation equal to the ground surface elevation (Figure 9).

If an extended base slab is used, the weight of the soil overlying the footing can be calculated using an effective wedge, as described in the Naval Facilities Engineering Command *Design Manual 7.02* (1986). Uplift should be calculated using a soil unit weight of 70 pcf for buoyant conditions.

Alternatively, sidewall soil friction between the outside of the structure and the surrounding backfill can be used to resist uplift forces. To calculate frictional resistance, LAI recommends using a lateral soil earth pressure of 30 pcf and a coefficient of friction ($\tan\delta$) of 0.57 for cast-in-place structures and 0.45 for precast concrete structures.

Sidewall soil friction and extended base slabs are alternative methods for resisting uplift forces, and should not be used in combination.

Slabs-on-Grade

A modulus of vertical subgrade reaction (subgrade modulus) can be used to design slabs-on-grade for new pump station structures and electrical pad foundations. The subgrade modulus will vary based on the dimensions of the slab and the magnitude of applied loads on the slab surface; slabs with larger dimensions and loads are affected by soils to a greater depth. To design slabs-on-grade, LAI recommends using a subgrade modulus of 150 pounds per cubic inch. This subgrade modulus is for a 1-ft by 1-ft square plate, and is not the overall modulus of a larger area.

Construction Considerations

The following key points should be considered when developing project specifications:

- **Site soils:** Site soils have a high fines content, and are considered moisture sensitive. Earthwork should be avoided during heavy and/or extended periods of precipitation. If reused as structural fill, site soils should be moisture conditioned and screened for constituents greater than 6 inches in diameter. Site soils should be reused only during periods of warm, dry weather.
- **Subgrade preparation:** After vegetation has been stripped and subgrade has been excavated to the proposed elevation, the upper 1 ft of subgrade should be scarified, moisture conditioned, and compacted to a firm, unyielding condition. Accessible subgrade areas should be proof-rolled in the presence of a qualified inspector. Areas of limited access can be evaluated with a steel T-probe. Soft/unsuitable subgrade, identified during proof-rolling or probing, should be overexcavated and replaced with structural fill.
- **Construction dewatering:** The perched groundwater observed between 3.0 and 16 ft bgs should be managed with construction dewatering. Construction excavations may cross existing utility trenches that contain perched water. Temporary excavations should be dewatered to allow construction to be completed in the dry. Conventional sumps and pumps should be sufficient to dewater excavations with minor groundwater seepage.

More substantial dewatering systems, such as well points or watertight shoring systems (i.e., sheet piles), may be required for installation of the wet well. The contractor should be responsible for the design, monitoring, and maintenance of any dewatering systems.

- **Foundation bearing pads:** Moisture-sensitive and/or poorly graded soils are anticipated at the base of shallow foundations. To provide a firm working surface, LAI recommends overexcavating the soils by at least 1 ft, and replacing with a bearing pad that consists of Class A Foundation Material. Class A Foundation Material should conform to the requirements in Section 9-03.12(1)A of the *2020 WSDOT Standard Specifications*. The overexcavation/bearing pad should extend 1 ft beyond the edge of the foundation element (i.e., shallow foundation, slabs-on-grade).
- **Structural fill:** Imported structural fill should meet the requirements for Select Borrow in Section 9-03.14(2) of the *2020 WSDOT Standard Specifications*. If wet weather construction is anticipated, the amount of fines should be less than 5 percent by weight, based on the minus $\frac{3}{4}$ -inch fraction. Site soils should be used for structural fill only if adequate compaction can be achieved.
- **Structural fill placement and compaction:** Structural fill should be placed on an approved subgrade that consists of uniformly firm, unyielding, inorganic native soils or of compacted structural fill extending to such soils. Structural fill should be placed and compacted in accordance with Section 2-03.3(14)C, Method C of the *2020 WSDOT Standard Specifications*. Method A is appropriate for non-structural areas, such as landscaping. Each layer of structural fill should be compacted to at least 95 percent of the maximum dry density, determined in accordance with the compaction control tests in Section 2-03.3(14)D of the *2020 WSDOT Standard Specifications*. Alternatively, the maximum dry density can be determined using ASTM standard test method D1557, *Standard Test Methods for Laboratory Compaction*

Characteristics of Soil Using Modified Effort (56,000 ft-lbf/ft³ (2,700 kN=m/m³), i.e., modified Proctor).

- Utility trench excavation and backfill:** LAI anticipates that utility trenches will be excavated in loose to medium dense fill or Esperance sand. A heavy-duty hydraulic excavator should be able to excavate trenches to the required depths. A smooth-bladed bucket should be used to remove loose and/or disturbed soil from the trench bottom. The final trench bottom should be firm and free of roots, topsoil, lumps of silt and clay, and organic and inorganic debris. Unsuitable soil should be overexcavated and replaced with suitable foundation material. Trench backfill above the pipe zone should be placed in loose, horizontal lifts, no more than 8 inches thick. The backfill should be compacted to at least 95 percent of the maximum dry density, determined in accordance with Section 2-03.3(14)D of the *2020 WSDOT Standard Specifications*. Alternatively, the maximum dry density can be determined using ASTM standard test method D1557, i.e., modified Proctor.
- Temporary excavations:** Temporary excavations should be completed in accordance with Section 2-09 of the *2020 WSDOT Standard Specifications*. Actual excavation trench configurations and the maintenance of safe working conditions, including temporary excavation stability, are the responsibilities of the contractor. Temporary excavations in excess of 4 ft should be shored or sloped in accordance with the requirements outlined in Safety Standards for Construction Work, Part N (Chapter 296-155 WAC). The soil likely to be exposed in the excavations should be considered Type C, with a maximum allowable excavation inclination of 1½ horizontal to 1 vertical. All applicable local, state, and federal safety codes should be followed. If excavation instability is detected, the contractor should flatten the side slopes or install temporary shoring. If groundwater seepage is present and the excavation is not properly dewatered, the soil may be prone to caving, channeling, and running.

The site is located in a relatively rural area, and open cutting (with dewatering) will likely be used to install the wet well. A steel casing may be placed in an open-cut or an open-drilled excavation to provide temporary shoring. Temporary shoring systems should be designed in accordance with the soil parameters presented in Table 5.

Table 5. Recommended Soil Parameters for Design of Temporary Shoring

Soil Unit	Moist Unit Weight (pcf)	Submerged Unit Weight (pcf)	Cohesion (psf)	Internal Angle of Friction (degrees)
Esperance Sand	130	68	0	36

pcf = pounds per cubic foot

psf = pounds per square foot

Use of This Technical Memorandum

Landau Associates, Inc. (LAI) has prepared this technical memorandum for the exclusive use of BHC Consultants, LLC and its client, the Kitsap County Wastewater Division, for specific application to the Silverdale Pump Station 31 Upgrades project in Silverdale, Washington. No other party is entitled to rely on the information, conclusions, and recommendations included in this document without the express written consent of LAI. Reuse of the information, conclusions, and recommendations provided herein for extensions of the project or for any other project, without review and authorization by LAI, shall be at the user's sole risk. LAI warrants that, within the limitations of scope, schedule, and budget, its services have been provided in a manner consistent with that level of skill and care ordinarily exercised by members of the profession currently practicing in the same locality under similar conditions as this project. LAI makes no other warranty, either express or implied.

Closing

We trust that this assessment provides you with the information needed to proceed. If you have questions or comments, or if we may be of further service, please contact the undersigned at (360) 791-3178.

LANDAU ASSOCIATES, INC.

Benjamin Ford, PE
Associate

Calvin McCaughan, PE
Principal




ALP/BJF/CAM/mcs

[Y:\1073\031 010\R\PS 31\PS 31 UPGRADES TECHNICAL MEMORANDUM 10 14 2020_TEXT.DOCX]


Attachments: Figure 1. Vicinity Map
Figure 2. Site and Exploration Plan
Figure 3. Soil Classification System and Key
Figure 4. Log of Boring B-1
Figure 5. Log of Test Pit TP-1
Figure 6–8. Grain Size Distribution
Figure 9. Extended Base Buoyancy Calculation

References

- ASTM. 2003. D420-D5876: Annual Book of ASTM Standards. In: *Soil and Rock(I)*. West Conshohocken, PA: ASTM International.
- Haugerud, R.A., and K.G. Troost. 2011. *Geologic Map of the Suquamish 7.5-minute Quadrangle and Part of the Seattle North 7.5' x 15' Quadrangle, Kitsap County, Washington*. U.S. Geological Survey, Scientific Investigations.
- ICC. 2017. 2018 International Building Code. International Code Council. August 31.
- LNI. 2016. Construction Work. Chapter 296-155 WAC; Part N. Excavation, Trenching, and Shoring. Washington State Department of Labor and Industries. May 20.
- NAVFAC. 1986. *Foundations & Earth Structures. Design Manual 7.02*. Naval Facilities Engineering Command. September 1.
- WSDOT. 2019. *Standard Specifications for Road, Bridge, and Municipal Construction*. 2020 Edition. Publication No. M 41-10. Washington State Department of Transportation. September 1.



G:\Projects\1073\02\010\014\F01 VicMap (PS31).mxd 4/30/2018




Data Source: Esri 2012



Kitsap County
Pump Station 31 Upgrades
Silverdale, Washington

Vicinity Map

Figure
1



Soil Classification System

	MAJOR DIVISIONS		USCS GRAPHIC SYMBOL	LETTER SYMBOL ⁽¹⁾	TYPICAL DESCRIPTIONS ⁽²⁾⁽³⁾
COARSE-GRAINED SOIL (More than 50% of material is larger than No. 200 sieve size)	GRAVEL AND GRAVELLY SOIL (More than 50% of coarse fraction retained on No. 4 sieve)	CLEAN GRAVEL (Little or no fines)		GW	Well-graded gravel; gravel/sand mixture(s); little or no fines
		GRAVEL WITH FINES (Appreciable amount of fines)		GP	Poorly graded gravel; gravel/sand mixture(s); little or no fines
				GM	Silty gravel; gravel/sand/silt mixture(s)
	SAND AND SANDY SOIL (More than 50% of coarse fraction passed through No. 4 sieve)	CLEAN SAND (Little or no fines)		SW	Well-graded sand; gravelly sand; little or no fines
		SAND WITH FINES (Appreciable amount of fines)		SP	Poorly graded sand; gravelly sand; little or no fines
				SM	Silty sand; sand/silt mixture(s)
FINE-GRAINED SOIL (More than 50% of material is smaller than No. 200 sieve size)	SILT AND CLAY (Liquid limit less than 50)			ML	Inorganic silt and very fine sand; rock flour; silty or clayey fine sand or clayey silt with slight plasticity
				CL	Inorganic clay of low to medium plasticity; gravelly clay; sandy clay; silty clay; lean clay
				OL	Organic silt; organic, silty clay of low plasticity
	SILT AND CLAY (Liquid limit greater than 50)			MH	Inorganic silt; micaceous or diatomaceous fine sand
				CH	Inorganic clay of high plasticity; fat clay
				OH	Organic clay of medium to high plasticity; organic silt
	HIGHLY ORGANIC SOIL			PT	Peat; humus; swamp soil with high organic content

OTHER MATERIALS	GRAPHIC SYMBOL	LETTER SYMBOL	TYPICAL DESCRIPTIONS
PAVEMENT		AC or PC	Asphalt concrete pavement or Portland cement pavement
ROCK		RK	Rock (See Rock Classification)
WOOD		WD	Wood, lumber, wood chips
DEBRIS		DB	Construction debris, garbage

- Notes: 1. USCS letter symbols correspond to symbols used by the Unified Soil Classification System and ASTM classification methods. Dual letter symbols (e.g., SP-SM for sand or gravel) indicate soil with an estimated 5-15% fines. Multiple letter symbols (e.g., ML/CL) indicate borderline or multiple soil classifications.
2. Soil descriptions are based on the general approach presented in the Standard Practice for Description and Identification of Soils (Visual-Manual Procedure), outlined in ASTM D 2488. Where laboratory index testing has been conducted, soil classifications are based on the Standard Test Method for Classification of Soils for Engineering Purposes, as outlined in ASTM D 2487.
3. Soil description terminology is based on visual estimates (in the absence of laboratory test data) of the percentages of each soil type and is defined as follows:

Primary Constituent: > 50% - "GRAVEL," "SAND," "SILT," "CLAY," etc.
 Secondary Constituents: > 30% and ≤ 50% - "very gravelly," "very sandy," "very silty," etc.
 > 15% and ≤ 30% - "gravelly," "sandy," "silty," etc.
 Additional Constituents: > 5% and ≤ 15% - "with gravel," "with sand," "with silt," etc.
 ≤ 5% - "with trace gravel," "with trace sand," "with trace silt," etc., or not noted.

4. Soil density or consistency descriptions are based on judgement using a combination of sampler penetration blow counts, drilling or excavating conditions, field tests, and laboratory tests, as appropriate.

Drilling and Sampling Key		Field and Lab Test Data	
SAMPLER TYPE	SAMPLE NUMBER & INTERVAL	Code	Description
Code	Description		
a	3.25-inch O.D., 2.42-inch I.D. Split Spoon	PP = 1.0	Pocket Penetrometer, tsf
b	2.00-inch O.D., 1.50-inch I.D. Split Spoon	TV = 0.5	Torvane, tsf
c	Shelby Tube	PID = 100	Photoionization Detector VOC screening, ppm
d	Grab Sample	W = 10	Moisture Content, %
e	Single-Tube Core Barrel	D = 120	Dry Density, pcf
f	Double-Tube Core Barrel	-200 = 60	Material smaller than No. 200 sieve, %
g	2.50-inch O.D., 2.00-inch I.D. WSDOT	GS	Grain Size - See separate figure for data
h	3.00-inch O.D., 2.375-inch I.D. Mod. California	AL	Atterberg Limits - See separate figure for data
i	Other - See text if applicable	GT	Other Geotechnical Testing
1	300-lb Hammer, 30-inch Drop	CA	Chemical Analysis
2	140-lb Hammer, 30-inch Drop		
3	Pushed		
4	Vibrocore (Rotasonic/Geoprobe)		
5	Other - See text if applicable		

Groundwater	
	Approximate water level at time of drilling (ATD)
	Approximate water level at time after drilling/excavation/well

B-1

LAI Project No: 1073020.010.014

SAMPLE DATA

SOIL PROFILE

Moisture Content (%)
Plastic Limit 20 40 60 80 Liquid Limit

▲ SPT N-Value ▲
△ Non-Standard N-Value △
20 40 60 80

× Fines Content (%) ×
20 40 60 80

Drilling Method: Hollow-Stem Auger

Ground Elevation (ft): 316

Drilled By: Holocene Drilling Inc.

Logged By: CAL Date: 03/08/19


Groundwater

4.5 ft ATD

Depth (ft)	Elevation (ft)	Sample Number & Interval	Sampler Type	Blows/Foot	Test Data	Graphic Symbol	USCS Symbol	Soil Description
315		S-1	d		W = 13 GS		SP-SM	Dark brown to brown, fine to medium SAND with trace silt and organics (loose, moist to wet) (TOPSOIL)
5								Brown, very gravelly, fine to coarse SAND with silt. Cobbles up to 4 inches in diameter observed. (medium dense, wet) (ESPERANCE SAND)
310		S-2	b2	20	W = 20 GS			- Grades to fine to medium sand and without gravel
10		S-3	b2	33	W = 20 GS			- Grades to dense, gravelly, and fine to coarse sand
305		S-4	b2	30	W = 27 GS		ML	Brown, very sandy SILT (hard, wet)
15		S-5	b2	32	W = 22 GS		SM	Brown, very silty, fine SAND (dense, wet)
300		S-6	b2	43	W = 12 GS			- Orange mottling observed throughout
20		S-7	b2	36	W = 13 GS			- Grades to gray-brown, moist, and silty
295		S-8	b2	53	W = 8 GS		SP-SM	Gray-brown, fine to medium SAND with silt (very dense, moist)
25		S-9	b2	60	W = 9 GS			- Grades to gravelly and fine to coarse sand
290		S-10	b2	63	W = 14 GS			- Grades to without gravel
30		S-11	b2	43	W = 18 GS			- Grades to dense
285								

Boring Completed 03/08/19
Total Depth of Boring = 31.5 ft.

- Notes:
1. Stratigraphic contacts are based on field interpretations and are approximate.
 2. Reference to the text of this report is necessary for a proper understanding of subsurface conditions.
 3. Refer to "Soil Classification System and Key" figure for explanation of graphics and symbols.




**LANDAU
ASSOCIATES**


Kitsap County
Pump Station 31 Upgrades
Silverdale, Washington

Log of Test Pit TP-1

Figure
5



1073030.010.018 4/24/20 C:\USERS\B\FORD\DESKTOP\IPS 19_31\PS 3111073020.010.014.GPJ GRAIN SIZE W/STATS




Point	Depth	Classification							LL	PL	PI	C _c	C _u
●	B-1 17.5	Silty, fine SAND (SM)										1.77	3.95
☒	B-1 20.0	Silty, fine SAND (SM)										2.19	5.37
▲	B-1 22.5	Fine to medium SAND with silt (SP-SM)										1.37	3.76
★	B-1 25.0	Gravelly, fine to coarse SAND with silt (SP-SM)										1.21	5.76
⊙	B-1 27.5	Fine to medium SAND with silt (SP-SM)										1.79	4.63
Point	Depth	D ₁₀₀	D ₆₀	D ₅₀	D ₃₀	D ₁₀	%Coarse Gravel	% Fine Gravel	% Coarse Sand	% Medium Sand	% Fine Sand	% Fines	
●	B-1 17.5	2	0.126	0.111	0.085	0.032	0.0	0.0	0.0	0.1	78.8	21.0	
☒	B-1 20.0	2	0.138	0.119	0.088	0.026	0.0	0.0	0.0	0.2	80.4	19.3	
▲	B-1 22.5	4.75	0.278	0.236	0.168	0.074	0.0	0.0	0.1	13.6	76.2	10.1	
★	B-1 25.0	37.5	0.415	0.322	0.19	0.072	5.6	10.9	6.6	16.0	50.6	10.3	
⊙	B-1 27.5	4.75	0.211	0.185	0.132	0.046	0.0	0.0	0.2	4.0	84.4	11.4	

$$C_c = D_{30}^2 / (D_{60} \cdot D_{10})$$


$$C_u = D_{60} / D_{10}$$

To be well graded: $1 < C_c < 3$ and $C_u > 4$ for GW or $C_u > 6$ for SW



Notes:

- 1) A minimum safety factor of 1.5 is recommended for buoyancy resistance (NAVFAC DM 7.02).



Legend

W_T = Weight of structure plus weight of soil wedge. Use $\gamma_B = 70$ pounds per cubic foot for buoyant soil weight.

P = Buoyancy force

Factor of Safety = W_T/P

$\Delta = 20^\circ$

∇ = Design groundwater level

Source: Naval Facilities Engineering Command Design Manual 7.2 1986

APPENDIX C

STORM WATER POLLUTION PREVENTION PLAN

THIS PAGE INTENTIONALLY LEFT BLANK

Construction Stormwater General Permit (CSWGP)

Stormwater Pollution Prevention Plan (SWPPP)

for

Central Kitsap Pump Stations 19 and 31
Conveyance System Upgrades – Pump Station Contract

Prepared for:

Department of Ecology
Northwest Regional Office

Permittee / Owner	Developer	Operator / Contractor
Kitsap County Wastewater Division	Kitsap County Wastewater Division	To Be Determined

Kitsap County

Certified Erosion and Sediment Control Lead (CESCL)

Name	Organization	Contact Phone Number
To Be Determined	To Be Determined	To Be Determined

SWPPP Prepared By

Name	Organization	Contact Phone Number
Kevin Garcia, EIT / Tony Fisher, PE	BHC Consultants, LLC	206-505-3400

SWPPP Preparation Date

April 12, 2021

Project Construction Dates

Activity / Phase	Start Date	End Date
Construction	To Be Determined	To Be Determined

Table of Contents

Project Information (1.0)	1
Existing Conditions (1.1)	1
Proposed Construction Activities (1.2)	2
Construction Stormwater Best Management Practices (BMPs) (2.0)	6
The 12 Elements (2.1)	6
Element 1: Preserve Vegetation / Mark Clearing Limits (2.1.1)	6
Element 2: Establish Construction Access (2.1.2)	7
Element 3: Control Flow Rates (2.1.3)	8
Element 4: Install Sediment Controls (2.1.4)	9
Element 5: Stabilize Soils (2.1.5)	10
Element 6: Protect Slopes (2.1.6)	12
Element 7: Protect Drain Inlets (2.1.7)	13
Element 8: Stabilize Channels and Outlets (2.1.8)	14
Element 9: Control Pollutants (2.1.9)	15
Element 10: Control Dewatering (2.1.10)	18
Element 11: Maintain BMPs (2.1.11)	19
Element 12: Manage the Project (2.1.12)	20
Element 13: Protect Low Impact Development (LID) BMPs (2.1.13)	22
Pollution Prevention Team (3.0)	22
Monitoring and Sampling Requirements (4.0)	23
Site Inspection (4.1)	23
Stormwater Quality Sampling (4.2)	23
Turbidity Sampling (4.2.1)	23
pH Sampling (4.2.2)	25
Discharges to 303(d) or Total Maximum Daily Load (TMDL) Waterbodies (5.0)	26
303(d) Listed Waterbodies (5.1)	26
TMDL Waterbodies (5.2)	26
Reporting and Record Keeping (6.0)	27
Record Keeping (6.1)	27
Site Log Book (6.1.1)	27
Records Retention (6.1.2)	27

Updating the SWPPP (6.1.3)	27
Reporting (6.2)	28
Discharge Monitoring Reports (6.2.1).....	28
Notification of Noncompliance (6.2.2).....	28
Appendix A - Site Map.....	30
Appendix B - BMP Detailsp	32
Appendix C - Site Inspection Form	34
Appendix D - Construction Stormwater General Permit (CSWGP).....	36

List of Tables

Table 1 – Pollutants

Table 2 – pH-Modifying Sources

Table 3 – Dewatering BMPs

Table 4 – Management

Table 5 – BMP Implementation Schedule

Table 6 – Team Information

Table 7 – Turbidity Sampling Method

Table 8 – pH Sampling Method

List of Appendices

Appendix A - Site Map

Appendix B - BMP Details

Appendix C - Site Inspection Form

Appendix D - Construction Stormwater General Permit (CSWGP)

List of Acronyms and Abbreviations

Acronym / Abbreviation	Explanation
303(d)	Section of the Clean Water Act pertaining to Impaired Waterbodies
BFO	Bellingham Field Office of the Department of Ecology
BMP(s)	Best Management Practice(s)
CESCL	Certified Erosion and Sediment Control Lead
CO₂	Carbon Dioxide
CRO	Central Regional Office of the Department of Ecology
CSWGP	Construction Stormwater General Permit
CWA	Clean Water Act
DMR	Discharge Monitoring Report
DO	Dissolved Oxygen
Ecology	Washington State Department of Ecology
EPA	United States Environmental Protection Agency
ERO	Eastern Regional Office of the Department of Ecology
ERTS	Environmental Report Tracking System
ESC	Erosion and Sediment Control
GULD	General Use Level Designation
NPDES	National Pollutant Discharge Elimination System
NTU	Nephelometric Turbidity Units
NWRO	Northwest Regional Office of the Department of Ecology
pH	Power of Hydrogen
RCW	Revised Code of Washington
SPCC	Spill Prevention, Control, and Countermeasure
su	Standard Units
SWMMEW	Stormwater Management Manual for Eastern Washington
SWMMWW	Stormwater Management Manual for Western Washington
SWPPP	Stormwater Pollution Prevention Plan
TESC	Temporary Erosion and Sediment Control
SWRO	Southwest Regional Office of the Department of Ecology
TMDL	Total Maximum Daily Load
VFO	Vancouver Field Office of the Department of Ecology
WAC	Washington Administrative Code
WSDOT	Washington Department of Transportation
WWHM	Western Washington Hydrology Model

Project Information (1.0)

Project/Site Name: Pump Station 19

Street/Location: Lot at the north end of the intersection of NW Bucklin Hill Road and Nels Nelson Road NW. Site address is 892 Bucklin Hill Road

City: Silverdale State: WA Zip code: 98311

Receiving waterbody: Unidentified Wetland, Barker Creek

Project/Site Name: Pump Station 31

Street/Location: Easement near the north side of an existing cul-de-sac north of NE Clover Blossom Lane and Larkin Lane NE Bremerton. Site address is 7198 Clover Blossom Lane

City: Bremerton State: WA Zip code: 98311

Receiving waterbody: Crouch Creek

Existing Conditions (1.1)

Pump Station 19

Total acreage: 9707 square foot or 0.22 acres

Disturbed acreage: 7,103 square foot or 0.16 acres

Existing structures:

The site consists of the pump station facilities, a graveled driveway, grassy areas, wetlands, and associated buffer areas. The existing pump station facilities include an above ground diesel tank, a below ground wet well and dry well, and a building in which the generator and the power/control equipment for the pump station are located. The site is sectioned off from the public by a 6-foot chain link fence and accessed via a gravel driveway off the north side of the intersection of NW Bucklin Hill Road and Nels Nelson Road NW.

Landscape topography:

The site is bounded by NW Bucklin Hill Road to the south and a grove of trees screens the site from Highway 303 to the north. Wetlands and waterways were delineated along the west, south, and east sides of the site with a stormwater detention pond located on an adjacent property to the west. Leakage from the detention pond may be contributing to the wet soil conditions and the wetlands. A grassy field slopes down from the detention pond to an asphalt-paved access road that abuts the western boundary of the site. The site continues to slope to the east/southeast at a grade of approximately 8 percent.

List of known impairments for 303(d) listed or Total Maximum Daily Load (TMDL) for the receiving waterbody:

There are no known impairments or Total Maximum Daily Load (TMDL) issues for the wetland. No contaminants are known or suspected of being located onsite. Barker Creek, a Category 5 303(d) listed stream, is located approximately 500 to 600 feet downstream (east) of the site.

The creek is listed as having dissolved oxygen impairments. The consultant is unaware of any known or suspected contaminants onsite. However, construction could result in fuel spill, sanitary sewer spills, and sediment transfer (TESC issues).

Pump Station 31

Total acreage: 4638 square foot or 0.11 acres

Disturbed acreage: 4638 square foot or 0.11 acres

Existing structures:

The pump station is located on an easement off a paved cul-de-sac and consists of a wet well, two above ground centrifugal pumps housed in a doghouse type structure, and a below ground valve vault. The doghouse type structure also contains the control panels for the station. A small, graveled area enclosed by a chain-link fence surrounds the station. Vehicular access to the station is limited. The existing force main extends along the shoulder of the paved cul-de-sac, encroaching into the paved area in limited locations.

Landscape topography:

Residential homes are located southeast and south of the site and the station borders NE Clover Blossom Lane to the northwest. The area north of the station is forested. The topography slopes downward to the north to an unnamed waterway that eventually drains to Crouch Creek. Landau Associates, Inc. (LAI) identified two waterways, including the unnamed stream in the vicinity of the station. No wetlands were identified within the study area.

List of known impairments for 303(d) listed or Total Maximum Daily Load (TMDL) for the receiving waterbody:

No 303(d) sites are located within the project area. There are no known impairments or Total Maximum Daily Load (TMDL) limits for Crouch Creek. The consultant is unaware of any known or suspected contaminants on site. However, construction could result in fuel spill, sanitary sewer spills, and sediment transfer (TESC issues).

Proposed Construction Activities (1.2)

Pump Station 19

Description of site development:

The existing wet well at PS 19 is in good condition and will be repurposed to house the new submersible pumps and the suction piping for the diesel pump. The interior of the wet well will be cleaned and coated with a corrosion resistant coating. The existing wet well lid will be removed, and a new lid constructed in place to accommodate the new access hatches.

The existing control building has reached the end of its useful life and would cost more to rehabilitate to current codes than to replace with a new building. With that in mind, a new, larger building will house the isolation and check valves, flow meter, and pig launch above ground to provide better access for maintenance. The building will also have separate rooms for the electrical control panels and the backup diesel pump. The new building will be located closer to the existing wet well to provide additional clearance from the wetlands and waterways located along the eastern portion of the site.

A new driveway will be constructed to provide access to the station as well as the detention pond to the west. Permeable interlocking concrete pavement will be used to mitigate stormwater runoff. In addition, provisions have been included for future odor control facilities to be constructed north of the wet well. The entire site will be surrounded with a chain link fence with gates to allow access to the station and to the detention pond.

Description of construction activities:

Construction activities will include site preparation, TESC installation, temporary bypassing of sewage flows while the existing wet well is being rehabilitated, and excavation and backfill to install the control building and associated pipes, valves, and fittings. The disturbed areas will be restored with permeable interlocking concrete pavement and hot mixed asphalt for the access roads/driveway and gravel, grass, or other vegetation as required to address the mitigation requirements. Site fencing will be replaced as required.

Description of site drainage including flow from and onto adjacent properties:

Geographic Information System (GIS) data was used to identify the downstream drainage path from the project site. The drainage system consists of a ditch and culvert along the south side of the site. The ditch discharges into an 18-inch stormwater pipe that conveys the runoff under NW Waaga Way. Flows from the 18-inch pipe enter another ditch that conveys the flows to a 24 inch stormwater pipe that transports the flows back to the south side of NW Waaga Way where it is released into a ditch that empties into a wetland. Eventually the runoff will make its way to Barker Creek.

Storm water flow paths will remain unchanged at this site during and after construction. Storm water that flows through the construction site and dewatering water that is pumped from the ground or from the trench will be treated using BMPs identified in Section 2. Turbidity will be monitored for all storm water runoff and dewatering discharges.

Description of final stabilization (example: extent of revegetation, paving, landscaping):

The improvements to the pump station will avoid direct impacts to the wetland and streams but will impact their associated buffers, which will trigger mitigation requirements. While extensive landscaping at PS 19 is not anticipated, disturbed areas will be restored with permeable interlocking concrete pavement and hot mixed asphalt for the access roads/driveway and gravel, grass or other vegetation as required to address the mitigation requirements.

Contaminated Site Information:

The consultant is unaware of any known or suspected contaminants on site.

Pump Station 31

Description of site development:

To bring the station into compliance with the County's current design standards, a new wet well will be installed adjacent to the existing wet well to house two submersible pumps and a new valve vault will be constructed for the isolation valves, check valves, pressure gauges, and flow meter. Provisions will be provided in the valve vault to allow County maintenance personnel to clean the station's force main. In addition, a new 4-inch force main will be installed from the station to NE Clover Blossom Lane where it will connect to the existing 12-inch force main from Pump Station 8. The control panels will be located under a canopy-type shelter for protection from elements. No control building is anticipated for this station due to the small nature of the station and a lack of space for a new building. A retaining wall will be required to provide a level area around the station for the wet well, valve vault, and control panels. Once the new station has been constructed, the existing valve vault will be demolished or abandoned, and the existing wet well will be converted to a manhole.

Description of construction activities (example: site preparation, demolition, excavation):

Construction activities will include site preparation, TESC installation, temporary bypassing of sewage flows, and excavation and backfill to install new wet well, valve vault, and associated pipes, valves, and fittings. A retaining wall will be constructed to provide a level area for the new facilities. Disturbed asphalt will be restored with hot mixed asphalt and gravel will be installed for the driveway and the area within the retaining wall around the pump station. Areas disturbed beyond the retaining wall will be restored with grass. A new chain link fence will be installed around the perimeter of the station for security.

Description of site drainage including flow from and onto adjacent properties. Must be consistent with Site Map in Appendix A:

Geographic Information System (GIS) data was also used to determine the downstream drainage path from the project site. The drainage consists of sheet flow down the slope to the northwest of the project area. The sheet flow drains to an unnamed stream that flows to the west before joining with another unnamed tributary. The second unnamed tributary transports the runoff north to Crouch Creek. Per the Wetland/Waterway Critical Areas Report prepared by LAI, no fish presence was identified in the unnamed streams. Coho have been documented in Crouch Creek.

Storm water flow paths will remain unchanged at this site during and after construction. Storm water that flows through the construction site and dewatering water that is pumped from the

ground or from the trench will be treated using BMPs identified in Section 2. Turbidity will be monitored for all storm water runoff and dewatering discharges.

Description of final stabilization (example: extent of revegetation, paving, landscaping):

The site will be restored with asphalt, gravel, and grass. In addition, the pump station site will have a new chain-link fence for security.

Contaminated Site Information:

The consultant is unaware of any known or suspected contaminants on site.

Construction Stormwater Best Management Practices (BMPs) (2.0)

The SWPPP is a living document reflecting current conditions and changes throughout the life of the project. These changes may be informal (i.e. hand-written notes and deletions). Update the SWPPP when the CESCL has noted a deficiency in BMPs or deviation from original design.

The 12 Elements (2.1)

Element 1: Preserve Vegetation / Mark Clearing Limits (2.1.1)

To protect adjacent properties and to reduce the area of soil exposed to construction, the limits of construction will be clearly marked with a fence before land-disturbing activities begin. In general, natural vegetation and native topsoil shall be retained in an undisturbed state to the maximum extent possible. Trees shall be protected unless specifically indicated to be removed in the plans.

List and describe BMPs:

1. High Visibility Plastic or Metal Fence (BMP C103): A 3'0-tall minimum heavy plastic safety orange construction fence will be installed along the project clearing limits. Install based on the manufacturer's specifications.
2. Silt Fence (BMP C233): Install a silt fence along contour whenever possible. The silt fence shall have a 2' minimum height above the original ground surface. Drive the fence posts into the ground 12" minimum. Ideally, the post spacing is 6' maximum, but this can be increased to 8' if wire backing is used. Install the silt fence per the manufacturer's specifications.

Installation Schedules: Install the fences before any land disturbing activity takes place.

Inspection and Maintenance plan:

1. Repair or replace the high visibility fence if it has been damaged or the visibility is reduced.
2. Repair any damage to the silt fence immediately. Replace the filter fabric that deteriorates due to ultraviolet breakdown.

Responsible Staff: Contractor

Element 2: Establish Construction Access (2.1.2)

Construction access or activities occurring on unpaved areas shall be minimized on both sites, yet where necessary, access points will be stabilized to minimize the tracking of sediment onto public roads. Each site will have one vehicle access route throughout the construction. Portions of construction exits may be paved with asphalt and drainage routed to a treatment system. Street sweeping and street cleaning shall be employed to prevent sediment from entering state waters or creating hazardous driving conditions. All wash wastewater shall be controlled and treated on site.

List and describe BMPs:

1. Stabilized Construction Entrance/Exit (BMP C105): Construct a stabilized entrance where specified on the plans. This will limit the vehicle access to one route. The entrance will be at least 50'-long, with a 1' thick layer of 4" to 8" quarry spalls. The stabilized construction entrance shall have a full width of ingress/egress area (15' minimum).

Installation Schedules: Construct the stabilized entrance before any land construction or demolition activity happens.

Inspection and Maintenance plan:

1. Replace or clean the quarry spalls if the entrance is not preventing sediment from being tracked onto pavement. Sweep the pavement by hand or with a high efficiency sweeper if there are any sediment that is tracked onto pavement. Do not use a non-high efficiency mechanical sweeper to prevent dust from being generated.

Responsible Staff: Contractor

Element 3: Control Flow Rates (2.1.3)

Will you construct stormwater retention and/or detention facilities?

Yes **No**

Will you use permanent infiltration ponds or other low impact development (example: rain gardens, bio-retention, porous pavement) to control flow during construction?

Yes **No**

In order to protect the properties and waterways downstream of the project sites, storm water discharges from the sites will be controlled. Permanent detention or retention ponds were not specified on the plans or these sites due to limited space available for these types of facilities. Captured runoff may be pumped west to the existing detention pond for treatment.

List and describe BMPs:

1. Wattles (BMP C235): Stake out fiber rolls with a diameter of 8' where specified on the plans. The wooden stake should be 1" x 2" x 18" and is driven through the middle of the wattle, leaving 4" protruding above the wattle.

Installation Schedules: Install wattles before any demolition or construction takes place.

Inspection and Maintenance plan: Ensure that wattles are in contact with the soil and are thoroughly entrenched, especially after a rainfall. The wattles should be embedded 3" to 4".

Responsible Staff: Contractor

Element 4: Install Sediment Controls (2.1.4)

All storm water runoff from disturbed areas shall pass through an appropriate sediment removal BMP before leaving the construction site or prior to being discharged to an infiltration facility. These sediment control BMPs are installed before other land disturbing activities take place. They shall be placed appropriately to direct the stormwater.

Construction will not impact any waters that may contain juvenile salmonids, so no protective measures are necessary.

List and describe BMPs:

1. Silt Fence (BMP C233): Install a silt fence where specified on the plans. The silt fence shall have a 2' minimum height above the original ground surface. Drive the fence posts into the ground 12" minimum. Ideally, the post spacing is 6' maximum, but this can be increased to 8' if wire backing is used. Install the silt fence per the manufacturer's specifications.
2. Storm Drain Inlet Protection (BMP C220): Install the storm drain inlet protection where specified on the plans. Clean the surrounding area before installation.
3. Wattles (BMP C235): Stake out fiber rolls with a diameter of 8' where specified on the plans. The wooden stake should be 1" x 2" x 18" and is driven through the middle of the wattle, leaving 4" protruding above the wattle.

Installation Schedules: Install the BMPs before any land disturbing activity takes place.

Inspection and Maintenance plan:

1. Check the uphill side of the fence for signs of clogging, which leads to channelization of flow; replace the fence or removed sediment should clogging occur. Remove sediment deposits when the deposit reaches approximately one-third the height of the silt fence.
2. Any sediment in the catch basin inserts shall be removed when the sediment has filled one-third of the available storage. The filter media for the insert shall be cleaned or replaced at least monthly.
3. Ensure that wattles are in contact with the soil and are thoroughly entrenched, especially after a rainfall. The wattles should be embedded 3" to 4". Repair any damage to the silt fence immediately.

Responsible Staff: Contractor

Element 5: Stabilize Soils (2.1.5)

Exposed and un-worked soils shall be stabilized with the application of effective BMPs to prevent erosion throughout the life of the project. The project sites are located west of the Cascade Mountain Crest. As such, no soils shall remain exposed and un-worked for more than 7 days during the dry season and 2 days during the wet season. The dates for the dry and wet season are shown below.

In general, cut and fill slopes will be stabilized as soon as possible and soil stockpiles will be temporarily covered with plastic sheeting. All stockpiled soils shall be stabilized from erosion, protected with sediment trapping measures, and where possible, be located away from storm drain inlets, waterways, and drainage channels.

West of the Cascade Mountains Crest

Season	Dates	Number of Days Soils Can be Left Exposed
During the Dry Season	May 1 – September 30	7 days
During the Wet Season	October 1 – April 30	2 days

Soils must be stabilized at the end of the shift before a holiday or weekend if needed based on the weather forecast.

Anticipated project dates: Start date: June 2021 End date: May 2022

Will you construct during the wet season?

Yes No

List and describe BMPs:

1. Temporary and Permanent Seeding (BMP C120): For Pump Station 19, seed all disturbed areas outside the fenced area with grass seed. The area within the fence will ultimately be graveled; however, contractor may need to temporarily seed this area or provide some type of rainfall protection in this area to avoid silt laden runoff prior to the final gravel being placed.
2. Mulching (BMP C121): Mulch can be used for less than 30 days on disturbed areas that require cover. Much may also be used at all times for seeded areas. Maintain 2-inch minimum mulch thickness.
3. Plastic Covering (C123): Cover stockpiles with plastic. Ensure a minimum of 8-inch overlap at seams.

Installation Schedules:

1. Seeding takes place after demolition has started. Seed areas that will remain unworked for more than 30 days.

2. Mulching can take place at any time of the year. Installation takes place after construction activity has begun. Mulch disturbed areas.
3. Use plastic covering to cover stockpile before a precipitation event.

Inspection and Maintenance plan:

1. Reseed any seeded areas that fail to establish at least 80 percent cover (100 percent cover for areas that receive sheet or concentrated flows)
2. Maintain the thickness of the cover. Protect eroded areas by remulching
3. Torn plastic sheets must be replaced and open seams should be repaired. Remove and replace the plastic if it begins to deteriorate due to ultraviolet radiation.

Responsible Staff: Contractor

Element 6: Protect Slopes (2.1.6)

Protecting slopes is not applicable for this project because the project area does not have any steep slopes nor will any steep slopes adjacent to the project boundaries be disturbed.

Will steep slopes be present at the site during construction?

Yes **No**

List and describe BMPs: Not Applicable

Installation Schedules: Not Applicable

Inspection and Maintenance plan: Not Applicable

Responsible Staff: Not Applicable

Element 7: Protect Drain Inlets (2.1.7)

All storm drain inlets and culverts in operation during construction shall be protected to prevent unfiltered or untreated water from entering the drainage conveyance system. However, the first priority is to keep all access roads clean of sediment and keep street wash water separate from entering storm drains until treatment can be provided.

List and describe BMPs:

1. Storm Drain Inlet Protection (BMP C220): Install the storm drain inlet protection where specified on the plans. Clean the surrounding area before installation.

Installation Schedules: Install storm drain inlet protection before any construction activity begins.

Inspection and Maintenance plan:

1. Any sediment in the catch basin insert shall be removed when the sediment has filled one-third of the available storage. Inspect the inlet weekly at a minimum and daily during storm events. The filter media for the insert shall be cleaned or replaced at least monthly.

Responsible Staff: Contractor

Element 8: Stabilize Channels and Outlets (2.1.8)

Provide stabilization, including armoring material, adequate to prevent erosion of outlets, adjacent stream banks, slopes, and downstream reaches, will be installed at the outlets of all conveyance systems.

Stormwater runoff will sheet flow off the site and will not be concentrated into channels before it enters existing ditches. Silt dikes will be installed within the existing ditches to prevent sediments from being washed further downstream.

List and describe BMPs: Triangular Silt Dike (BMP C208): The silt dike will be urethane foam sewn into a woven geosynthetic fabric. A 2' minimum apron shall extend on either side of the triangular section. The staples used shall be No. 11 gauge wire, 8"-12" in length. They should be installed 3' on center and where dike units overlap. The leading edge shall be secured with sandbags or keyed into native ground.

Installation Schedules: Install the check dams before any land disturbing activity takes place.

Inspection and Maintenance plan:

1. Inspect for performance and sediment accumulation during and after each runoff producing rainfall. Remove the sediments when it reaches one half the height of the dam.
2. Anticipate submergence and depositity above the triangular silt dam and erosion from high flows around the edges of the dam. Immediately repair any damage or any undercutting of the dam.

Responsible Staff: Contractor

Element 9: Control Pollutants (2.1.9)

The following pollutants are anticipated to be present on-site:

Table 1 – Pollutants

Pollutant (and source, if applicable)
Concrete and cementitious particles
Diesel fuel for operating construction equipment

All pollutants, including waste materials and demolition debris, that occur onsite shall be handled and disposed of in a manner that does not cause contamination of storm water. Good housekeeping and preventative measures will be taken to ensure that the site will be kept clean, well organized, and free of debris. Process water, such as wheel wash water and potentially contaminated water from asphalt surfaces will either be disposed of offsite or treated with settlement tanks. Necessary precautions will be taken to ensure pollutants are handled and disposed of in a safe manner. The contractor will be required to prepare a Spill Prevention, Control, and Countermeasure (SPCC) Plan under the Federal regulations of the Clean Water Act (CWA).

List and describe BMPs:

1. Sawcutting and Surfacing Pollution Prevention (BMP C152): Handle and dispose cleaning waste material and demolition debris in a manner that does not cause contamination of water.

Installation Schedules:

1. BMP C152 applies in the demolition of existing structures.

Inspection and Maintenance plan:

1. Monitor operations to determine whether slurry, cuttings, or process water could enter waters of the state. Stop operations and implement preventive measures should there be a violation of water quality standards.

Responsible Staff: Contractor

Will maintenance, fueling, and/or repair of heavy equipment and vehicles occur on-site?

Yes No

Contractor will need to fuel heavy equipment onsite and may be allowed to make minor repairs to equipment. Major repairs to equipment would be done offsite. The Contractor will prepare a

SPCC that describes the measures that will be implemented to prevent spills and to address inadvertent spills.

List and describe BMPs:

1. Mobile Fueling of Vehicles and Heavy Equipment (S419): Ensure the point of fueling is at least 25 feet from the nearest storm sewer or inside an impervious containment with a volumetric capacity equal to or greater than 110 percent of the fueling tank volume, or covering the storm sewer to ensure no inflow of spilled or leaked fuel. Place a drip pan, or an absorbent pad under each fueling location prior to and during all dispensing operations.
2. Spills of Oil and Hazardous Substances (BMP S426): Maintain, update, and implement a Spill Prevention and Emergency Cleanup Plan. Train key personnel in the implementation of the SPECP.

Installation Schedules:

1. The BMP for mobile fueling should be applied whenever the equipment onsite is fueled.
2. The Spill Prevention and Emergency Cleanup Plan should be present from the beginning of construction through the end of construction.

Inspection and Maintenance plan:

1. Instruction and maintenance plan depends on the contractor's SPCC.

Responsible Staff: Contractor

Will wheel wash or tire bath system BMPs be used during construction?

Yes **No**

List and describe BMPs: Not applicable

Installation Schedules: Not Applicable

Inspection and Maintenance plan: Not Applicable

Responsible Staff: Not Applicable

Will pH-modifying sources be present on-site?

Yes No If yes, check the source(s).

Table 2 – pH-Modifying Sources

	None
	Bulk cement
	Cement kiln dust

	Fly ash
✓	Other cementitious materials
	New concrete washing or curing waters
✓	Waste streams generated from concrete grinding and sawing
	Exposed aggregate processes
✓	Dewatering concrete vaults
✓	Concrete pumping and mixer washout waters
✓	Recycled concrete
	Other (i.e. calcium lignosulfate) [please describe]

List and describe BMPs:

1. BMP C151: Concrete Handling: Ensure that washout of concrete trucks, chutes, pumps, and internals is performed at an approved off-site location. Do not allow washdown from areas, such as concrete pavers in areas that do not directly drain to natural or constructed stormwater conveyances.
2. BMP C152: Sawcutting and Surfacing Pollution Prevention: Handle and dispose of cleaning waste material and demolition debris in a manner that does not cause contamination of water.

Installation Schedules:

1. BMP C151 applies when there is concrete work.
2. BMP C152 applies in the demolition of existing structures.

Inspection and Maintenance plan:

1. Check containers for holes in the liners daily during concrete pours and repair the same day.
2. Monitor operations to determine whether slurry, cuttings, or process water could enter waters of the state. Stop operations and implement preventive measures should there be a violation of water quality standards.

Responsible Staff: Contractor

Concrete trucks must not be washed out onto the ground, or into storm drains, open ditches, streets, or streams. Excess concrete must not be dumped on-site, except in designated concrete washout areas with appropriate BMPs installed.

Element 10: Control Dewatering (2.1.10)

All dewatering water from open cut excavation, tunneling, foundation work, trench, or underground vaults shall be pumped out and cleaned using methods such as a Baker tank. Discharged water shall be dispersed in a manner that does not cause erosion, flooding or a violation of State water quality standards in receiving waters. BMPs that may be used for sediment trapping and turbidity reduction include:

Table 3 – Dewatering BMPs

	Infiltration
✓	Transport off-site in a vehicle (vacuum truck for legal disposal). Effluent may also be pumped to the detention pond located west of the project after being treated.
	Ecology-approved on-site chemical treatment or other suitable treatment technologies
	Sanitary or combined sewer discharge with local sewer district approval (last resort)
	Use of sedimentation bag with discharge to ditch or swale (small volumes of localized dewatering)

List and describe BMPs:

1. Dewatering effluent from open cut excavation, foundation work, and trenching will be routed to a Baker tank to allow sediments to settle before the water is released. The Contractor may opt to release the water to the detention pond located west of the site. The Contractor may also use well points to lower the water table prior to excavating. Effluent from the well points may be pumped to the detention pond for release once the well points are established. Effluent from the well points while they are being established will be routed to a Baker tank before release.
2. Transport off-site in a vehicle, such as a vacuum flush truck, for legal disposal in a manner that does not pollute state waters.
3. BMP C151: Concrete Handling: Ensure that washout of concrete trucks, chutes, pumps, and internals is performed at an approved off-site location. Do not allow washdown from areas, such as concrete pavers in areas that directly drain directly to natural or constructed stormwater conveyances.

Installation Schedules:

1. BMP C151 applies when there is concrete work.

Inspection and Maintenance plan:

3. Check containers for holes in the liners daily during concrete pours and repair the same day.

Responsible Staff: Contractor

Element 11: Maintain BMPs (2.1.11)

All temporary and permanent Erosion and Sediment Control (ESC) BMPs shall be maintained and repaired as needed to ensure continued performance of their intended function.

Maintenance and repair shall be conducted in accordance with each particular BMP specification (see *Volume II of the SWMMWW* or *Chapter 7 of the SWMMEW*).

Visual monitoring of all BMPs installed at the site will be conducted at least once every calendar week and within 24 hours of any stormwater or non-stormwater discharge from the site. If the site becomes inactive and is temporarily stabilized, the inspection frequency may be reduced to once every calendar month.

All temporary ESC BMPs shall be removed within 30 days after final site stabilization is achieved or after the temporary BMPs are no longer needed.

Trapped sediment shall be stabilized on-site or removed. Disturbed soil resulting from removal of either BMPs or vegetation shall be permanently stabilized.

Additionally, protection must be provided for all BMPs installed for the permanent control of stormwater from sediment and compaction. BMPs that are to remain in place following completion of construction shall be examined and restored to full operating condition. If sediment enters these BMPs during construction, the sediment shall be removed and the facility shall be returned to conditions specified in the construction documents.

Element 12: Manage the Project (2.1.12)

The project will be managed based on the following principles:

- Projects will be phased to the maximum extent practicable and seasonal work limitations will be taken into account.
- Inspection and monitoring:
 - o Inspection, maintenance and repair of all BMPs will occur as needed to ensure performance of their intended function.
 - o Site inspections and monitoring will be conducted in accordance with Special Condition S4 of the CSWGP. Sampling locations are indicated on the Site Map. Sampling station(s) are located in accordance with applicable requirements of the CSWGP.
- Maintain an updated SWPPP.
 - o The SWPPP will be updated, maintained, and implemented in accordance with Special Conditions S3, S4, and S9 of the CSWGP.

As site work progresses, the SWPPP will be modified to reflect changing site conditions. The SWPPP will be reviewed at least monthly by the Contractor to ensure the content is current.

Table 4 – Management

✓	Design the project to fit the existing topography, soils, and drainage patterns
✓	Emphasize erosion control rather than sediment control
✓	Minimize the extent and duration of the area exposed
✓	Keep runoff velocities low
✓	Retain sediment on-site
✓	Thoroughly monitor site and maintain all ESC measures
✓	Schedule major earthwork during the dry season
	Other (please describe)

Table 5 – BMP Implementation Schedule

Phase of Construction Project	Stormwater BMPs	Date	Wet/Dry Season
Estimate of Construction start date:	N/A	TBD	Dry
Install ESC measures:	C103, C233, C235, C220, C105, C208	TBD	
Mobilize equipment on site:	S426	TBD	
Mobilize and store ESC and soil stabilization products (store materials on hand BMP C150):	C123	TBD	
Begin clearing and grubbing:	TBD	TBD	
Construction of sewer facilities:	C152, C151	TBD	
Final paving and re-surfacing:	C120, C121	TBD	
Estimate of Construction finish date:	N/A	TBD	

Element 13: Protect Low Impact Development (LID) BMPs (2.1.13)

Low Impact Development (LID) BMPs are stormwater management practices used to mimic the an existing site's natural hydrologic response to precipitation. Some of the common LID BMPs include bioretention/rain gardens and permeable pavements. In general, these facilities must be protected from sedimentation by installing and maintaining erosion and sediment control BMPs. These facilities must also be protected from compaction from construction equipment and foot traffic to maintain their infiltration capacities.

One of the sites, Pump Station 19, uses BMP C208 or Triangular Silt Dike to prevent sediments from being transported downstream within the ditch. Sediment shall be removed when it reaches half the height of the dam. The site also uses a permeable interlocking concrete pavement system, which specifies an uncompacted subgrade soil. All the components of the permeable interlocking concrete pavement system will be installed one area at a time to prevent heavy machinery from compacting the soil. Excavation required to establish the grades for the base and sub base will not occur until all non-restoration associated work is complete.

Pollution Prevention Team (3.0)

Table 6 – Team Information

Title	Name(s)	Phone Number
Certified Erosion and Sediment Control Lead (CESCL)	To Be Determined	To Be Determined
Resident Engineer		
Emergency Ecology Contact		
Emergency Permittee/ Owner Contact	Floyd Bayless	(360) 337-5631
Non-Emergency Owner Contact	Floyd Bayless	(360) 337-5631
Monitoring Personnel	On Duty Contact	(425) 649-7000
Ecology Regional Office	Northwest Regional Office	(425)-649-7000

Monitoring and Sampling Requirements (4.0)

Monitoring includes visual inspection, sampling for water quality parameters of concern, and documentation of the inspection and sampling findings in a site log book. A site log book will be maintained for all on-site construction activities and will include:

- A record of the implementation of the SWPPP and other permit requirements
- Site inspections
- Stormwater sampling data

The site log book must be maintained on-site within reasonable access to the site and be made available upon request to Ecology or the local jurisdiction.

Numeric effluent limits may be required for certain discharges to 303(d) listed waterbodies. See CSWGP Special Condition S8 and Section 5 of this template.

Complete the following paragraph for sites that discharge to impaired waterbodies for fine sediment, turbidity, phosphorus, or pH:

Site Inspection (4.1)

Site inspections will be conducted at least once every calendar week and within 24 hours following any discharge from the site. For sites that are temporarily stabilized and inactive, the required frequency is reduced to once per calendar month.

The discharge point(s) are indicated on the Site Map (see Appendix A) and in accordance with the applicable requirements of the CSWGP.

Stormwater Quality Sampling (4.2)

Turbidity Sampling (4.2.1)

Requirements include calibrated turbidity meter or transparency tube to sample site discharges for compliance with the CSWGP. Sampling will be conducted at all discharge points at least once per calendar week.

Method for sampling turbidity:

Table 7 – Turbidity Sampling Method

	Turbidity Meter/Turbidimeter (required for disturbances 5 acres or greater in size)
✓	Transparency Tube (option for disturbances less than 1 acre and up to 5 acres in size)

The benchmark for turbidity value is 25 nephelometric turbidity units (NTU) and a transparency less than 33 centimeters.

If the discharge's turbidity is 26 to 249 NTU or the transparency is less than 33 cm but equal to or greater than 6 cm, the following steps will be conducted:

1. Review the SWPPP for compliance with Special Condition S9. Make appropriate revisions within 7 days of the date the discharge exceeded the benchmark.
2. Immediately begin the process to fully implement and maintain appropriate source control and/or treatment BMPs as soon as possible. Address the problems within 10 days of the date the discharge exceeded the benchmark. If installation of necessary treatment BMPs is not feasible within 10 days, Ecology may approve additional time when the Permittee requests an extension within the initial 10-day response period.
3. Document BMP implementation and maintenance in the site log book.

If the turbidity exceeds 250 NTU or the transparency is 6 cm or less at any time, the following steps will be conducted:

1. Telephone or submit an electronic report to the applicable Ecology Region's Environmental Report Tracking System (ERTS) within 24 hours.
<https://www.ecology.wa.gov/About-us/Get-involved/Report-an-environmental-issue>
 - Central Region (Benton, Chelan, Douglas, Kittitas, Klickitat, Okanogan, Yakima): (509) 575-2490
 - Eastern Region (Adams, Asotin, Columbia, Ferry, Franklin, Garfield, Grant, Lincoln, Pend Oreille, Spokane, Stevens, Walla Walla, Whitman): (509) 329-3400
 - Northwest Region (King, Kitsap, Island, San Juan, Skagit, Snohomish, Whatcom): (425) 649-7000
 - Southwest Region (Clallam, Clark, Cowlitz, Grays Harbor, Jefferson, Lewis, Mason, Pacific, Pierce, Skamania, Thurston, Wahkiakum,): (360) 407-6300
2. Immediately begin the process to fully implement and maintain appropriate source control and/or treatment BMPs as soon as possible. Address the problems within 10 days of the date the discharge exceeded the benchmark. If installation of necessary treatment BMPs is not feasible within 10 days, Ecology may approve additional time when the Permittee requests an extension within the initial 10-day response period
3. Document BMP implementation and maintenance in the site log book.
4. Continue to sample discharges daily until one of the following is true:
 - Turbidity is 25 NTU (or lower).
 - Transparency is 33 cm (or greater).
 - Compliance with the water quality limit for turbidity is achieved.
 - o 1 - 5 NTU over background turbidity, if background is less than 50 NTU
 - o 1% - 10% over background turbidity, if background is 50 NTU or greater
 - The discharge stops or is eliminated.

pH Sampling (4.2.2)

pH monitoring is required for “Significant concrete work” (i.e. greater than 1000 cubic yards poured concrete or recycled concrete over the life of the project). The use of engineered soils (soil amendments including but not limited to Portland cement-treated base [CTB], cement kiln dust [CKD] or fly ash) also requires pH monitoring.

For significant concrete work, pH sampling will start the first day concrete is poured and continue until it is cured, typically three (3) weeks after the last pour.

For engineered soils and recycled concrete, pH sampling begins when engineered soils or recycled concrete are first exposed to precipitation and continues until the area is fully stabilized.

If the measured pH is 8.5 or greater, the following measures will be taken:

1. Prevent high pH water from entering storm sewer systems or surface water.
2. Adjust or neutralize the high pH water to the range of 6.5 to 8.5 su using appropriate technology such as carbon dioxide (CO₂) sparging (liquid or dry ice).
3. Written approval will be obtained from Ecology prior to the use of chemical treatment other than CO₂ sparging or dry ice.

Method for sampling pH:

Check the analysis method you will use:

Table 8 – pH Sampling Method

	pH meter
	pH test kit
	Wide range pH indicator paper

Discharges to 303(d) or Total Maximum Daily Load (TMDL) Waterbodies (5.0)

303(d) Listed Waterbodies (5.1)

Is the receiving water 303(d) (Category 5) listed for turbidity, fine sediment, phosphorus, or pH?

Yes **No**

Neither Pump Station 19 nor 31 discharges to a 303(d) waterbody listed for turbidity, fine sediment, phosphorus, or pH.

List and describe BMPs: Not Applicable

TMDL Waterbodies (5.2)

Waste Load Allocation for CWSGP discharges:

Both Pump Stations 19 and 31 are in the Sinclair and Dyes Inlets Tributaries Bacteria TMDL. The project sites are far from the Sinclair and Dyes Inlets. Construction activities will have negligible impact to the TMDL at those inlets.

List and describe BMPs:

1. Not Applicable

Discharges to TMDL receiving waterbodies will meet in-stream water quality criteria at the point of discharge.

Reporting and Record Keeping (6.0)

Record Keeping (6.1)

Site Log Book (6.1.1)

A site log book will be maintained for all on-site construction activities and will include:

- A record of the implementation of the SWPPP and other permit requirements
- Site inspections
- Sample logs

Records Retention (6.1.2)

Records will be retained during the life of the project and for a minimum of three (3) years following the termination of permit coverage in accordance with Special Condition S5.C of the CSWGP.

Permit documentation to be retained on-site:

- CSWGP
- Permit Coverage Letter
- SWPPP
- Site Log Book

Permit documentation will be provided within 14 days of receipt of a written request from Ecology. A copy of the SWPPP or access to the SWPPP will be provided to the public when requested in writing in accordance with Special Condition S5.G.2.b of the CSWGP.

Updating the SWPPP (6.1.3)

The SWPPP will be modified if:

- Found ineffective in eliminating or significantly minimizing pollutants in stormwater discharges from the site.
- There is a change in design, construction, operation, or maintenance at the construction site that has, or could have, a significant effect on the discharge of pollutants to waters of the State.

The SWPPP will be modified within seven (7) days if inspection(s) or investigation(s) determine additional or modified BMPs are necessary for compliance. An updated timeline for BMP implementation will be prepared.

Reporting (6.2)

Discharge Monitoring Reports (6.2.1)

Cumulative soil disturbance is less than one (1) acre; therefore, Discharge Monitoring Reports (DMRs) will not be submitted to Ecology because water quality sampling is not being conducted at the site.

Notification of Noncompliance (6.2.2)

If any of the terms and conditions of the permit is not met, and the resulting noncompliance may cause a threat to human health or the environment, the following actions will be taken:

1. Ecology will be notified within 24-hours of the failure to comply by calling the applicable Regional office ERTS phone number (Regional office numbers listed below).
2. Immediate action will be taken to prevent the discharge/pollution or otherwise stop or correct the noncompliance. If applicable, sampling and analysis of any noncompliance will be repeated immediately and the results submitted to Ecology within five (5) days of becoming aware of the violation.
3. A detailed written report describing the noncompliance will be submitted to Ecology within five (5) days, unless requested earlier by Ecology.

Specific information to be included in the noncompliance report is found in Special Condition S5.F.3 of the CSWGP.

Anytime turbidity sampling indicates turbidity is 250 NTUs or greater, or water transparency is 6 cm or less, the Ecology Regional office will be notified by phone within 24 hours of analysis as required by Special Condition S5.A of the CSWGP.

- Central Region at (509) 575-2490 for Benton, Chelan, Douglas, Kittitas, Klickitat, Okanogan, or Yakima County
- Eastern Region at (509) 329-3400 for Adams, Asotin, Columbia, Ferry, Franklin, Garfield, Grant, Lincoln, Pend Oreille, Spokane, Stevens, Walla Walla, or Whitman County
- Northwest Region at (425) 649-7000 for Island, King, Kitsap, San Juan, Skagit, Snohomish, or Whatcom County
- Southwest Region at (360) 407-6300 for Clallam, Clark, Cowlitz, Grays Harbor, Jefferson, Lewis, Mason, Pacific, Pierce, Skamania, Thurston, or Wahkiakum

Include the following information:


1. Your name and / Phone number
2. Permit number
3. City / County of project
4. Sample results
5. Date / Time of call
6. Date / Time of sample
7. Project name

In accordance with Special Condition S4.D.5.b of the CSWGP, the Ecology Regional office will be notified if chemical treatment other than CO₂ sparging is planned for adjustment of high pH water.

This page left intentionally blank.

Appendix A - Site Map


This page left intentionally blank.



- | COORDINATE CONTROL | | | | |
|--------------------|-----------|------------|-----------|------------------------------|
| PT # | NORTHING | EASTING | ELEVATION | DESCRIPTION |
| S1 | 242702.93 | 1189979.58 | 99.30 | BUILDING CORNER |
| S2 | 242700.34 | 1190004.78 | 98.55 | BUILDING CORNER |
| S3 | 242697.12 | 1190016.52 | 97.53 | BUILDING CORNER |
| S4 | 242677.89 | 1190014.54 | 97.43 | BUILDING CORNER |
| S5 | 242681.70 | 1189977.40 | 99.20 | BUILDING CORNER |
| S6 | 242723.52 | 1189971.48 | 100.50 | GROUND AT FUEL TANK |
| S7 | 242715.78 | 1189971.82 | 100.20 | GROUND AT FUEL TANK |
| S8 | 242708.07 | 1189980.03 | 100.00 | FUEL MONITORING VAULT |
| S9 | 242703.69 | 1189983.60 | 100.00 | FUEL MONITORING VAULT |
| SS1 | 242728.93 | 1189970.89 | 97.37 | CENTER BYPASS CONNECTION LID |
| W1 | 242657.66 | 1189974.73 | 98.70 | CENTER WATER METER BOX |
| SU1 | 242658.86 | 1189945.86 | 99.90 | BENCH MARK #1 |

- Drawing: **C19-1**
-
- Sheet: **27** of **92**
-
- File: P18-10530_C19-1
-
- Date: April 2021

Path: S:\Cadd\Kitsap County\19-10530 PS 19-31 Design\dwgs 2 Filename: P19-10530_C31-1 Plot date: Apr 02, 2021 08:04:54am CAD User: palmton.
Xref Filename: | X19-10530_TB | X19-10530_Prelim | X19-10530_PSS31 Prop | Fisher | X19-10530_PSS31 Prop Emt | X19-10530_PSS31 Prop Elec | Palmatter | Dahl |




NOTES:

- EXISTING PUMP STATION FACILITIES ARE SHOWN AND SHALL REMAIN IN SERVICE THROUGHOUT CONSTRUCTION. SEE DEMOLITION DWGS FOR DECOMMISSIONING, DEMOLITION, REMOVAL AND ABANDONING OF EXISTING PUMP STATION FACILITIES. SEE RESTORATION DWGS FOR FINISHED SITE AND RESTORATION PLAN.
- SEE DRAWING C31-5 AND SPECIAL PROVISIONS SECTION 1-08.3(2)C FOR CONSTRUCTION SEQUENCING AND CONSTRAINTS.
- MAINTAIN ACCESS TO EXISTING PUMP STATION AND SITE FACILITIES FOR COUNTY STAFF AND SERVICE TRUCKS AT ALL TIMES DURING CONSTRUCTION.
- ALL SSFM PIPE AND VALVE JOINTS, FITTINGS AND COUPLINGS SHALL BE RESTRAINED.
- PROTECT AND SUPPORT EXISTING WET WELL AS NECESSARY DURING INSTALLATION OF NEW WET WELL AND VALVE VAULT.
- SEE DRAWING S31-1 FOR RETAINING WALL ELEVATIONS.
- SEE DRAWING C31-4 FOR PROFILE OF STORM DRAIN.

COORDINATE CONTROL

PT #	NORTHING	EASTING	DESCRIPTION
1	234111.55	1199714.83	RETAINING WALL CORNER (TOW)
2	234137.97	1199739.01	RETAINING WALL CORNER (TOW)
3	234120.16	1199758.47	RETAINING WALL CORNER (TOW)
4	234096.72	1199729.65	RETAINING WALL CORNER (TOW)
5	234093.39	1199747.71	FENCE CORNER
6	234116.07	1199762.20	FENCE CORNER
7	234096.37	1199730.71	GATE POST
8	234094.13	1199746.55	GATE POST
9	234093.79	1199722.53	TOP OF UTILITY TRANSFORMER (EL 315.6±)
10	234093.79	1199711.21	TOP OF UTILITY TRANSFORMER (EL 315.6±)
11	234068.15	1199743.42	SURVEY BENCH MARK
12	234123.45	1199738.94	CENTER WET WELL
13	234113.80	1199725.84	VALVE VAULT CORNER
14	234114.86	1199735.74	VALVE VAULT CORNER
15	234101.40	1199738.27	CENTER CATCH BASIN

NORTH



NOTES:

- ROTATE EX BEND AS NEEDED FOR CONNECTION. CAP EX. PIPE TO 2' EAST OF ROTATED BEND. MAINTAIN FLOW THROUGH EX. 4" DI SSFM TO SOUTH.
- ONCE NEW STATION IS READY TO BE PLACED INTO OPERATION, DIRECT FLOW THROUGH NEW 4" SSFM. REMOVE EX. GATE VALVE, FITTINGS, AND ASSOCIATED APPURTENANCES EAST OF CAP AND ABANDON EXISTING SSFM.

PS31 FM CONNECTION

DETAIL

NTS

1

**Call 48 Hours
Before You Dig**

1-800-424-5555
UNDERGROUND SERVICE



BHC Consultants, LLC
1601 Fifth Avenue, Suite 500
Seattle, Washington 98101
206.505.3400
206.505.3406 (fax)
www.bhcconsultants.com

Designed: T. Fisher, P.E.

Drawn: S. Olsoe

Checked: R. Dorn, P.E.

Scale:

1" = 10'-0"

One Inch at Full Scale

If Not One Inch
Scale Accordingly



Kitsap County Public Works

614 Division Street, MS 26
Port Orchard, WA 98366

SILVERDALE PUMP STATION 19 AND 31 UPGRADES

**PUMP STATION 31
SITE PLAN**

Drawing: **C31-1**

Sheet: **76** of **92**

File: P19-10530_C31-1

Date: April 2021

Appendix B - BMP Details

This page left intentionally blank.

BMP C103: High Visibility Fence

Purpose

Fencing is intended to:

1. Restrict clearing to approved limits.
2. Prevent disturbance of sensitive areas, their buffers, and other areas required to be left undisturbed.
3. Limit construction traffic to designated construction entrances, exits, or internal roads.
4. Protect areas where marking with survey tape may not provide adequate protection.

Conditions of Use

To establish clearing limits plastic, fabric, or metal fence may be used:

- At the boundary of sensitive areas, their buffers, and other areas required to be left uncleared.
- As necessary to control vehicle access to and on the site.

Design and Installation Specifications

High visibility plastic fence shall be composed of a high-density polyethylene material and shall be at least four feet in height. Posts for the fencing shall be steel or wood and placed every 6 feet on center (maximum) or as needed to ensure rigidity. The fencing shall be fastened to the post every six inches with a polyethylene tie. On long continuous lengths of fencing, a tension wire or rope shall be used as a top stringer to prevent sagging between posts. The fence color shall be high visibility orange. The fence tensile strength shall be 360 lbs./ft. using the ASTM D4595 testing method.

If appropriate install fabric silt fence in accordance with [BMP C233](#) to act as high visibility fence. Silt fence shall be at least 3 feet high and must be highly visible to meet the requirements of this BMP.

Metal fences shall be designed and installed according to the manufacturer's specifications.

Metal fences shall be at least 3 feet high and must be highly visible.

Fences shall not be wired or stapled to trees.

Maintenance Standards

If the fence has been damaged or visibility reduced, it shall be repaired or replaced immediately and visibility restored.

BMP C105: Stabilized Construction Entrance / Exit

Purpose

Stabilized Construction entrances are established to reduce the amount of sediment transported onto paved roads by vehicles or equipment. This is done by constructing a stabilized pad of quarry spalls at entrances and exits for construction sites.

Conditions of Use

Construction entrances shall be stabilized wherever traffic will be entering or leaving a construction site if paved roads or other paved areas are within 1,000 feet of the site.

For residential construction provide stabilized construction entrances for each residence, rather than only at the main subdivision entrance.

Stabilized surfaces shall be of sufficient length/width to provide vehicle access/parking, based on lot size/configuration.

On large commercial, highway, and road projects, the designer should include enough extra materials in the contract to allow for additional stabilized entrances not shown in the initial Construction SWPPP. It is difficult to determine exactly where access to these projects will take place; additional materials will enable the contractor to install them where needed.

Design and Installation Specifications

See [Figure 4.1.1](#) for details. Note: the 100' minimum length of the entrance shall be reduced to the maximum practicable size when the size or configuration of the site does not allow the full length (100').

Construct stabilized construction entrances with a 12-inch thick pad of 4-inch to 8-inch quarry spalls, a 4-inch course of asphalt treated base (ATB), or use existing pavement. Do not use crushed concrete, cement, or calcium chloride for construction entrance stabilization because these products raise pH levels in stormwater and concrete discharge to surface waters of the State is prohibited.

A separation geotextile shall be placed under the spalls to prevent fine sediment from pumping up into the rock pad. The geotextile shall meet the following standards:

Grab Tensile Strength (ASTM D4751)	200 psi min.
Grab Tensile Elongation (ASTM D4632)	30% max.
Mullen Burst Strength (ASTM D3786-80a)	400 psi min.
AOS (ASTM D4751)	20-45 (U.S. standard sieve size)

- Consider early installation of the first lift of asphalt in areas that will be paved; this can be used as a stabilized entrance. Also consider the installation of excess concrete as a stabilized entrance. During large concrete pours, excess concrete is often available for this purpose.

- Fencing (see [BMP C103](#)) shall be installed as necessary to restrict traffic to the construction entrance.
- Whenever possible, the entrance shall be constructed on a firm, compacted subgrade. This can substantially increase the effectiveness of the pad and reduce the need for maintenance.
- Construction entrances should avoid crossing existing sidewalks and back of walk drains if at all possible. If a construction entrance must cross a sidewalk or back of walk drain, the full length of the sidewalk and back of walk drain must be covered and protected from sediment leaving the site.

Maintenance Standards

Quarry spalls shall be added if the pad is no longer in accordance with the specifications.

- If the entrance is not preventing sediment from being tracked onto pavement, then alternative measures to keep the streets free of sediment shall be used. This may include replacement/cleaning of the existing quarry spalls, street sweeping, an increase in the dimensions of the entrance, or the installation of a wheel wash.
- Any sediment that is tracked onto pavement shall be removed by shoveling or street sweeping. The sediment collected by sweeping shall be removed or stabilized on site. The pavement shall not be cleaned by washing down the street, except when high efficiency sweeping is ineffective and there is a threat to public safety. If it is necessary to wash the streets, the construction of a small sump to contain the wash water shall be considered. The sediment would then be washed into the sump where it can be controlled.
- Perform street sweeping by hand or with a high efficiency sweeper. Do not use a non-high efficiency mechanical sweeper because this creates dust and throws soils into storm systems or conveyance ditches.
- Any quarry spalls that are loosened from the pad, which end up on the roadway shall be removed immediately.
- If vehicles are entering or exiting the site at points other than the construction entrance(s), fencing (see [BMP C103](#)) shall be installed to control traffic.
- Upon project completion and site stabilization, all construction accesses intended as permanent access for maintenance shall be permanently stabilized.




Figure 4.1.1 – Stabilized Construction Entrance

Approved as Equivalent

Ecology has approved products as able to meet the requirements of [BMP C105](#). The products did not pass through the Technology Assessment Protocol – Ecology (TAPE) process. Local jurisdictions may choose not to accept this product approved as equivalent, or may require additional testing prior to consideration for local use. The products are available for review on Ecology's website at <http://www.ecy.wa.gov/programs/wq/stormwater/newtech/equivalent.html>

BMP C106: Wheel Wash

Purpose

Wheel washes reduce the amount of sediment transported onto paved roads by motor vehicles.

Conditions of Use

When a stabilized construction entrance (see [BMP C105](#)) is not preventing sediment from being tracked onto pavement.

- Wheel washing is generally an effective BMP when installed with careful attention to topography. For example, a wheel wash can be detrimental if installed at the top of a slope abutting a right-of-way where the water from the dripping truck can run unimpeded into the street.

stable driving surface and to stabilize any areas that have eroded.

Following construction, these areas shall be restored to pre-construction condition or better to prevent future erosion.

Perform street cleaning at the end of each day or more often if necessary.

BMP C120: Temporary and Permanent Seeding

<i>Purpose</i>	Seeding reduces erosion by stabilizing exposed soils. A well-established vegetative cover is one of the most effective methods of reducing erosion.
<i>Conditions of Use</i>	Use seeding throughout the project on disturbed areas that have reached final grade or that will remain unworked for more than 30 days. The optimum seeding windows for western Washington are April 1 through June 30 and September 1 through October 1. Between July 1 and August 30 seeding requires irrigation until 75 percent grass cover is established. Between October 1 and March 30 seeding requires a cover of mulch with straw or an erosion control blanket until 75 percent grass cover is established. Review all disturbed areas in late August to early September and complete all seeding by the end of September. Otherwise, vegetation will not establish itself enough to provide more than average protection. • Mulch is required at all times for seeding because it protects seeds from heat, moisture loss, and transport due to runoff. Mulch can be applied on top of the seed or simultaneously by hydroseeding. See BMP C121: Mulching for specifications. • Seed and mulch, all disturbed areas not otherwise vegetated at final site stabilization. Final stabilization means the completion of all soil disturbing activities at the site and the establishment of a permanent vegetative cover, or equivalent permanent stabilization measures (such as pavement, riprap, gabions, or geotextiles) which will prevent erosion.
<i>Design and Installation Specifications</i>	Seed retention/detention ponds as required. Install channels intended for vegetation before starting major earthwork and hydroseed with a Bonded Fiber Matrix. For vegetated channels that will have high flows, install erosion control blankets over hydroseed. Before allowing water to flow in vegetated channels, establish 75 percent vegetation cover. If vegetated channels cannot be established by seed before water flow; install sod in the channel bottom—over hydromulch and erosion control blankets.

- Confirm the installation of all required surface water control measures to prevent seed from washing away.
 - Hydroseed applications shall include a minimum of 1,500 pounds per acre of mulch with 3 percent tackifier. See [BMP C121: Mulching](#) for specifications.
 - Areas that will have seeding only and not landscaping may need compost or meal-based mulch included in the hydroseed in order to establish vegetation. Re-install native topsoil on the disturbed soil surface before application.
 - When installing seed via hydroseeding operations, only about 1/3 of the seed actually ends up in contact with the soil surface. This reduces the ability to establish a good stand of grass quickly. To overcome this, consider increasing seed quantities by up to 50 percent.
 - Enhance vegetation establishment by dividing the hydromulch operation into two phases:
 1. Phase 1- Install all seed and fertilizer with 25-30 percent mulch and tackifier onto soil in the first lift.
 2. Phase 2- Install the rest of the mulch and tackifier over the first lift.
- Or, enhance vegetation by:
1. Installing the mulch, seed, fertilizer, and tackifier in one lift.
 2. Spread or blow straw over the top of the hydromulch at a rate of 800-1000 pounds per acre.
 3. Hold straw in place with a standard tackifier.

Both of these approaches will increase cost moderately but will greatly improve and enhance vegetative establishment. The increased cost may be offset by the reduced need for:

- Irrigation.
- Reapplication of mulch.
- Repair of failed slope surfaces.

This technique works with standard hydromulch (1,500 pounds per acre minimum) and BFM/MBFMs (3,000 pounds per acre minimum).

- Seed may be installed by hand if:
 - Temporary and covered by straw, mulch, or topsoil.
 - Permanent in small areas (usually less than 1 acre) and covered with mulch, topsoil, or erosion blankets.
 - The seed mixes listed in the tables below include recommended mixes for both temporary and permanent seeding.

- Apply these mixes, with the exception of the wetland mix, at a rate of 120 pounds per acre. This rate can be reduced if soil amendments or slow-release fertilizers are used.
- Consult the local suppliers or the local conservation district for their recommendations because the appropriate mix depends on a variety of factors, including location, exposure, soil type, slope, and expected foot traffic. Alternative seed mixes approved by the local authority may be used.
- Other mixes may be appropriate, depending on the soil type and hydrology of the area.
- [Table 4.1.2](#) lists the standard mix for areas requiring a temporary vegetative cover.

Table 4.1.2 Temporary Erosion Control Seed Mix			
	% Weight	% Purity	% Germination
Chewings or annual blue grass <i>Festuca rubra</i> var. <i>commutata</i> or <i>Poa annua</i>	40	98	90
Perennial rye - <i>Lolium perenne</i>	50	98	90
Redtop or colonial bentgrass <i>Agrostis alba</i> or <i>Agrostis tenuis</i>	5	92	85
White dutch clover <i>Trifolium repens</i>	5	98	90

- [Table 4.1.3](#) lists a recommended mix for landscaping seed.

Table 4.1.3 Landscaping Seed Mix			
	% Weight	% Purity	% Germination
Perennial rye blend <i>Lolium perenne</i>	70	98	90
Chewings and red fescue blend <i>Festuca rubra</i> var. <i>commutata</i> or <i>Festuca rubra</i>	30	98	90

- [Table 4.1.4](#) lists a turf seed mix for dry situations where there is no need for watering. This mix requires very little maintenance.

Table 4.1.4 Low-Growing Turf Seed Mix			
	% Weight	% Purity	% Germination
Dwarf tall fescue (several varieties) <i>Festuca arundinacea</i> var.	45	98	90
Dwarf perennial rye (Barclay) <i>Lolium perenne</i> var. <i>barclay</i>	30	98	90
Red fescue <i>Festuca rubra</i>	20	98	90
Colonial bentgrass <i>Agrostis tenuis</i>	5	98	90

- [Table 4.1.5](#) lists a mix for bioswales and other intermittently wet areas.

Table 4.1.5 Bioswale Seed Mix*			
	% Weight	% Purity	% Germination
Tall or meadow fescue <i>Festuca arundinacea</i> or <i>Festuca elatior</i>	75-80	98	90
Seaside/Creeping bentgrass <i>Agrostis palustris</i>	10-15	92	85
Redtop bentgrass <i>Agrostis alba</i> or <i>Agrostis gigantea</i>	5-10	90	80

* Modified Briargreen, Inc. Hydroseeding Guide Wetlands Seed Mix

- [Table 4.1.6](#) lists a low-growing, relatively non-invasive seed mix appropriate for very wet areas that are not regulated wetlands. Apply this mixture at a rate of 60 pounds per acre. Consult Hydraulic Permit Authority (HPA) for seed mixes if applicable.

Table 4.1.6 Wet Area Seed Mix*			
	% Weight	% Purity	% Germination
Tall or meadow fescue <i>Festuca arundinacea</i> or <i>Festuca elatior</i>	60-70	98	90
Seaside/Creeping bentgrass <i>Agrostis palustris</i>	10-15	98	85
Meadow foxtail <i>Alepocurus pratensis</i>	10-15	90	80
Alsike clover <i>Trifolium hybridum</i>	1-6	98	90
Redtop bentgrass <i>Agrostis alba</i>	1-6	92	85

* Modified Briargreen, Inc. Hydroseeding Guide Wetlands Seed Mix

- [Table 4.1.7](#) lists a recommended meadow seed mix for infrequently maintained areas or non-maintained areas where colonization by native plants is desirable. Likely applications include rural road and utility right-of-way. Seeding should take place in September or very early October in order to obtain adequate establishment prior to the winter months. Consider the appropriateness of clover, a fairly invasive species, in the mix. Amending the soil can reduce the need for clover.

Table 4.1.7 Meadow Seed Mix			
	% Weight	% Purity	% Germination
Redtop or Oregon bentgrass <i>Agrostis alba</i> or <i>Agrostis oregonensis</i>	20	92	85
Red fescue <i>Festuca rubra</i>	70	98	90
White dutch clover <i>Trifolium repens</i>	10	98	90

- **Roughening and Rototilling:**
 - The seedbed should be firm and rough. Roughen all soil no matter what the slope. Track walk slopes before seeding if engineering purposes require compaction. Backblading or smoothing of slopes greater than 4H:1V is not allowed if they are to be seeded.
 - Restoration-based landscape practices require deeper incorporation than that provided by a simple single-pass rototilling treatment. Wherever practical, initially rip the subgrade to improve long-term permeability, infiltration, and water inflow qualities. At a minimum, permanent areas shall use soil amendments to achieve organic matter and permeability performance defined in engineered soil/landscape systems. For systems that are deeper than 8 inches complete the rototilling process in multiple lifts, or prepare the engineered soil system per specifications and place to achieve the specified depth.
- **Fertilizers:**
 - Conducting soil tests to determine the exact type and quantity of fertilizer is recommended. This will prevent the over-application of fertilizer.
 - Organic matter is the most appropriate form of fertilizer because it provides nutrients (including nitrogen, phosphorus, and potassium) in the least water-soluble form.
 - In general, use 10-4-6 N-P-K (nitrogen-phosphorus-potassium) fertilizer at a rate of 90 pounds per acre. Always use slow-release fertilizers because they are more efficient and have fewer environmental impacts. Do not add fertilizer to the hydromulch machine, or agitate, more than 20 minutes before use. Too much agitation destroys the slow-release coating.
 - There are numerous products available that take the place of chemical fertilizers. These include several with seaweed extracts that are beneficial to soil microbes and organisms. If 100 percent cottonseed meal is used as the mulch in hydroseed, chemical fertilizer may not be necessary. Cottonseed meal provides a good source of long-term, slow-release, available nitrogen.
- **Bonded Fiber Matrix and Mechanically Bonded Fiber Matrix:**
 - On steep slopes use Bonded Fiber Matrix (BFM) or Mechanically Bonded Fiber Matrix (MBFM) products. Apply BFM/MBFM products at a minimum rate of 3,000 pounds per acre of mulch with approximately 10 percent tackifier. Achieve a minimum of 95 percent soil coverage during application. Numerous products are available commercially. Installed products per manufacturer's instructions. Most products require 24-36 hours to cure before rainfall and cannot be installed on wet or saturated soils.

Generally, products come in 40-50 pound bags and include all necessary ingredients except for seed and fertilizer.

- BFMs and MBFMs provide good alternatives to blankets in most areas requiring vegetation establishment. Advantages over blankets include:
 - BFM and MBFMs do not require surface preparation.
 - Helicopters can assist in installing BFM and MBFMs in remote areas.
 - On slopes steeper than 2.5H:1V, blanket installers may require ropes and harnesses for safety.
 - Installing BFM and MBFMs can save at least \$1,000 per acre compared to blankets.

Maintenance Standards

Reseed any seeded areas that fail to establish at least 80 percent cover (100 percent cover for areas that receive sheet or concentrated flows). If reseeding is ineffective, use an alternate method such as sodding, mulching, or nets/blankets. If winter weather prevents adequate grass growth, this time limit may be relaxed at the discretion of the local authority when sensitive areas would otherwise be protected.

- Reseed and protect by mulch any areas that experience erosion after achieving adequate cover. Reseed and protect by mulch any eroded area.
- Supply seeded areas with adequate moisture, but do not water to the extent that it causes runoff.

Approved as Equivalent

Ecology has approved products as able to meet the requirements of [BMP C120](#). The products did not pass through the Technology Assessment Protocol – Ecology (TAPE) process. Local jurisdictions may choose not to accept this product approved as equivalent, or may require additional testing prior to consideration for local use. The products are available for review on Ecology's website at <http://www.ecy.wa.gov/programs/wq/stormwater/newtech/equivalent.html>.

BMP C121: Mulching

Purpose

Mulching soils provides immediate temporary protection from erosion. Mulch also enhances plant establishment by conserving moisture, holding fertilizer, seed, and topsoil in place, and moderating soil temperatures. There is an enormous variety of mulches that can be used. This section discusses only the most common types of mulch.

Conditions of Use

As a temporary cover measure, mulch should be used:

- For less than 30 days on disturbed areas that require cover.
- At all times for seeded areas, especially during the wet season and during the hot summer months.

- During the wet season on slopes steeper than 3H:1V with more than 10 feet of vertical relief.

Mulch may be applied at any time of the year and must be refreshed periodically.

- For seeded areas mulch may be made up of 100 percent: cottonseed meal; fibers made of wood, recycled cellulose, hemp, kenaf; compost; or blends of these. Tackifier shall be plant-based, such as guar or alpha plantago, or chemical-based such as polyacrylamide or polymers. Any mulch or tackifier product used shall be installed per manufacturer's instructions. Generally, mulches come in 40-50 pound bags. Seed and fertilizer are added at time of application.

Design and Installation Specifications

For mulch materials, application rates, and specifications, see [Table 4.1.8](#). Always use a 2-inch minimum mulch thickness; increase the thickness until the ground is 95% covered (i.e. not visible under the mulch layer).

Note: Thickness may be increased for disturbed areas in or near sensitive areas or other areas highly susceptible to erosion.

Where the option of "Compost" is selected, it should be a coarse compost that meets the following size gradations when tested in accordance with the U.S. Composting Council "Test Methods for the Examination of Compost and Composting" (TMECC) Test Method 02.02-B.

Coarse Compost

Minimum Percent passing 3" sieve openings 100%

Minimum Percent passing 1" sieve openings 90%

Minimum Percent passing ¾" sieve openings 70%

Minimum Percent passing ¼" sieve openings 40%

Mulch used within the ordinary high-water mark of surface waters should be selected to minimize potential flotation of organic matter. Composted organic materials have higher specific gravities (densities) than straw, wood, or chipped material. Consult Hydraulic Permit Authority (HPA) for mulch mixes if applicable.

Maintenance Standards

- The thickness of the cover must be maintained.
- Any areas that experience erosion shall be remulched and/or protected with a net or blanket. If the erosion problem is drainage related, then the problem shall be fixed and the eroded area remulched.

**Table 4.1.8
Mulch Standards and Guidelines**

Mulch Material	Quality Standards	Application Rates	Remarks
Straw	Air-dried; free from undesirable seed and coarse material.	2"-3" thick; 5 bales per 1,000 sf or 2-3 tons per acre	Cost-effective protection when applied with adequate thickness. Hand-application generally requires greater thickness than blown straw. The thickness of straw may be reduced by half when used in conjunction with seeding. In windy areas straw must be held in place by crimping, using a tackifier, or covering with netting. Blown straw always has to be held in place with a tackifier as even light winds will blow it away. Straw, however, has several deficiencies that should be considered when selecting mulch materials. It often introduces and/or encourages the propagation of weed species and it has no significant long-term benefits. It should also not be used within the ordinary high-water elevation of surface waters (due to flotation).
Hydromulch	No growth inhibiting factors.	Approx. 25-30 lbs per 1,000 sf or 1,500 - 2,000 lbs per acre	Shall be applied with hydromulcher. Shall not be used without seed and tackifier unless the application rate is at least doubled. Fibers longer than about ¾-1 inch clog hydromulch equipment. Fibers should be kept to less than ¾ inch.
Compost	No visible water or dust during handling. Must be produced per WAC 173-350 , Solid Waste Handling Standards, but may have up to 35% biosolids.	2" thick min.; approx. 100 tons per acre (approx. 800 lbs per yard)	More effective control can be obtained by increasing thickness to 3". Excellent mulch for protecting final grades until landscaping because it can be directly seeded or tilled into soil as an amendment. Compost used for mulch has a coarser size gradation than compost used for BMP C125 or BMP T5.13 (see Chapter 5 of Volume V of this manual) It is more stable and practical to use in wet areas and during rainy weather conditions. Do not use near wetlands or near phosphorous impaired water bodies.
Chipped Site Vegetation	Average size shall be several inches. Gradations from fines to 6 inches in length for texture, variation, and interlocking properties.	2" thick min.;	This is a cost-effective way to dispose of debris from clearing and grubbing, and it eliminates the problems associated with burning. Generally, it should not be used on slopes above approx. 10% because of its tendency to be transported by runoff. It is not recommended within 200 feet of surface waters. If seeding is expected shortly after mulch, the decomposition of the chipped vegetation may tie up nutrients important to grass establishment.
Wood-based Mulch or Wood Straw	No visible water or dust during handling. Must be purchased from a supplier with a Solid Waste Handling Permit or one exempt from solid waste regulations.	2" thick min.; approx. 100 tons per acre (approx. 800 lbs. per cubic yard)	This material is often called "hog or hogged fuel." The use of mulch ultimately improves the organic matter in the soil. Special caution is advised regarding the source and composition of wood-based mulches. Its preparation typically does not provide any weed seed control, so evidence of residual vegetation in its composition or known inclusion of weed plants or seeds should be monitored and prevented (or minimized).
Wood Strand Mulch	A blend of loose, long, thin wood pieces derived from native conifer or deciduous trees with high length-to-width ratio.	2" thick min.	Cost-effective protection when applied with adequate thickness. A minimum of 95-percent of the wood strand shall have lengths between 2 and 10-inches, with a width and thickness between 1/16 and ¾-inches. The mulch shall not contain resin, tannin, or other compounds in quantities that would be detrimental to plant life. Sawdust or wood shavings shall not be used as mulch. (WSDOT specification (9-14.4(4))

BMP C123: Plastic Covering

Purpose

Plastic covering provides immediate, short-term erosion protection to slopes and disturbed areas.

Conditions of Use

Plastic covering may be used on disturbed areas that require cover measures for less than 30 days, except as stated below.

- Plastic is particularly useful for protecting cut and fill slopes and stockpiles. Note: The relatively rapid breakdown of most polyethylene sheeting makes it unsuitable for long-term (greater than six months) applications.
- Due to rapid runoff caused by plastic covering, do not use this method upslope of areas that might be adversely impacted by concentrated runoff. Such areas include steep and/or unstable slopes.
- Plastic sheeting may result in increased runoff volumes and velocities, requiring additional on-site measures to counteract the increases. Creating a trough with wattles or other material can convey clean water away from these areas.
- To prevent undercutting, trench and backfill rolled plastic covering products.
- While plastic is inexpensive to purchase, the added cost of installation, maintenance, removal, and disposal make this an expensive material, up to \$1.50-2.00 per square yard.
- Whenever plastic is used to protect slopes install water collection measures at the base of the slope. These measures include plastic-covered berms, channels, and pipes used to convey clean rainwater away from bare soil and disturbed areas. Do not mix clean runoff from a plastic covered slope with dirty runoff from a project.
- Other uses for plastic include:
 1. Temporary ditch liner.
 2. Pond liner in temporary sediment pond.
 3. Liner for bermed temporary fuel storage area if plastic is not reactive to the type of fuel being stored.
 4. Emergency slope protection during heavy rains.
 5. Temporary drainpipe (“elephant trunk”) used to direct water.
- Plastic slope cover must be installed as follows:
 1. Run plastic up and down slope, not across slope.
 2. Plastic may be installed perpendicular to a slope if the slope length is less than 10 feet.
 3. Minimum of 8-inch overlap at seams.

Design and Installation Specifications

4. On long or wide slopes, or slopes subject to wind, tape all seams.
 5. Place plastic into a small (12-inch wide by 6-inch deep) slot trench at the top of the slope and backfill with soil to keep water from flowing underneath.
 6. Place sand filled burlap or geotextile bags every 3 to 6 feet along seams and tie them together with twine to hold them in place.
 7. Inspect plastic for rips, tears, and open seams regularly and repair immediately. This prevents high velocity runoff from contacting bare soil which causes extreme erosion.
 8. Sandbags may be lowered into place tied to ropes. However, all sandbags must be staked in place.
- Plastic sheeting shall have a minimum thickness of 0.06 millimeters.
 - If erosion at the toe of a slope is likely, a gravel berm, riprap, or other suitable protection shall be installed at the toe of the slope in order to reduce the velocity of runoff.
 - Torn sheets must be replaced and open seams repaired.
 - Completely remove and replace the plastic if it begins to deteriorate due to ultraviolet radiation.
 - Completely remove plastic when no longer needed.
 - Dispose of old tires used to weight down plastic sheeting appropriately.

Maintenance Standards

Approved as Equivalent

Ecology has approved products as able to meet the requirements of [BMP C123](#). The products did not pass through the Technology Assessment Protocol – Ecology (TAPE) process. Local jurisdictions may choose not to accept this product approved as equivalent, or may require additional testing prior to consideration for local use. The products are available for review on Ecology’s website at <http://www.ecy.wa.gov/programs/wq/stormwater/newtech/equivalent.html>

BMP C124: Sodding

Purpose

The purpose of sodding is to establish permanent turf for immediate erosion protection and to stabilize drainage ways where concentrated overland flow will occur.

Conditions of Use

Sodding may be used in the following areas:

- Disturbed areas that require short-term or long-term cover.
- Disturbed areas that require immediate vegetative cover.
- All waterways that require vegetative lining. Waterways may also be seeded rather than sodded, and protected with a net or blanket.

***Design and
Installation
Specifications***

Depending on project type, size, complexity, and length, materials and quantities will vary. A good minimum list of items that will cover numerous situations includes:

Material
Clear Plastic, 6 mil
Drainpipe, 6 or 8 inch diameter
Sandbags, filled
Straw Bales for mulching,
Quarry Spalls
Washed Gravel
Geotextile Fabric
Catch Basin Inserts
Steel “T” Posts
Silt fence material
Straw Wattles

***Maintenance
Standards***

- All materials with the exception of the quarry spalls, steel “T” posts, and gravel should be kept covered and out of both sun and rain.
- Re-stock materials used as needed.

BMP C151: Concrete Handling

Purpose

Concrete work can generate process water and slurry that contain fine particles and high pH, both of which can violate water quality standards in the receiving water. Concrete spillage or concrete discharge to surface waters of the State is prohibited. Use this BMP to minimize and eliminate concrete, concrete process water, and concrete slurry from entering waters of the state.

Conditions of Use

Any time concrete is used, utilize these management practices. Concrete construction projects include, but are not limited to, the following:

- Curbs
- Sidewalks
- Roads
- Bridges
- Foundations
- Floors
- Runways

***Design and
Installation***

- Assure that washout of concrete trucks, chutes, pumps, and internals is performed at an approved off-site location or in designated concrete

Specifications

washout areas. Do not wash out concrete trucks onto the ground, or into storm drains, open ditches, streets, or streams. Refer to [BMP C154](#) for information on concrete washout areas.

- Return unused concrete remaining in the truck and pump to the originating batch plant for recycling. Do not dump excess concrete on site, except in designated concrete washout areas.
- Wash off hand tools including, but not limited to, screeds, shovels, rakes, floats, and trowels into formed areas only.
- Wash equipment difficult to move, such as concrete pavers in areas that do not directly drain to natural or constructed stormwater conveyances.
- Do not allow washdown from areas, such as concrete aggregate driveways, to drain directly to natural or constructed stormwater conveyances.
- Contain washwater and leftover product in a lined container when no formed areas are available. Dispose of contained concrete in a manner that does not violate ground water or surface water quality standards.
- Always use forms or solid barriers for concrete pours, such as pilings, within 15-feet of surface waters.
- Refer to [BMPs C252](#) and [C253](#) for pH adjustment requirements.
- Refer to the Construction Stormwater General Permit for pH monitoring requirements if the project involves one of the following activities:
 - Significant concrete work (greater than 1,000 cubic yards poured concrete or recycled concrete used over the life of a project).
 - The use of engineered soils amended with (but not limited to) Portland cement-treated base, cement kiln dust or fly ash.
 - Discharging stormwater to segments of water bodies on the 303(d) list (Category 5) for high pH.

Maintenance Standards

Check containers for holes in the liner daily during concrete pours and repair the same day.

BMP C152: Sawcutting and Surfacing Pollution Prevention

Purpose Sawcutting and surfacing operations generate slurry and process water that contains fine particles and high pH (concrete cutting), both of which can violate the water quality standards in the receiving water. Concrete spillage or concrete discharge to surface waters of the State is prohibited. Use this BMP to minimize and eliminate process water and slurry created through sawcutting or surfacing from entering waters of the State.

Conditions of Use Utilize these management practices anytime sawcutting or surfacing operations take place. Sawcutting and surfacing operations include, but are not limited to, the following:

- Sawing
 - Coring
 - Grinding
 - Roughening
 - Hydro-demolition
 - Bridge and road surfacing
- Design and Installation Specifications**
- Vacuum slurry and cuttings during cutting and surfacing operations.
 - Slurry and cuttings shall not remain on permanent concrete or asphalt pavement overnight.
 - Slurry and cuttings shall not drain to any natural or constructed drainage conveyance including stormwater systems. This may require temporarily blocking catch basins.
 - Dispose of collected slurry and cuttings in a manner that does not violate ground water or surface water quality standards.
 - Do not allow process water generated during hydro-demolition, surface roughening or similar operations to drain to any natural or constructed drainage conveyance including stormwater systems. Dispose process water in a manner that does not violate ground water or surface water quality standards.
 - Handle and dispose cleaning waste material and demolition debris in a manner that does not cause contamination of water. Dispose of sweeping material from a pick-up sweeper at an appropriate disposal site.

Maintenance Standards Continually monitor operations to determine whether slurry, cuttings, or process water could enter waters of the state. If inspections show that a violation of water quality standards could occur, stop operations and immediately implement preventive measures such as berms, barriers, secondary containment, and vacuum trucks.

BMP C160: Certified Erosion and Sediment Control Lead

Purpose The project proponent designates at least one person as the responsible representative in charge of erosion and sediment control (ESC), and water quality protection. The designated person shall be the Certified Erosion and Sediment Control Lead (CESCL) who is responsible for ensuring compliance with all local, state, and federal erosion and sediment control and water quality requirements.

Conditions of Use A CESCL shall be made available on projects one acre or larger that discharge stormwater to surface waters of the state. Sites less than one acre may have a person without CESCL certification conduct inspections; sampling is not required on sites that disturb less than an acre.

- The CESCL shall:
 - Have a current certificate proving attendance in an erosion and sediment control training course that meets the minimum ESC training and certification requirements established by Ecology (see details below).

Ecology will maintain a list of ESC training and certification providers at:

<http://www.ecy.wa.gov/programs/wq/stormwater/cescl.html>

OR

- Be a Certified Professional in Erosion and Sediment Control (CPESC); for additional information go to: www.cpesc.net

Specifications

- Certification shall remain valid for three years.
- The CESCL shall have authority to act on behalf of the contractor or developer and shall be available, or on-call, 24 hours per day throughout the period of construction.
- The Construction SWPPP shall include the name, telephone number, fax number, and address of the designated CESCL.
- A CESCL may provide inspection and compliance services for multiple construction projects in the same geographic region.

Duties and responsibilities of the CESCL shall include, but are not limited to the following:

- Maintaining permit file on site at all times which includes the Construction SWPPP and any associated permits and plans.
- Directing BMP installation, inspection, maintenance, modification, and removal.

- Updating all project drawings and the Construction SWPPP with changes made.
- Completing any sampling requirements including reporting results using WebDMR.
- Keeping daily logs, and inspection reports. Inspection reports should include:
 - Inspection date/time.
 - Weather information; general conditions during inspection and approximate amount of precipitation since the last inspection.
 - A summary or list of all BMPs implemented, including observations of all erosion/sediment control structures or practices. The following shall be noted:
 1. Locations of BMPs inspected.
 2. Locations of BMPs that need maintenance.
 3. Locations of BMPs that failed to operate as designed or intended.
 4. Locations of where additional or different BMPs are required.
 - Visual monitoring results, including a description of discharged stormwater. The presence of suspended sediment, turbid water, discoloration, and oil sheen shall be noted, as applicable.
 - Any water quality monitoring performed during inspection.
 - General comments and notes, including a brief description of any BMP repairs, maintenance or installations made as a result of the inspection.
- Facilitate, participate in, and take corrective actions resulting from inspections performed by outside agencies or the owner.

BMP C162: Scheduling

<i>Purpose</i>	Sequencing a construction project reduces the amount and duration of soil exposed to erosion by wind, rain, runoff, and vehicle tracking.
<i>Conditions of Use</i>	The construction sequence schedule is an orderly listing of all major land-disturbing activities together with the necessary erosion and sedimentation control measures planned for the project. This type of schedule guides the contractor on work to be done before other work is started so that serious erosion and sedimentation problems can be avoided. Following a specified work schedule that coordinates the timing of land-disturbing activities and the installation of control measures is perhaps the most cost-effective way of controlling erosion during construction. The removal of surface ground cover leaves a site vulnerable to accelerated

erosion. Construction procedures that limit land clearing provide timely installation of erosion and sedimentation controls, and restore protective cover quickly can significantly reduce the erosion potential of a site.

***Design
Considerations***

- Minimize construction during rainy periods.
- Schedule projects to disturb only small portions of the site at any one time. Complete grading as soon as possible. Immediately stabilize the disturbed portion before grading the next portion. Practice staged seeding in order to revegetate cut and fill slopes as the work progresses.

BMP C208: Triangular Silt Dike (TSD) (Geotextile-Encased Check Dam)

<i>Purpose</i>	Triangular silt dikes may be used as check dams, for perimeter protection, for temporary soil stockpile protection, for drop inlet protection, or as a temporary interceptor dike.
<i>Conditions of use</i>	• May be used on soil or pavement with adhesive or staples. • TSDs have been used to build temporary: 1. sediment ponds; 2. diversion ditches; 3. concrete wash out facilities; 4. curbing; 5. water bars; 6. level spreaders; and, 7. berms.
<i>Design and Installation Specifications</i>	Made of urethane foam sewn into a woven geosynthetic fabric. It is triangular, 10 inches to 14 inches high in the center, with a 20-inch to 28-inch base. A 2-foot apron extends beyond both sides of the triangle along its standard section of 7 feet. A sleeve at one end allows attachment of additional sections as needed. • Install with ends curved up to prevent water from flowing around the ends. • The fabric flaps and check dam units are attached to the ground with wire staples. Wire staples should be No. 11 gauge wire and should be 200 mm to 300 mm in length. • When multiple units are installed, the sleeve of fabric at the end of the unit shall overlap the abutting unit and be stapled. • Check dams should be located and installed as soon as construction will allow. • Check dams should be placed perpendicular to the flow of water. • When used as check dams, the leading edge must be secured with rocks, sandbags, or a small key slot and staples. • In the case of grass-lined ditches and swales, check dams and accumulated sediment shall be removed when the grass has matured sufficiently to protect the ditch or swale unless the slope of the swale is greater than 4 percent. The area beneath the check dams shall be seeded and mulched immediately after dam removal.
<i>Maintenance</i>	• Triangular silt dams shall be inspected for performance and sediment

Standards

accumulation during and after each runoff producing rainfall. Sediment shall be removed when it reaches one half the height of the dam.

- Anticipate submergence and deposition above the triangular silt dam and erosion from high flows around the edges of the dam. Immediately repair any damage or any undercutting of the dam.

BMP C209: Outlet Protection**Purpose**

Outlet protection prevents scour at conveyance outlets and minimizes the potential for downstream erosion by reducing the velocity of concentrated stormwater flows.

Conditions of use

Outlet protection is required at the outlets of all ponds, pipes, ditches, or other conveyances, and where runoff is conveyed to a natural or manmade drainage feature such as a stream, wetland, lake, or ditch.

**Design and
Installation
Specifications**

The receiving channel at the outlet of a culvert shall be protected from erosion by rock lining a minimum of 6 feet downstream and extending up the channel sides a minimum of 1-foot above the maximum tailwater elevation or 1-foot above the crown, whichever is higher. For large pipes (more than 18 inches in diameter), the outlet protection lining of the channel is lengthened to four times the diameter of the culvert.

- Standard wingwalls, and tapered outlets and paved channels should also be considered when appropriate for permanent culvert outlet protection. (See WSDOT Hydraulic Manual, available through WSDOT Engineering Publications).
- Organic or synthetic erosion blankets, with or without vegetation, are usually more effective than rock, cheaper, and easier to install. Materials can be chosen using manufacturer product specifications. ASTM test results are available for most products and the designer can choose the correct material for the expected flow.
- With low flows, vegetation (including sod) can be effective.
- The following guidelines shall be used for riprap outlet protection:
 1. If the discharge velocity at the outlet is less than 5 fps (pipe slope less than 1 percent), use 2-inch to 8-inch riprap. Minimum thickness is 1-foot.
 2. For 5 to 10 fps discharge velocity at the outlet (pipe slope less than 3 percent), use 24-inch to 48-inch riprap. Minimum thickness is 2 feet.
 3. For outlets at the base of steep slope pipes (pipe slope greater than 10 percent), an engineered energy dissipater shall be used.
- Filter fabric or erosion control blankets should always be used under riprap to prevent scour and channel erosion.

- New pipe outfalls can provide an opportunity for low-cost fish habitat improvements. For example, an alcove of low-velocity water can be created by constructing the pipe outfall and associated energy dissipater back from the stream edge and digging a channel, over-widened to the upstream side, from the outfall. Overwintering juvenile and migrating adult salmonids may use the alcove as shelter during high flows. Bank stabilization, bioengineering, and habitat features may be required for disturbed areas. This work may require a HPA. See Volume V for more information on outfall system design.

Maintenance Standards

- Inspect and repair as needed.
- Add rock as needed to maintain the intended function.
- Clean energy dissipater if sediment builds up.

BMP C220: Storm Drain Inlet Protection

Purpose

Storm drain inlet protection prevents coarse sediment from entering drainage systems prior to permanent stabilization of the disturbed area.

Conditions of Use

Use storm drain inlet protection at inlets that are operational before permanent stabilization of the disturbed drainage area. Provide protection for all storm drain inlets downslope and within 500 feet of a disturbed or construction area, unless conveying runoff entering catch basins to a sediment pond or trap.

Also consider inlet protection for lawn and yard drains on new home construction. These small and numerous drains coupled with lack of gutters in new home construction can add significant amounts of sediment into the roof drain system. If possible delay installing lawn and yard drains until just before landscaping or cap these drains to prevent sediment from entering the system until completion of landscaping. Provide 18-inches of sod around each finished lawn and yard drain.

[Table 4.2.2](#) lists several options for inlet protection. All of the methods for storm drain inlet protection tend to plug and require a high frequency of maintenance. Limit drainage areas to one acre or less. Possibly provide emergency overflows with additional end-of-pipe treatment where stormwater ponding would cause a hazard.

Table 4.2.2 Storm Drain Inlet Protection			
Type of Inlet Protection	Emergency Overflow	Applicable for Paved/ Earthen Surfaces	Conditions of Use
Drop Inlet Protection			
Excavated drop inlet protection	Yes, temporary flooding will occur	Earthen	Applicable for heavy flows. Easy to maintain. Large area Requirement: 30' X 30'/acre
Block and gravel drop inlet protection	Yes	Paved or Earthen	Applicable for heavy concentrated flows. Will not pond.
Gravel and wire drop inlet protection	No		Applicable for heavy concentrated flows. Will pond. Can withstand traffic.
Catch basin filters	Yes	Paved or Earthen	Frequent maintenance required.
Curb Inlet Protection			
Curb inlet protection with a wooden weir	Small capacity overflow	Paved	Used for sturdy, more compact installation.
Block and gravel curb inlet protection	Yes	Paved	Sturdy, but limited filtration.
Culvert Inlet Protection			
Culvert inlet sediment trap			18 month expected life.

Design and Installation Specifications

Excavated Drop Inlet Protection - An excavated impoundment around the storm drain. Sediment settles out of the stormwater prior to entering the storm drain.

- Provide a depth of 1-2 ft as measured from the crest of the inlet structure.
- Slope sides of excavation no steeper than 2H:1V.
- Minimum volume of excavation 35 cubic yards.
- Shape basin to fit site with longest dimension oriented toward the longest inflow area.
- Install provisions for draining to prevent standing water problems.
- Clear the area of all debris.
- Grade the approach to the inlet uniformly.
- Drill weep holes into the side of the inlet.
- Protect weep holes with screen wire and washed aggregate.
- Seal weep holes when removing structure and stabilizing area.

- Build a temporary dike, if necessary, to the down slope side of the structure to prevent bypass flow.

Block and Gravel Filter - A barrier formed around the storm drain inlet with standard concrete blocks and gravel. See [Figure 4.2.8](#).

- Provide a height of 1 to 2 feet above inlet.
- Recess the first row 2-inches into the ground for stability.
- Support subsequent courses by placing a 2x4 through the block opening.
- Do not use mortar.
- Lay some blocks in the bottom row on their side for dewatering the pool.
- Place hardware cloth or comparable wire mesh with ½-inch openings over all block openings.
- Place gravel just below the top of blocks on slopes of 2H:1V or flatter.
- An alternative design is a gravel donut.
- Provide an inlet slope of 3H:1V.
- Provide an outlet slope of 2H:1V.
- Provide a 1-foot wide level stone area between the structure and the inlet.
- Use inlet slope stones 3 inches in diameter or larger.
- Use gravel ½- to ¾-inch at a minimum thickness of 1-foot for the outlet slope.




Figure 4.2.8 – Block and Gravel Filter

Gravel and Wire Mesh Filter - A gravel barrier placed over the top of the inlet. This structure does not provide an overflow.

- Use a hardware cloth or comparable wire mesh with ½-inch openings.
- Use coarse aggregate.
- Provide a height 1-foot or more, 18-inches wider than inlet on all sides.
- Place wire mesh over the drop inlet so that the wire extends a minimum of 1-foot beyond each side of the inlet structure.
- Overlap the strips if more than one strip of mesh is necessary.

- Place coarse aggregate over the wire mesh.
- Provide at least a 12-inch depth of gravel over the entire inlet opening and extend at least 18-inches on all sides.

Catchbasin Filters – Use inserts designed by manufacturers for construction sites. The limited sediment storage capacity increases the amount of inspection and maintenance required, which may be daily for heavy sediment loads. To reduce maintenance requirements combine a catchbasin filter with another type of inlet protection. This type of inlet protection provides flow bypass without overflow and therefore may be a better method for inlets located along active rights-of-way.

- Provides 5 cubic feet of storage.
- Requires dewatering provisions.
- Provides a high-flow bypass that will not clog under normal use at a construction site.
- Insert the catchbasin filter in the catchbasin just below the grating.

Curb Inlet Protection with Wooden Weir – Barrier formed around a curb inlet with a wooden frame and gravel.

- Use wire mesh with ½-inch openings.
- Use extra strength filter cloth.
- Construct a frame.
- Attach the wire and filter fabric to the frame.
- Pile coarse washed aggregate against wire/fabric.
- Place weight on frame anchors.

Block and Gravel Curb Inlet Protection – Barrier formed around a curb inlet with concrete blocks and gravel. See [Figure 4.2.9](#).

- Use wire mesh with ½-inch openings.
- Place two concrete blocks on their sides abutting the curb at either side of the inlet opening. These are spacer blocks.
- Place a 2x4 stud through the outer holes of each spacer block to align the front blocks.
- Place blocks on their sides across the front of the inlet and abutting the spacer blocks.
- Place wire mesh over the outside vertical face.
- Pile coarse aggregate against the wire to the top of the barrier.

Curb and Gutter Sediment Barrier – Sandbag or rock berm (riprap and aggregate) 3 feet high and 3 feet wide in a horseshoe shape. See [Figure 4.2.10](#).


***Maintenance
Standards***

- Construct a horseshoe shaped berm, faced with coarse aggregate if using riprap, 3 feet high and 3 feet wide, at least 2 feet from the inlet.
- Construct a horseshoe shaped sedimentation trap on the outside of the berm sized to sediment trap standards for protecting a culvert inlet.
- Inspect catch basin filters frequently, especially after storm events. Clean and replace clogged inserts. For systems with clogged stone filters: pull away the stones from the inlet and clean or replace. An alternative approach would be to use the clogged stone as fill and put fresh stone around the inlet.
- Do not wash sediment into storm drains while cleaning. Spread all excavated material evenly over the surrounding land area or stockpile and stabilize as appropriate.


***Approved as
Equivalent***

Ecology has approved products as able to meet the requirements of [BMP C220](#). The products did not pass through the Technology Assessment Protocol – Ecology (TAPE) process. Local jurisdictions may choose not to accept this product approved as equivalent, or may require additional testing prior to consideration for local use. The products are available for review on Ecology’s website at <http://www.ecy.wa.gov/programs/wq/stormwater/newtech/equivalent.html>

Plan View



Section A - A




NOTES:

1. Use block and gravel type sediment barrier when curb inlet is located in gently sloping street segment, where water can pond and allow sediment to separate from runoff.
2. Barrier shall allow for overflow from severe storm event.
3. Inspect barriers and remove sediment after each storm event. Sediment and gravel must be removed from the traveled way immediately.

Figure 4.2.9 – Block and Gravel Curb Inlet Protection

Plan View



NOTES:

1. Place curb type sediment barriers on gently sloping street segments, where water can pond and allow sediment to separate from runoff.
2. Sandbags of either burlap or woven 'geotextile' fabric, are filled with gravel, layered and packed tightly.
3. Leave a one sandbag gap in the top row to provide a spillway for overflow.
4. Inspect barriers and remove sediment after each storm event. Sediment and gravel must be removed from the traveled way immediately.

Figure 4.2.10 – Curb and Gutter Barrier

BMP C232: Gravel Filter Berm

Purpose	A gravel filter berm is constructed on rights-of-way or traffic areas within a construction site to retain sediment by using a filter berm of gravel or crushed rock.
Conditions of Use	Where a temporary measure is needed to retain sediment from rights-of-way or in traffic areas on construction sites.
Design and Installation Specifications	• Berm material shall be $\frac{3}{4}$ to 3 inches in size, washed well-grade gravel or crushed rock with less than 5 percent fines. • Spacing of berms: – Every 300 feet on slopes less than 5 percent – Every 200 feet on slopes between 5 percent and 10 percent – Every 100 feet on slopes greater than 10 percent • Berm dimensions: – 1 foot high with 3H:1V side slopes – 8 linear feet per 1 cfs runoff based on the 10-year, 24-hour design storm
Maintenance Standards	• Regular inspection is required. Sediment shall be removed and filter material replaced as needed.

BMP C233: Silt Fence

Purpose	Use of a silt fence reduces the transport of coarse sediment from a construction site by providing a temporary physical barrier to sediment and reducing the runoff velocities of overland flow. See Figure 4.2.12 for details on silt fence construction.
Conditions of Use	Silt fence may be used downslope of all disturbed areas. • Silt fence shall prevent soil carried by runoff water from going beneath, through, or over the top of the silt fence, but shall allow the water to pass through the fence. • Silt fence is not intended to treat concentrated flows, nor is it intended to treat substantial amounts of overland flow. Convey any concentrated flows through the drainage system to a sediment pond. • Do not construct silt fences in streams or use in V-shaped ditches. Silt fences do not provide an adequate method of silt control for anything deeper than sheet or overland flow.




Figure 4.2.12 – Silt Fence

**Design and
Installation
Specifications**

- Use in combination with sediment basins or other BMPs.
- Maximum slope steepness (normal (perpendicular) to fence line) 1H:1V.
- Maximum sheet or overland flow path length to the fence of 100 feet.
- Do not allow flows greater than 0.5 cfs.
- The geotextile used shall meet the following standards. All geotextile properties listed below are minimum average roll values (i.e., the test result for any sampled roll in a lot shall meet or exceed the values shown in [Table 4.2.3](#)):

Table 4.2.3 Geotextile Standards	
Polymeric Mesh AOS (ASTM D4751)	0.60 mm maximum for slit film woven (#30 sieve). 0.30 mm maximum for all other geotextile types (#50 sieve). 0.15 mm minimum for all fabric types (#100 sieve).
Water Permittivity (ASTM D4491)	0.02 sec ⁻¹ minimum
Grab Tensile Strength (ASTM D4632)	180 lbs. Minimum for extra strength fabric. 100 lbs minimum for standard strength fabric.
Grab Tensile Strength (ASTM D4632)	30% maximum
Ultraviolet Resistance (ASTM D4355)	70% minimum

- Support standard strength fabrics with wire mesh, chicken wire, 2-inch x 2-inch wire, safety fence, or jute mesh to increase the strength of the fabric. Silt fence materials are available that have synthetic mesh backing attached.

- Filter fabric material shall contain ultraviolet ray inhibitors and stabilizers to provide a minimum of six months of expected usable construction life at a temperature range of 0°F. to 120°F.
- One-hundred percent biodegradable silt fence is available that is strong, long lasting, and can be left in place after the project is completed, if permitted by local regulations.
- Refer to [Figure 4.2.12](#) for standard silt fence details. Include the following standard Notes for silt fence on construction plans and specifications:
 1. The contractor shall install and maintain temporary silt fences at the locations shown in the Plans.
 2. Construct silt fences in areas of clearing, grading, or drainage prior to starting those activities.
 3. The silt fence shall have a 2-feet min. and a 2½-feet max. height above the original ground surface.
 4. The filter fabric shall be sewn together at the point of manufacture to form filter fabric lengths as required. Locate all sewn seams at support posts. Alternatively, two sections of silt fence can be overlapped, provided the Contractor can demonstrate, to the satisfaction of the Engineer, that the overlap is long enough and that the adjacent fence sections are close enough together to prevent silt laden water from escaping through the fence at the overlap.
 5. Attach the filter fabric on the up-slope side of the posts and secure with staples, wire, or in accordance with the manufacturer's recommendations. Attach the filter fabric to the posts in a manner that reduces the potential for tearing.
 6. Support the filter fabric with wire or plastic mesh, dependent on the properties of the geotextile selected for use. If wire or plastic mesh is used, fasten the mesh securely to the up-slope side of the posts with the filter fabric up-slope of the mesh.
 7. Mesh support, if used, shall consist of steel wire with a maximum mesh spacing of 2-inches, or a prefabricated polymeric mesh. The strength of the wire or polymeric mesh shall be equivalent to or greater than 180 lbs. grab tensile strength. The polymeric mesh must be as resistant to the same level of ultraviolet radiation as the filter fabric it supports.
 8. Bury the bottom of the filter fabric 4-inches min. below the ground surface. Backfill and tamp soil in place over the buried portion of the filter fabric, so that no flow can pass beneath the fence and scouring cannot occur. When wire or polymeric back-up support

mesh is used, the wire or polymeric mesh shall extend into the ground 3-inches min.

9. Drive or place the fence posts into the ground 18-inches min. A 12-inch min. depth is allowed if topsoil or other soft subgrade soil is not present and 18-inches cannot be reached. Increase fence post min. depths by 6 inches if the fence is located on slopes of 3H:1V or steeper and the slope is perpendicular to the fence. If required post depths cannot be obtained, the posts shall be adequately secured by bracing or guying to prevent overturning of the fence due to sediment loading.
 10. Use wood, steel or equivalent posts. The spacing of the support posts shall be a maximum of 6-feet. Posts shall consist of either:
 - Wood with dimensions of 2-inches by 2-inches wide min. and a 3-feet min. length. Wood posts shall be free of defects such as knots, splits, or gouges.
 - No. 6 steel rebar or larger.
 - ASTM A 120 steel pipe with a minimum diameter of 1-inch.
 - U, T, L, or C shape steel posts with a minimum weight of 1.35 lbs./ft.
 - Other steel posts having equivalent strength and bending resistance to the post sizes listed above.
 11. Locate silt fences on contour as much as possible, except at the ends of the fence, where the fence shall be turned uphill such that the silt fence captures the runoff water and prevents water from flowing around the end of the fence.
 12. If the fence must cross contours, with the exception of the ends of the fence, place gravel check dams perpendicular to the back of the fence to minimize concentrated flow and erosion. The slope of the fence line where contours must be crossed shall not be steeper than 3H:1V.
 - Gravel check dams shall be approximately 1-foot deep at the back of the fence. Gravel check dams shall be continued perpendicular to the fence at the same elevation until the top of the check dam intercepts the ground surface behind the fence.
 - Gravel check dams shall consist of crushed surfacing base course, gravel backfill for walls, or shoulder ballast. Gravel check dams shall be located every 10 feet along the fence where the fence must cross contours.
- Refer to [Figure 4.2.13](#) for slicing method details. Silt fence installation using the slicing method specifications:

1. The base of both end posts must be at least 2- to 4-inches above the top of the filter fabric on the middle posts for ditch checks to drain properly. Use a hand level or string level, if necessary, to mark base points before installation.
2. Install posts 3- to 4-feet apart in critical retention areas and 6- to 7-feet apart in standard applications.
3. Install posts 24-inches deep on the downstream side of the silt fence, and as close as possible to the filter fabric, enabling posts to support the filter fabric from upstream water pressure.
4. Install posts with the nipples facing away from the filter fabric.
5. Attach the filter fabric to each post with three ties, all spaced within the top 8-inches of the filter fabric. Attach each tie diagonally 45 degrees through the filter fabric, with each puncture at least 1-inch vertically apart. Each tie should be positioned to hang on a post nipple when tightening to prevent sagging.
6. Wrap approximately 6-inches of fabric around the end posts and secure with 3 ties.
7. No more than 24-inches of a 36-inch filter fabric is allowed above ground level.

Compact the soil immediately next to the filter fabric with the front wheel of the tractor, skid steer, or roller exerting at least 60 pounds per square inch. Compact the upstream side first and then each side twice for a total of four trips. Check and correct the silt fence installation for any deviation before compaction. Use a flat-bladed shovel to tuck fabric deeper into the ground if necessary.




Figure 4.2.13 – Silt Fence Installation by Slicing Method

Maintenance Standards

- Repair any damage immediately.
- Intercept and convey all evident concentrated flows uphill of the silt fence to a sediment pond.
- Check the uphill side of the fence for signs of the fence clogging and acting as a barrier to flow and then causing channelization of flows parallel to the fence. If this occurs, replace the fence or remove the trapped sediment.

- Remove sediment deposits when the deposit reaches approximately one-third the height of the silt fence, or install a second silt fence.
- Replace filter fabric that has deteriorated due to ultraviolet breakdown.

BMP C234: Vegetated Strip

Purpose

Vegetated strips reduce the transport of coarse sediment from a construction site by providing a temporary physical barrier to sediment and reducing the runoff velocities of overland flow.

Conditions of Use

- Vegetated strips may be used downslope of all disturbed areas.
- Vegetated strips are not intended to treat concentrated flows, nor are they intended to treat substantial amounts of overland flow. Any concentrated flows must be conveyed through the drainage system to a sediment pond. The only circumstance in which overland flow can be treated solely by a strip, rather than by a sediment pond, is when the following criteria are met (see [Table 4.2.4](#)):

Table 4.2.4 Contributing Drainage Area for Vegetated Strips		
Average Contributing area Slope	Average Contributing area Percent Slope	Max Contributing area Flowpath Length
1.5H:1V or flatter	67% or flatter	100 feet
2H:1V or flatter	50% or flatter	115 feet
4H:1V or flatter	25% or flatter	150 feet
6H:1V or flatter	16.7% or flatter	200 feet
10H:1V or flatter	10% or flatter	250 feet

Design and Installation Specifications

- The vegetated strip shall consist of a minimum of a 25-foot flowpath length continuous strip of dense vegetation with topsoil. Grass-covered, landscaped areas are generally not adequate because the volume of sediment overwhelms the grass. Ideally, vegetated strips shall consist of undisturbed native growth with a well-developed soil that allows for infiltration of runoff.
- The slope within the strip shall not exceed 4H:1V.
- The uphill boundary of the vegetated strip shall be delineated with clearing limits.

Maintenance Standards

- Any areas damaged by erosion or construction activity shall be seeded immediately and protected by mulch.
- If more than 5 feet of the original vegetated strip width has had vegetation removed or is being eroded, sod must be installed.
- If there are indications that concentrated flows are traveling across the buffer, surface water controls must be installed to reduce the flows

entering the buffer, or additional perimeter protection must be installed.

BMP C235: Wattles

Purpose

Wattles are temporary erosion and sediment control barriers consisting of straw, compost, or other material that is wrapped in biodegradable tubular plastic or similar encasing material. They reduce the velocity and can spread the flow of rill and sheet runoff, and can capture and retain sediment. Wattles are typically 8 to 10 inches in diameter and 25 to 30 feet in length. Wattles are placed in shallow trenches and staked along the contour of disturbed or newly constructed slopes. See [Figure 4.2.14](#) for typical construction details. WSDOT Standard Plan I-30.30-00 also provides information on Wattles (<http://www.wsdot.wa.gov/Design/Standards/Plans.htm#SectionI>)

Conditions of Use


- Use wattles:
 - In disturbed areas that require immediate erosion protection.
 - On exposed soils during the period of short construction delays, or over winter months.
 - On slopes requiring stabilization until permanent vegetation can be established.
- The material used dictates the effectiveness period of the wattle. Generally, Wattles are typically effective for one to two seasons.
- Prevent rilling beneath wattles by properly entrenching and abutting wattles together to prevent water from passing between them.

Design Criteria

- Install wattles perpendicular to the flow direction and parallel to the slope contour.
- Narrow trenches should be dug across the slope on contour to a depth of 3- to 5-inches on clay soils and soils with gradual slopes. On loose soils, steep slopes, and areas with high rainfall, the trenches should be dug to a depth of 5- to 7- inches, or 1/2 to 2/3 of the thickness of the wattle.
- Start building trenches and installing wattles from the base of the slope and work up. Spread excavated material evenly along the uphill slope and compacted using hand tamping or other methods.
- Construct trenches at intervals of 10- to 25-feet depending on the steepness of the slope, soil type, and rainfall. The steeper the slope the closer together the trenches.
- Install the wattles snugly into the trenches and abut tightly end to end. Do not overlap the ends.
- Install stakes at each end of the wattle, and at 4-foot centers along entire length of wattle.

***Maintenance
Standards***

- If required, install pilot holes for the stakes using a straight bar to drive holes through the wattle and into the soil.
- Wooden stakes should be approximately 3/4 x 3/4 x 24 inches min. Willow cuttings or 3/8-inch rebar can also be used for stakes.
- Stakes should be driven through the middle of the wattle, leaving 2 to 3 inches of the stake protruding above the wattle.
- Wattles may require maintenance to ensure they are in contact with soil and thoroughly entrenched, especially after significant rainfall on steep sandy soils.



NOTE:

1. Straw roll installation requires the placement and secure staking of the roll in a trench, 3"-5" (75-125mm) deep, dug on contour. runoff must not be allowed to run under or around roll.

Figure 4.2.14 – Wattles

***Approved as
Equivalent***

- Inspect the slope after significant storms and repair any areas where wattles are not tightly abutted or water has scoured beneath the wattles.

Ecology has approved products as able to meet the requirements of [BMP C235](#). The products did not pass through the Technology Assessment Protocol – Ecology (TAPE) process. Local jurisdictions may choose not to accept this product approved as equivalent, or may require additional testing prior to consideration for local use. The products are available for review on Ecology’s website at <http://www.ecy.wa.gov/programs/wq/stormwater/newtech/equivalent.html>

BMP C236: Vegetative Filtration

Purpose

Vegetative Filtration may be used in conjunction with [BMP C241](#) Temporary Sediment Ponds, [BMP C206](#) Level Spreader and a pumping system with surface intake to improve turbidity levels of stormwater discharges by filtering through existing vegetation where undisturbed forest floor duff layer or established lawn with thatch layer are present. Vegetative Filtration can also be used to infiltrate dewatering waste from foundations, vaults, and trenches as long as runoff does not occur.

Conditions of Use

- For every five acre of disturbed soil use one acre of grass field, farm pasture, or wooded area. Reduce or increase this area depending on project size, ground water table height, and other site conditions.
- Wetlands shall not be used for filtration.
- Do not use this BMP in areas with a high ground water table, or in areas that will have a high seasonal ground water table during the use of this BMP.
- This BMP may be less effective on soils that prevent the infiltration of the water, such as hard till.
- Using other effective source control measures throughout a construction site will prevent the generation of additional highly turbid water and may reduce the time period or area need for this BMP.
- Stop distributing water into the vegetated area if standing water or erosion results.

Design Criteria

- Find land adjacent to the project that has a vegetated field, preferably a farm field, or wooded area.
- If the project site does not contain enough vegetated field area consider obtaining permission from adjacent landowners (especially for farm fields).
- Install a pump and downstream distribution manifold depending on the project size. Generally, the main distribution line should reach 100 to 200-feet long (many large projects, or projects on tight soil, will

- Isolate and segregate pollutants as feasible. Convey the segregated pollutants to a sanitary sewer, process treatment, or a dead-end sump depending on available methods and applicable permit requirements.




Figure 2.2.6 – Enclose the Activity




Figure 2.2.7 – Cover the Activity

S419 BMPs for Mobile Fueling of Vehicles and Heavy Equipment

Description of Pollutant Sources: Mobile fueling, also known as fleet fueling, wet fueling, or wet hosing, is the practice of filling fuel tanks of vehicles by tank trucks that are driven to the yards or sites where the vehicles to be fueled are located. Regulators categorize diesel fuel as a

Note that some local fire departments may have restrictions on mobile fueling practices.

Class II Combustible Liquid, whereas they categorize gasoline as a Flammable Liquid.

Historically organizations conducted mobile fueling for off-road vehicles operated for extended periods in remote areas. This includes construction sites, logging operations, and farms. Some organizations conduct mobile fueling of on-road vehicles commercially in the State of Washington.

Pollutant Control Approach: Operators typically need proper training of the fueling operators, and the use of spill/drip control and reliable fuel transfer equipment with backup shutoff valving.

Applicable Operational BMPs:

Organizations and individuals conducting mobile fueling operations must implement the bulleted BMPs below. The operating procedures for the driver/operator should be simple, clear, effective, and their implementation verified by the organization liable for environmental and third party damage.

- Ensure that the local fire department approves all mobile fueling operations. Comply with local and Washington State fire codes.
- In fueling locations that are in close proximity to sensitive aquifers, designated wetlands, wetland buffers, or other waters of the State, approval by local jurisdictions is necessary to ensure compliance with additional local requirements.
- Ensure compliance with all 49 CFR 178 requirements for DOT 406 cargo tanker. Documentation from a Department of Transportation (DOT) Registered Inspector provides proof of compliance.
- Ensure the presence and the constant observation/monitoring of the driver/operator at the fuel transfer location at all times during fuel transfer and ensure implementation of the following procedures at the fuel transfer locations:
 - Locate the point of fueling at least 25 feet from the nearest storm sewer or inside an impervious containment with a volumetric holding capacity equal to or greater than 110 percent of the fueling tank volume, or covering the storm sewer to ensure no inflow of spilled or leaked fuel. Covers are not required for storm sewers that convey the inflow to a spill control separator approved by the local jurisdiction and the fire department. Potential spill/leak conveyance surfaces must be impervious and in good repair.
 - Place a drip pan, or an absorbent pad under each fueling location prior to and during all dispensing operations. The pan (must be liquid tight) and the absorbent pad must have a capacity of at least 5 gallons. There is no need to report spills retained in the drip pan or the pad.

- Manage the handling and operation of fuel transfer hoses and nozzle, drip pan(s), and absorbent pads as needed to prevent spills/leaks of fuel from reaching the ground, storm sewer, and receiving waters.
- Avoid extending the fueling hoses across a traffic lane without fluorescent traffic cones, or equivalent devices, conspicuously placed to block all traffic from crossing the fuel hose.
- Remove the fill nozzle and cease filling the tank when the automatic shut-off valve engages. Do not lock automatic shutoff fueling nozzles in the open position.
- Do not “top off” the fuel receiving equipment.
- Provide the driver/operator of the fueling vehicle with:
 - Adequate flashlights or other mobile lighting to view fuel fill openings with poor accessibility. Consult with local fire department for additional lighting requirements.
 - Two-way communication with his/her home base.
- Train the driver/operator annually in spill prevention and cleanup measures and emergency procedures. Make all employees aware of the significant liability associated with fuel spills.
- The responsible manager shall properly sign and date the fueling operating procedures. Distribute procedures to the operators, retain them in the organization files, and make them available in the event an authorized government agency requests a review.
- Immediately notify the local fire department (911) and the appropriate regional office of Ecology in the event of any spill entering surface or ground waters. Establish a “call down list” to ensure the rapid and proper notification of management and government officials should any significant amount of product be lost off-site. Keep the list in a protected but readily accessible location in the mobile fueling truck. The “call down list” should also pre-identify spill response contractors available in the area to ensure the rapid removal of significant product spillage into the environment.
- Maintain a minimum of the following spill clean-up materials in all fueling vehicles, that are readily available for use:
 - Non-water absorbents capable of absorbing at least 15 gallons of diesel fuel.
 - A storm drain plug or cover kit.
 - A non-water absorbent containment boom of a minimum 10 feet in length with a 12-gallon minimum absorbent capacity.
 - A non-spark generating shovel (a steel shovels could generate a spark and cause an explosion in the right environment around a spill).

- Two, five-gallon buckets with lids.
- Use automatic shutoff nozzles for dispensing the fuel. Replace automatic shut-off nozzles as recommended by the manufacturer.
- Maintain and replace equipment on fueling vehicles, particularly hoses and nozzles, at established intervals to prevent failures.

Applicable Structural Source Control BMPs: Include the following fuel transfer site components:

- Automatic fuel transfer shut-off nozzles.
- An adequate lighting system at the filling point.

S420 BMPs for Painting/ Finishing /Coating of Vehicles/Boats/ Buildings/ Equipment

Description of Pollutant Sources: Surface preparation and the application of paints, finishes, and/or coatings to vehicles, boats, buildings, and/or equipment outdoors can be sources of pollutants. Potential pollutants include organic compounds, oils and greases, heavy metals, and suspended solids.

Pollutant Control Approach: Cover and contain painting and sanding operations and apply good housekeeping and preventive maintenance practices to prevent the contamination of stormwater with painting over sprays and grit from sanding.

Applicable Operational BMPs:

- Train employees in the careful application of paints, finishes, and coatings to reduce misuse and over spray. Use drop cloths underneath outdoor painting, scraping, sandblasting work, and properly clean and temporarily store collected debris daily.
- Do not conduct spraying, blasting, or sanding activities over open water or where wind may blow paint into water.
- Wipe up spills with rags and other absorbent materials immediately. Do not hose down the area to a storm sewer, receiving water, or conveyance ditch.
- On marine dock areas sweep rather than hose down debris. Collect any hose water generated and convey to appropriate treatment and disposal.
- Use an effective runoff control device if dust, grit, washwater, or other pollutants may escape the work area and enter a catch basin. The containment device(s) must be in place at the beginning of the workday. Collect contaminated runoff and solids and properly dispose of such wastes before removing the containment device(s) at the end of the workday.

S425 BMPs for Soil Erosion and Sediment Control at Industrial Sites

Description of Pollutant Sources: Industrial activities on soil areas; exposed and disturbed soils; steep grading; etc. can be sources of sediments that can contaminate stormwater runoff.

Pollutant Control Approach: Limit the exposure of erodible soil, stabilize, or cover erodible soil where necessary to prevent erosion, and/or provide treatment for stormwater contaminated with TSS caused by eroded soil.

Applicable BMPs:

Cover Practice Options:

- Vegetative cover such as grass, trees, shrubs, on erodible soil areas.
- Covering with mats such as clear plastic, jute, synthetic fiber.
- Preservation of natural vegetation including grass, trees, shrubs, and vines.

Structural Practice Options:

- Vegetated swale
- Dike
- Silt fence
- Check dam
- Gravel filter berm
- Sedimentation basin
- Proper grading.

(For design information refer to Volume II, “Standards and Specifications for BMPs”).

S426 BMPs for Spills of Oil and Hazardous Substances

Description of Pollutant Sources: Federal law requires owners or operators of facilities engaged in drilling, producing, gathering, storing, processing, transferring, distributing, refining, or consuming oil and/or oil products to have a Spill Prevention and Emergency Cleanup Plan (SPECPlan). The SPECPlan is required if the above ground storage capacity of the facility, is 1,320 gallons or more of oil. Additionally, the SPECPlan is required if any single container with a capacity in excess of 660 gallons and which, due to their location, could reasonably be expected to discharge oil in harmful quantities, as defined in 40 CFR Part 110, into or upon the navigable waters of the United States or adjoining shorelines {40 CFR 112.1 (b)}. Onshore and offshore facilities, which, due to their location, could not reasonably be expected to discharge oil into or upon

the navigable waters of the United States or adjoining shorelines are exempt from these regulations {40 CFR 112.1(1)(i)}. State Law requires owners of businesses that produce dangerous wastes to have a SPECP. These businesses should refer to [Appendix IV-D R.6](#). The federal definition of oil is oil of any kind or any form, including, but not limited to petroleum, fuel oil, sludge, oil refuse, and oil mixed with wastes other than dredged spoil.

Pollutant Control Approach: Maintain, update, and implement a Spill Prevention and Emergency Cleanup Plan.

Applicable Operational BMPs: The businesses and public agencies identified in [Appendix IV-A](#) required to prepare and implement a Spill Prevention and Emergency Cleanup Plan shall implement the following:

- Prepare a Spill Prevention and Emergency Cleanup Plan (SPECP), which includes:
 - A description of the facility including the owner's name and address.
 - The nature of the activity at the facility.
 - The general types of chemicals used or stored at the facility.
 - A site plan showing the location of storage areas for chemicals, the locations of storm drains, the areas draining to them, and the location and description of any devices to stop spills from leaving the site such as positive control valves.
 - Cleanup procedures.
 - Notification procedures used in the event of a spill, such as notifying key personnel. Agencies such as Ecology, local fire department, Washington State Patrol, and the local Sewer Authority, shall be notified.
 - The name of the designated person with overall spill cleanup and notification responsibility.
- Train key personnel in the implementation of the SPECP. Prepare a summary of the plan and post it at appropriate points in the building, identifying the spill cleanup coordinators, location of cleanup kits, and phone numbers of regulatory agencies to contact in the event of a spill.
- Update the SPECP regularly.
- Immediately notify Ecology, the local jurisdiction, and the local Sewer Authority if a spill may reach sanitary or storm sewers, ground water, or surface water, in accordance with federal and Ecology spill reporting requirements.

- Immediately clean up spills. Do not use emulsifiers for cleanup unless there is an appropriate disposal method for the resulting oily wastewater. Do not wash absorbent material down a floor drain or into a storm sewer.
- Locate emergency spill containment and cleanup kit(s) in high-potential spill areas. The contents of the kit shall be appropriate for the type and quantities of chemical liquids stored at the facility.

Recommended Additional Operational BMP: Spill kits should include appropriately lined drums, absorbent pads, and granular or powdered materials for neutralizing acids or alkaline liquids where applicable. In fueling areas: Package absorbent material in small bags for easy use and make available small drums for storage of absorbent and/or used absorbent. Deploy spill kits in a manner that allows rapid access and use by employees.

S427 BMPs for Storage of Liquid, Food Waste, or Dangerous Waste Containers

Description of Pollutant Sources: Steel and plastic drums with volumetric capacities of 55 gallons or less are typically used at industrial facilities for container storage of liquids and powders. The BMPs specified below apply to container(s) located outside a building. Use these BMPs when temporarily storing accumulated food wastes, vegetable or animal grease, used oil, liquid feedstock, cleaning chemicals, or Dangerous Wastes (liquid or solid). These BMPs do not apply when Ecology has permitted the business to store the wastes ([Appendix IV-D R.4](#)). Leaks and spills of pollutant materials during handling and storage are the primary sources of pollutants. Oil and grease, acid/alkali pH, BOD, COD are potential pollutant constituents.

Pollutant Control Approach: Store containers in impervious containment under a roof, or other appropriate cover, or in a building. When collection trucks directly pick up roll-containers, ensure a filet is on both sides of the curb to facilitate moving the dumpster. For storage areas on-site for less than 30 days, consider using a portable temporary secondary system like that shown in [Figure 2.2.8](#) in lieu of a permanent system as described above.

This page left intentionally blank.

Appendix C - Site Inspection Form

This page left intentionally blank.

Construction Stormwater Site Inspection Form

Project Name _____ Permit # _____ Inspection Date _____ Time _____

Name of Certified Erosion Sediment Control Lead (CESCL) or qualified inspector if *less than one acre*

Print Name: _____

Approximate rainfall amount since the last inspection (in inches): _____

Approximate rainfall amount in the last 24 hours (in inches): _____

Current Weather Clear ☐ Cloudy ☐ Mist ☐ Rain ☐ Wind ☐ Fog ☐

A. Type of inspection: Weekly ☐ Post Storm Event ☐ Other ☐

B. Phase of Active Construction (check all that apply):

Pre Construction/installation of erosion/sediment controls

Concrete pours

Offsite improvements

☐

Clearing/Demo/Grading

☐

Vertical

Construction/buildings

☐

Site temporary stabilized

☐

Infrastructure/storm/roads

☐

Utilities

☐

Final stabilization

☐☐☐

C. Questions:

1. Were all areas of construction and discharge points inspected? Yes _____ No _____
2. Did you observe the presence of suspended sediment, turbidity, discoloration, or oil sheen Yes _____ No _____
3. Was a water quality sample taken during inspection? (*refer to permit conditions S4 & S5*) Yes _____ No _____
4. Was there a turbid discharge 250 NTU or greater, or Transparency 6 cm or less? * Yes _____ No _____
5. If yes to #4 was it reported to Ecology? Yes _____ No _____
6. Is pH sampling required? pH range required is 6.5 to 8.5. Yes _____ No _____

If answering yes to a discharge, describe the event. Include when, where, and why it happened; what action was taken, and when.

*If answering yes to # 4 record NTU/Transparency with continual sampling daily until turbidity is 25 NTU or less/ transparency is 33 cm or greater.

Sampling Results: _____ Date: _____

Parameter	Method (circle one)	Result			Other/Note
		NTU	cm	pH	
Turbidity	tube, meter, laboratory				
pH	Paper, kit, meter				

Construction Stormwater Site Inspection Form

D. Check the observed status of all items. Provide "Action Required" details and dates.

Element #	Inspection	BMPs Inspected			BMP needs maintenance	BMP failed	Action required (describe in section F)
		yes	no	n/a			
1 Clearing Limits	Before beginning land disturbing activities are all clearing limits, natural resource areas (streams, wetlands, buffers, trees) protected with barriers or similar BMPs? (high visibility recommended)						
2 Construction Access	Construction access is stabilized with quarry spalls or equivalent BMP to prevent sediment from being tracked onto roads?						
	Sediment tracked onto the road way was cleaned thoroughly at the end of the day or more frequent as necessary.						
3 Control Flow Rates	Are flow control measures installed to control stormwater volumes and velocity during construction and do they protect downstream properties and waterways from erosion?						
	If permanent infiltration ponds are used for flow control during construction, are they protected from siltation?						
4 Sediment Controls	All perimeter sediment controls (e.g. silt fence, wattles, compost socks, berms, etc.) installed, and maintained in accordance with the Stormwater Pollution Prevention Plan (SWPPP).						
	Sediment control BMPs (sediment ponds, traps, filters etc.) have been constructed and functional as the first step of grading.						
	Stormwater runoff from disturbed areas is directed to sediment removal BMP.						
5 Stabilize Soils	Have exposed un-worked soils been stabilized with effective BMP to prevent erosion and sediment deposition?						

Construction Stormwater Site Inspection Form

Element #	Inspection	BMPs Inspected			BMP needs maintenance	BMP failed	Action required (describe in section F)
		yes	no	n/a			
5 Stabilize Soils Cont.	Are stockpiles stabilized from erosion, protected with sediment trapping measures and located away from drain inlet, waterways, and drainage channels?						
	Have soils been stabilized at the end of the shift, before a holiday or weekend if needed based on the weather forecast?						
6 Protect Slopes	Has stormwater and ground water been diverted away from slopes and disturbed areas with interceptor dikes, pipes and or swales?						
	Is off-site storm water managed separately from stormwater generated on the site?						
	Is excavated material placed on uphill side of trenches consistent with safety and space considerations?						
	Have check dams been placed at regular intervals within constructed channels that are cut down a slope?						
7 Drain Inlets	Storm drain inlets made operable during construction are protected.						
	Are existing storm drains within the influence of the project protected?						
8 Stabilize Channel and Outlets	Have all on-site conveyance channels been designed, constructed and stabilized to prevent erosion from expected peak flows?						
	Is stabilization, including armoring material, adequate to prevent erosion of outlets, adjacent stream banks, slopes and downstream conveyance systems?						
9 Control Pollutants	Are waste materials and demolition debris handled and disposed of to prevent contamination of stormwater?						
	Has cover been provided for all chemicals, liquid products, petroleum products, and other material?						
	Has secondary containment been provided capable of containing 110% of the volume?						
	Were contaminated surfaces cleaned immediately after a spill incident?						
	Were BMPs used to prevent contamination of stormwater by a pH modifying sources?						

Construction Stormwater Site Inspection Form

Element #	Inspection	BMPs Inspected			BMP needs maintenance	BMP failed	Action required (describe in section F)
		yes	no	n/a			
9 Cont.	Wheel wash wastewater is handled and disposed of properly.						
10 Control Dewatering	Concrete washout in designated areas. No washout or excess concrete on the ground.						
	Dewatering has been done to an approved source and in compliance with the SWPPP.						
	Were there any clean non turbid dewatering discharges?						
11 Maintain BMP	Are all temporary and permanent erosion and sediment control BMPs maintained to perform as intended?						
12 Manage the Project	Has the project been phased to the maximum degree practicable?						
	Has regular inspection, monitoring and maintenance been performed as required by the permit?						
	Has the SWPPP been updated, implemented and records maintained?						
13 Protect LID	Is all Bioretention and Rain Garden Facilities protected from sedimentation with appropriate BMPs?						
	Is the Bioretention and Rain Garden protected against over compaction of construction equipment and foot traffic to retain its infiltration capabilities?						
	Permeable pavements are clean and free of sediment and sediment laden-water runoff. Muddy construction equipment has not been on the base material or pavement.						
	Have soiled permeable pavements been cleaned of sediments and pass infiltration test as required by stormwater manual methodology?						
	Heavy equipment has been kept off existing soils under LID facilities to retain infiltration rate.						

E. Check all areas that have been inspected. ✓

All in place BMPs ☐ All disturbed soils ☐ All concrete wash out area ☐ All material storage areas ☐
 All discharge locations ☐ All equipment storage areas ☐ All construction entrances/exits ☐

Construction Stormwater Site Inspection Form

F. Elements checked "Action Required" (section D) describe corrective action to be taken. List the element number; be specific on location and work needed. Document, initial, and date when the corrective action has been completed and inspected.

Element #	Description and Location	Action Required	Completion Date	Initials

Attach additional page if needed

Sign the following certification:

"I certify that this report is true, accurate, and complete, to the best of my knowledge and belief"

Inspected by: (print) _____ (Signature) _____ Date: _____

Title/Qualification of Inspector: _____

This page left intentionally blank.

Appendix D - Construction Stormwater General Permit (CSWGP)

This page left intentionally blank.

Issuance Date: November 18, 2020
Effective Date: January 1, 2021
Expiration Date: December 31, 2025

CONSTRUCTION STORMWATER GENERAL PERMIT

National Pollutant Discharge Elimination System (NPDES) and State Waste Discharge
General Permit for Stormwater Discharges Associated with Construction Activity

State of Washington
Department of Ecology
Olympia, Washington 98504

In compliance with the provisions of
Chapter 90.48 Revised Code of Washington
(State of Washington Water Pollution Control Act)
and
Title 33 United States Code, Section 1251 et seq.
The Federal Water Pollution Control Act (The Clean Water Act)

Until this permit expires, is modified, or revoked, Permittees that have properly
obtained coverage under this general permit are authorized to discharge in accordance
with the special and general conditions that follow.



Vincent McGowan, P.E.
Water Quality Program Manager
Washington State Department of Ecology

TABLE OF CONTENTS

LIST OF TABLES	ii
SUMMARY OF PERMIT REPORT SUBMITTALS	1
SPECIAL CONDITIONS	3
S1. Permit Coverage	3
S2. Application Requirements	7
S3. Compliance with Standards	9
S4. Monitoring Requirements, Benchmarks, and Reporting Triggers	10
S5. Reporting and Recordkeeping Requirements	17
S6. Permit Fees	20
S7. Solid and Liquid Waste Disposal	20
S8. Discharges to 303(D) or TMDL Waterbodies	20
S9. Stormwater Pollution Prevention Plan	23
S10. Notice Of Termination	32
GENERAL CONDITIONS	34
G1. Discharge Violations	34
G2. Signatory Requirements	34
G3. Right of Inspection and Entry	35
G4. General Permit Modification and Revocation	35
G5. Revocation of Coverage Under tPermit	35
G6. Reporting a Cause for Modification	36
G7. Compliance with Other Laws and Statutes	36
G8. Duty to Reapply	36
G9. Removed Substance	36
G10. Duty to Provide Information	36
G11. Other Requirements of 40 CFR	37
G12. Additional Monitoring	37
G13. Penalties for Violating Permit Conditions	37
G14. Upset	37
G15. Property Rights	37
G16. Duty to Comply	37
G17. Toxic Pollutants	38
G18. Penalties for Tampering	38
G19. Reporting Planned Changes	38
G20. Reporting Other Information	38
G21. Reporting Anticipated Non-Compliance	38

G22.	Requests to Be Excluded From Coverage Under the Permit	39
G23.	Appeals.....	39
G24.	Severability.....	39
G25.	Bypass Prohibited	39
APPENDIX A – DEFINITIONS.....		42
APPENDIX B – ACRONYMS.....		50

LIST OF TABLES

Table 1	Summary of Required Submittals.....	1
Table 2	Summary of Required On-site Documentation	2
Table 3	Summary of Primary Monitoring Requirements	12
Table 4	Monitoring and Reporting Requirements	14
Table 5	Turbidity, Fine Sediment & Phosphorus Sampling and Limits for 303(d)-Listed Waters	22
Table 6	pH Sampling and Limits for 303(d)-Listed Waters.....	22

SUMMARY OF PERMIT REPORT SUBMITTALS

Refer to the Special and General Conditions within this permit for additional submittal requirements. Appendix A provides a list of definitions. Appendix B provides a list of acronyms.

Table 1 Summary of Required Submittals

Permit Section	Submittal	Frequency	First Submittal Date
S5.A and S8	High Turbidity/Transparency Phone Reporting	As Necessary	Within 24 hours
S5.B	Discharge Monitoring Report	Monthly*	Within 15 days following the end of each month
S5.F and S8	Noncompliance Notification – Telephone Notification	As necessary	Within 24 hours
S5.F	Noncompliance Notification – Written Report	As necessary	Within 5 Days of non-compliance
S9.D	Request for Chemical Treatment Form	As necessary	Written approval from Ecology is required prior to using chemical treatment (with the exception of dry ice, CO ₂ or food grade vinegar to adjust pH)
G2	Notice of Change in Authorization	As necessary	
G6	Permit Application for Substantive Changes to the Discharge	As necessary	
G8	Application for Permit Renewal	1/permit cycle	No later than 180 days before expiration
S2.A	Notice of Permit Transfer	As necessary	
G19	Notice of Planned Changes	As necessary	
G21	Reporting Anticipated Non-compliance	As necessary	

NOTE: *Permittees must submit electronic Discharge Monitoring Reports (DMRs) to the Washington State Department of Ecology monthly, regardless of site discharge, for the full duration of permit coverage. Refer to Section S5.B of this General Permit for more specific information regarding DMRs.

Table 2 Summary of Required On-site Documentation

Document Title	Permit Conditions
Permit Coverage Letter	See Conditions S2, S5
Construction Stormwater General Permit (CSWGP)	See Conditions S2, S5
Site Log Book	See Conditions S4, S5
Stormwater Pollution Prevention Plan (SWPPP)	See Conditions S5, S9
Site Map	See Conditions S5, S9

SPECIAL CONDITIONS

S1. PERMIT COVERAGE

A. Permit Area

This Construction Stormwater General Permit (CSWGP) covers all areas of Washington State, except for federal operators and Indian Country as specified in Special Condition S1.E.3 and 4.

B. Operators Required to Seek Coverage Under this General Permit

1. Operators of the following construction activities are required to seek coverage under this CSWGP:
 - a. Clearing, grading and/or excavation that results in the disturbance of one or more acres (including off-site disturbance acreage related to construction-support activity as authorized in S1.C.2) and discharges stormwater to surface waters of the State; and clearing, grading and/or excavation on sites smaller than one acre that are part of a larger common plan of development or sale, if the common plan of development or sale will ultimately disturb one acre or more and discharge stormwater to surface waters of the State.
 - i. This category includes forest practices (including, but not limited to, class IV conversions) that are part of a construction activity that will result in the disturbance of one or more acres, and discharge to surface waters of the State (that is, forest practices that prepare a site for construction activities); and
 - b. Any size construction activity discharging stormwater to waters of the State that the Washington State Department of Ecology (Ecology):
 - i. Determines to be a significant contributor of pollutants to waters of the State of Washington.
 - ii. Reasonably expects to cause a violation of any water quality standard.
2. Operators of the following activities are not required to seek coverage under this CSWGP (unless specifically required under Special Condition S1.B.1.b, above):
 - a. Construction activities that discharge all stormwater and non-stormwater to groundwater, sanitary sewer, or combined sewer, and have no point source discharge to either surface water or a storm sewer system that drains to surface waters of the State.
 - b. Construction activities covered under an Erosivity Waiver (Special Condition S1.F).
 - c. Routine maintenance that is performed to maintain the original line and grade, hydraulic capacity, or original purpose of a facility.

C. Authorized Discharges

1. ***Stormwater Associated with Construction Activity.*** Subject to compliance with the terms and conditions of this permit, Permittees are authorized to discharge stormwater associated with construction activity to surface waters of the State or to a storm sewer system that drains to surface waters of the State. (Note that “surface waters of the

State” may exist on a construction site as well as off site; for example, a creek running through a site.)

2. ***Stormwater Associated with Construction Support Activity.*** This permit also authorizes stormwater discharge from support activities related to the permitted construction site (for example, an on-site portable rock crusher, off-site equipment staging yards, material storage areas, borrow areas, etc.) provided:
 - a. The support activity relates directly to the permitted construction site that is required to have an NPDES permit; and
 - b. The support activity is not a commercial operation serving multiple unrelated construction projects, and does not operate beyond the completion of the construction activity; and
 - c. Appropriate controls and measures are identified in the Stormwater Pollution Prevention Plan (SWPPP) for the discharges from the support activity areas.
3. ***Non-Stormwater Discharges.*** The categories and sources of non-stormwater discharges identified below are authorized conditionally, provided the discharge is consistent with the terms and conditions of this permit:
 - a. Discharges from fire-fighting activities.
 - b. Fire hydrant system flushing.
 - c. Potable water, including uncontaminated water line flushing.
 - d. Hydrostatic test water.
 - e. Uncontaminated air conditioning or compressor condensate.
 - f. Uncontaminated groundwater or spring water.
 - g. Uncontaminated excavation dewatering water (in accordance with S9.D.10).
 - h. Uncontaminated discharges from foundation or footing drains.
 - i. Uncontaminated or potable water used to control dust. Permittees must minimize the amount of dust control water used.
 - j. Routine external building wash down that does not use detergents.
 - k. Landscape irrigation water.

The SWPPP must adequately address all authorized non-stormwater discharges, except for discharges from fire-fighting activities, and must comply with Special Condition S3. At a minimum, discharges from potable water (including water line flushing), fire hydrant system flushing, and pipeline hydrostatic test water must undergo the following: dechlorination to a concentration of 0.1 parts per million (ppm) or less, and pH adjustment to within 6.5 – 8.5 standard units (su), if necessary.

D. Prohibited Discharges

The following discharges to waters of the State, including groundwater, are prohibited:

1. Concrete wastewater
2. Wastewater from washout and clean-up of stucco, paint, form release oils, curing compounds and other construction materials.
3. Process wastewater as defined by 40 Code of Federal Regulations (CFR) 122.2 (See Appendix A of this permit).
4. Slurry materials and waste from shaft drilling, including process wastewater from shaft drilling for construction of building, road, and bridge foundations unless managed according to Special Condition S9.D.9.j.
5. Fuels, oils, or other pollutants used in vehicle and equipment operation and maintenance.
6. Soaps or solvents used in vehicle and equipment washing.
7. Wheel wash wastewater, unless managed according to Special Condition S9.D.9.
8. Discharges from dewatering activities, including discharges from dewatering of trenches and excavations, unless managed according to Special Condition S9.D.10.

E. Limits on Coverage

Ecology may require any discharger to apply for and obtain coverage under an individual permit or another more specific general permit. Such alternative coverage will be required when Ecology determines that this CSWGP does not provide adequate assurance that water quality will be protected, or there is a reasonable potential for the project to cause or contribute to a violation of water quality standards.

The following stormwater discharges are not covered by this permit:

1. Post-construction stormwater discharges that originate from the site after completion of construction activities and the site has undergone final stabilization.
2. Non-point source silvicultural activities such as nursery operations, site preparation, reforestation and subsequent cultural treatment, thinning, prescribed burning, pest and fire control, harvesting operations, surface drainage, or road construction and maintenance, from which there is natural runoff as excluded in 40 CFR Subpart 122.
3. Stormwater from any federal operator.
4. Stormwater from facilities located on **Indian Country** as defined in 18 U.S.C. §1151, except portions of the Puyallup Reservation as noted below.

Indian Country includes:

- a. All land within any Indian Reservation notwithstanding the issuance of any patent, and, including rights-of-way running through the reservation. This includes all federal, tribal, and Indian and non-Indian privately owned land within the reservation.
- b. All off-reservation Indian allotments, the Indian titles to which have not been extinguished, including rights-of-way running through the same.
- c. All off-reservation federal trust lands held for Native American Tribes.

Puyallup Exception: Following the *Puyallup Tribes of Indians Land Settlement Act of 1989*, 25 U.S.C. §1773; the permit does apply to land within the Puyallup Reservation except for discharges to surface water on land held in trust by the federal government.

5. Stormwater from any site covered under an existing NPDES individual permit in which stormwater management and/or treatment requirements are included for all stormwater discharges associated with construction activity.
6. Stormwater from a site where an applicable Total Maximum Daily Load (TMDL) requirement specifically precludes or prohibits discharges from construction activity.

F. Erosivity Waiver

Construction site operators may qualify for an Erosivity Waiver from the CSWGP if the following conditions are met:

1. The site will result in the disturbance of fewer than five (5) acres and the site is not a portion of a common plan of development or sale that will disturb five (5) acres or greater.
2. Calculation of Erosivity “R” Factor and Regional Timeframe:
 - a. The project’s calculated rainfall erosivity factor (“R” Factor) must be less than five (5) during the period of construction activity, (See the CSWGP homepage <http://www.ecy.wa.gov/programs/wq/stormwater/construction/index.html> for a link to the EPA’s calculator and step by step instructions on computing the “R” Factor in the *EPA Erosivity Waiver Fact Sheet*). The period of construction activity starts when the land is first disturbed and ends with final stabilization. In addition:
 - b. The entire period of construction activity must fall within the following timeframes:
 - i. For sites west of the Cascades Crest: June 15 – September 15.
 - ii. For sites east of the Cascades Crest, excluding the Central Basin: June 15 – October 15.
 - iii. For sites east of the Cascades Crest, within the Central Basin: no timeframe restrictions apply. The Central Basin is defined as the portions of Eastern Washington with mean annual precipitation of less than 12 inches. For a map of the Central Basin (Average Annual Precipitation Region 2), refer to: <http://www.ecy.wa.gov/programs/wq/stormwater/construction/resourcesguidance.html>.
3. Construction site operators must submit a complete Erosivity Waiver certification form at least one week before disturbing the land. Certification must include statements that the operator will:
 - a. Comply with applicable local stormwater requirements; and
 - b. Implement appropriate erosion and sediment control BMPs to prevent violations of water quality standards.
4. This waiver is not available for facilities declared significant contributors of pollutants as defined in Special Condition S1.B.1.b or for any size construction activity that could

reasonably expect to cause a violation of any water quality standard as defined in Special Condition S1.B.1.b.ii.

5. This waiver does not apply to construction activities which include non-stormwater discharges listed in Special Condition S1.C.3.
6. If construction activity extends beyond the certified waiver period for any reason, the operator must either:
 - a. Recalculate the rainfall erosivity “R” factor using the original start date and a new projected ending date and, if the “R” factor is still under 5 *and* the entire project falls within the applicable regional timeframe in Special Condition S1.F.2.b, complete and submit an amended waiver certification form before the original waiver expires; *or*
 - b. Submit a complete permit application to Ecology in accordance with Special Condition S2.A and B before the end of the certified waiver period.

S2. APPLICATION REQUIREMENTS

A. Permit Application Forms

1. ***Notice of Intent Form***

- a. Operators of new or previously unpermitted construction activities must submit a complete and accurate permit application (Notice of Intent, or NOI) to Ecology.
- b. Operators must apply using the electronic application form (NOI) available on Ecology’s website (<http://ecy.wa.gov/programs/wq/stormwater/construction/index.html>). Permittees unable to submit electronically (for example, those who do not have an internet connection) must contact Ecology to request a waiver and obtain instructions on how to obtain a paper NOI.

Department of Ecology
Water Quality Program - Construction Stormwater
PO Box 47696
Olympia, Washington 98504-7696

- c. The operator must submit the NOI at least 60 days before discharging stormwater from construction activities and must submit it prior to the date of the first public notice (See Special Condition S2.B, below, for details). The 30-day public comment period begins on the publication date of the second public notice. Unless Ecology responds to the complete application in writing, coverage under the general permit will automatically commence on the 31st day following receipt by Ecology of a *completed* NOI, or the issuance date of this permit, whichever is later; unless Ecology specifies a later date in writing as required by WAC173-226-200(2). See S8.B for Limits on Coverage for New Discharges to TMDL or 303(d)-Listed Waters.
- d. If an applicant intends to use a Best Management Practice (BMP) selected on the basis of Special Condition S9.C.4 (“demonstrably equivalent” BMPs), the applicant must notify Ecology of its selection as part of the NOI. In the event the applicant selects BMPs after submission of the NOI, the applicant must provide notice of the

selection of an equivalent BMP to Ecology at least 60 days before intended use of the equivalent BMP.

- e. Applicants must notify Ecology if they are aware of contaminated soils and/or groundwater associated with the construction activity. Provide detailed information with the NOI (as known and readily available) on the nature and extent of the contamination (concentrations, locations, and depth), as well as pollution prevention and/or treatment BMPs proposed to control the discharge of soil and/or groundwater contaminants in stormwater. Examples of such detail may include, but are not limited to:
 - i. List or table of all known contaminants with laboratory test results showing concentration and depth,
 - ii. Map with sample locations,
 - iii. Related portions of the Stormwater Pollution Prevention Plan (SWPPP) that address the management of contaminated and potentially contaminated construction stormwater and dewatering water,
 - iv. Dewatering plan and/or dewatering contingency plan.

2. *Transfer of Coverage Form*

The Permittee can transfer current coverage under this permit to one or more new operators, including operators of sites within a Common Plan of Development, provided:

- i. The Permittee submits a complete Transfer of Coverage Form to Ecology, signed by the current and new discharger and containing a specific date for transfer of permit responsibility, coverage and liability (including any Administrative Orders associated with the permit); and
- ii. Ecology does not notify the current discharger and new discharger of intent to revoke coverage under the general permit. If this notice is not given, the transfer is effective on the date specified in the written agreement.

When a current discharger (Permittee) transfers a portion of a permitted site, the current discharger must also indicate the remaining permitted acreage after the transfer. Transfers do not require public notice.

3. *Modification of Coverage Form*

Permittees must notify Ecology regarding any changes to the information provided on the NOI by submitting an Update/Modification of Permit Coverage form in accordance with General Conditions G6 and G19. Examples of such changes include, but are not limited to:

- i. Changes to the Permittee's mailing address,
- ii. Changes to the on-site contact person information, and
- iii. Changes to the area/acreage affected by construction activity.

B. Public Notice

For new or previously unpermitted construction activities, the applicant must publish a public notice at least one time each week for two consecutive weeks, at least 7 days apart, in a newspaper with general circulation in the county where the construction is to take place. The notice must be run after the NOI has been submitted and must contain:

1. A statement that *“The applicant is seeking coverage under the Washington State Department of Ecology’s Construction Stormwater NPDES and State Waste Discharge General Permit.”*
2. The name, address, and location of the construction site.
3. The name and address of the applicant.
4. The type of construction activity that will result in a discharge (for example, residential construction, commercial construction, etc.), and the total number of acres to be disturbed over the lifetime of the project.
5. The name of the receiving water(s) (that is, the surface water(s) to which the site will discharge), or, if the discharge is through a storm sewer system, the name of the operator of the system and the receiving water(s) the system discharges to.
6. The statement: *Any persons desiring to present their views to the Washington State Department of Ecology regarding this application, or interested in Ecology’s action on this application, may notify Ecology in writing no later than 30 days of the last date of publication of this notice. Ecology reviews public comments and considers whether discharges from this project would cause a measurable change in receiving water quality, and, if so, whether the project is necessary and in the overriding public interest according to Tier II antidegradation requirements under WAC 173-201A-320. Comments can be submitted to: Department of Ecology, PO Box 47696, Olympia, Washington 98504-7696 Attn: Water Quality Program, Construction Stormwater.*

S3. COMPLIANCE WITH STANDARDS

- A. Discharges must not** cause or contribute to a violation of surface water quality standards (Chapter 173-201A WAC), groundwater quality standards (Chapter 173-200 WAC), sediment management standards (Chapter 173-204 WAC), and human health-based criteria in the Federal water quality criteria applicable to Washington. (40 CFR Part 131.45) Discharges that are not in compliance with these standards are prohibited.
- B. Prior to the discharge** of stormwater and non-stormwater to waters of the State, the Permittee must apply All Known, Available, and Reasonable methods of prevention, control, and Treatment (AKART). This includes the preparation and implementation of an adequate SWPPP, with all appropriate BMPs installed and maintained in accordance with the SWPPP and the terms and conditions of this permit.
- C. Ecology presumes** that a Permittee complies with water quality standards unless discharge monitoring data or other site-specific information demonstrates that a discharge causes or contributes to a violation of water quality standards, when the Permittee complies with the following conditions. The Permittee must fully:

1. Comply with all permit conditions, including; planning, sampling, monitoring, reporting, and recordkeeping conditions.
 2. Implement stormwater BMPs contained in stormwater management manuals published or approved by Ecology, or BMPs that are demonstrably equivalent to BMPs contained in stormwater management manuals published or approved by Ecology, including the proper selection, implementation, and maintenance of all applicable and appropriate BMPs for on-site pollution control. (For purposes of this section, the stormwater manuals listed in Appendix 10 of the *Phase I Municipal Stormwater Permit* are approved by Ecology.)
- D. Where construction sites** also discharge to groundwater, the groundwater discharges must also meet the terms and conditions of this CSWGP. Permittees who discharge to groundwater through an injection well must also comply with any applicable requirements of the Underground Injection Control (UIC) regulations, Chapter 173-218 WAC.

S4. MONITORING REQUIREMENTS, BENCHMARKS, AND REPORTING TRIGGERS

A. Site Log Book

The Permittee must maintain a site log book that contains a record of the implementation of the SWPPP and other permit requirements, including the installation and maintenance of BMPs, site inspections, and stormwater monitoring.

B. Site Inspections

Construction sites one (1) acre or larger that discharge stormwater to surface waters of the State must have site inspections conducted by a Certified Erosion and Sediment Control Lead (CESCL). Sites less than one (1) acre may have a person without CESCL certification conduct inspections. (See Special Conditions S4.B.3 and B.4, below, for detailed requirements of the Permittee's CESCL.)

Site inspections must include all areas disturbed by construction activities, all BMPs, and all stormwater discharge points under the Permittee's operational control.

1. The Permittee must have staff knowledgeable in the principles and practices of erosion and sediment control. The CESCL (sites one acre or more) or inspector (sites less than one acre) must have the skills to assess the:
 - a. Site conditions and construction activities that could impact the quality of stormwater; and
 - b. Effectiveness of erosion and sediment control measures used to control the quality of stormwater discharges. The SWPPP must identify the CESCL or inspector, who must be present on site or on-call at all times. The CESCL (sites one (1) acre or more) must obtain this certification through an approved erosion and sediment control training program that meets the minimum training standards established by Ecology. (See BMP C160 in the manual, referred to in Special Condition S9.C.1 and 2.)
2. The CESCL or inspector must examine stormwater visually for the presence of suspended sediment, turbidity, discoloration, and oil sheen. BMP effectiveness must be evaluated to

determine if it is necessary to install, maintain, or repair BMPs to improve the quality of stormwater discharges.

Based on the results of the inspection, the Permittee must correct the problems identified, by:

- a. Reviewing the SWPPP for compliance with Special Condition S9 and making appropriate revisions within 7 days of the inspection.
 - b. Immediately beginning the process of fully implementing and maintaining appropriate source control and/or treatment BMPs, within 10 days of the inspection. If installation of necessary treatment BMPs is not feasible within 10 days, Ecology may approve additional time when an extension is requested by a Permittee within the initial 10-day response period.
 - c. Documenting BMP implementation and maintenance in the site log book.
3. The CESCL or inspector must inspect all areas disturbed by construction activities, all BMPs, and all stormwater discharge points at least once every calendar week and within 24 hours of any discharge from the site. (For purposes of this condition, individual discharge events that last more than one (1) day do not require daily inspections. For example, if a stormwater pond discharges continuously over the course of a week, only one (1) inspection is required that week.) Inspection frequency may be reduced to once every calendar month for inactive sites that are temporarily stabilized.
4. The Permittee must summarize the results of each inspection in an inspection report or checklist and enter the report/checklist into, or attach it to, the site log book. At a minimum, each inspection report or checklist must include:
 - a. Inspection date and time.
 - b. Weather information.
 - c. The general conditions during inspection.
 - d. The approximate amount of precipitation since the last inspection.
 - e. The approximate amount of precipitation within the last 24 hours.
 - f. A summary or list of all implemented BMPs, including observations of all erosion/sediment control structures or practices.
 - g. A description of:
 - i. BMPs inspected (including location).
 - ii. BMPs that need maintenance and why.
 - iii. BMPs that failed to operate as designed or intended, and
 - iv. Where additional or different BMPs are needed, and why.
 - h. A description of stormwater discharged from the site. The Permittee must note the presence of suspended sediment, turbidity, discoloration, and oil sheen, as applicable.

- i. Any water quality monitoring performed during inspection.
- j. General comments and notes, including a brief description of any BMP repairs, maintenance, or installations made following the inspection.
- k. An implementation schedule for the remedial actions that the Permittee plans to take if the site inspection indicates that the site is out of compliance. The remedial actions taken must meet the requirements of the SWPPP and the permit.
- l. A summary report of the inspection.
- m. The name, title, and signature of the person conducting the site inspection, a phone number or other reliable method to reach this person, and the following statement:
I certify that this report is true, accurate, and complete to the best of my knowledge and belief.

Table 3 Summary of Primary Monitoring Requirements

Size of Soil Disturbance ¹	Weekly Site Inspections	Weekly Sampling w/ Turbidity Meter	Weekly Sampling w/ Transparency Tube	Weekly pH Sampling ²	CESCL Required for Inspections?
Sites that disturb less than 1 acre, but are part of a larger Common Plan of Development	Required	Not Required	Not Required	Not Required	No
Sites that disturb 1 acre or more, but fewer than 5 acres	Required	Sampling Required – either method ³		Required	Yes
Sites that disturb 5 acres or more	Required	Required	Not Required ⁴	Required	Yes

¹ Soil disturbance is calculated by adding together all areas that will be affected by construction activity. Construction activity means clearing, grading, excavation, and any other activity that disturbs the surface of the land, including ingress/egress from the site.

² If construction activity results in the disturbance of 1 acre or more, and involves significant concrete work (1,000 cubic yards of concrete or recycled concrete placed or poured over the life of a project) or the use of engineered soils (soil amendments including but not limited to Portland cement-treated base [CTB], cement kiln dust [CKD], or fly ash), and stormwater from the affected area drains to surface waters of the State or to a storm sewer stormwater collection system that drains to other surface waters of the State, the Permittee must conduct pH sampling in accordance with Special Condition S4.D.

³ Sites with one or more acres, but fewer than 5 acres of soil disturbance, must conduct turbidity or transparency sampling in accordance with Special Condition S4.C.4.a or b.

⁴ Sites equal to or greater than 5 acres of soil disturbance must conduct turbidity sampling using a turbidity meter in accordance with Special Condition S4.C.4.a.

C. Turbidity/Transparency Sampling Requirements

1. Sampling Methods

- a. If construction activity involves the disturbance of five (5) acres or more, the Permittee must conduct turbidity sampling per Special Condition S4.C.4.a, below.
- b. If construction activity involves one (1) acre or more but fewer than five (5) acres of soil disturbance, the Permittee must conduct either transparency sampling *or* turbidity sampling per Special Condition S4.C.4.a or b, below.

2. Sampling Frequency

- a. The Permittee must sample all discharge points at least once every calendar week when stormwater (or authorized non-stormwater) discharges from the site or enters any on-site surface waters of the state (for example, a creek running through a site); sampling is not required on sites that disturb less than an acre.
- b. Samples must be representative of the flow and characteristics of the discharge.
- c. Sampling is not required when there is no discharge during a calendar week.
- d. Sampling is not required outside of normal working hours or during unsafe conditions.
- e. If the Permittee is unable to sample during a monitoring period, the Permittee must include a brief explanation in the monthly Discharge Monitoring Report (DMR).
- f. Sampling is not required before construction activity begins.
- g. The Permittee may reduce the sampling frequency for temporarily stabilized, inactive sites to once every calendar month.

3. Sampling Locations

- a. Sampling is required at all points where stormwater associated with construction activity (or authorized non-stormwater) is discharged off site, including where it enters any on-site surface waters of the state (for example, a creek running through a site).
- b. The Permittee may discontinue sampling at discharge points that drain areas of the project that are fully stabilized to prevent erosion.
- c. The Permittee must identify all sampling point(s) in the SWPPP and on the site map and clearly mark these points in the field with a flag, tape, stake or other visible marker.
- d. Sampling is not required for discharge that is sent directly to sanitary or combined sewer systems.
- e. The Permittee may discontinue sampling at discharge points in areas of the project where the Permittee no longer has operational control of the construction activity.

4. Sampling and Analysis Methods

- a. The Permittee performs turbidity analysis with a calibrated turbidity meter (turbidimeter) either on site or at an accredited lab. The Permittee must record the results in the site log book in nephelometric turbidity units (NTUs).
- b. The Permittee performs transparency analysis on site with a 1¾ inch diameter, 60 centimeter (cm)-long transparency tube. The Permittee will record the results in the site log book in centimeters (cm).

Table 4 Monitoring and Reporting Requirements

Parameter	Unit	Analytical Method	Sampling Frequency	Benchmark Value
Turbidity	NTU	SM2130	Weekly, if discharging	25 NTUs
Transparency	Cm	Manufacturer instructions, or Ecology guidance	Weekly, if discharging	33 cm

5. Turbidity/Transparency Benchmark Values and Reporting Triggers

The benchmark value for turbidity is 25 NTUs. The benchmark value for transparency is 33 centimeters (cm). Note: Benchmark values do not apply to discharges to segments of water bodies on Washington State's 303(d) list (Category 5) for turbidity, fine sediment, or phosphorus; these discharges are subject to a numeric effluent limit for turbidity. Refer to Special Condition S8 for more information and follow S5.F – Noncompliance Notification for reporting requirements applicable to discharges which exceed the numeric effluent limit for turbidity.

- a. Turbidity 26 – 249 NTUs, or Transparency 32 – 7 cm:

If the discharge turbidity is 26 to 249 NTUs; or if discharge transparency is 32 to 7 cm, the Permittee must:

- i. Immediately begin the process to fully implement and maintain appropriate source control and/or treatment BMPs, and no later than 10 days of the date the discharge exceeded the benchmark. If installation of necessary treatment BMPs is not feasible within 10 days, Ecology may approve additional time when the Permittee requests an extension within the initial 10-day response period.
- ii. Review the SWPPP for compliance with Special Condition S9 and make appropriate revisions within 7 days of the date the discharge exceeded the benchmark.
- iii. Document BMP implementation and maintenance in the site log book.

- b. Turbidity 250 NTUs or greater, or Transparency 6 cm or less:

If a discharge point's turbidity is 250 NTUs or greater, or if discharge transparency is less than or equal to 6 cm, the Permittee must complete the reporting and adaptive

management process described below. For discharges which are subject to a numeric effluent limit for turbidity, see S5.F – Noncompliance Notification.

- i. Within 24 hours, telephone or submit an electronic report to the applicable Ecology Region's Environmental Report Tracking System (ERTS) number (or through Ecology's Water Quality Permitting Portal [WQWebPortal] – Permit Submittals when the form is available), in accordance with Special Condition S5.A.
 - **Central Region** (Okanogan, Chelan, Douglas, Kittitas, Yakima, Klickitat, Benton): (509) 575-2490
 - **Eastern Region** (Adams, Asotin, Columbia, Ferry, Franklin, Garfield, Grant, Lincoln, Pend Oreille, Spokane, Stevens, Walla Walla, Whitman): (509) 329-3400
 - **Northwest Region** (Kitsap, Snohomish, Island, King, San Juan, Skagit, Whatcom): (425) 649-7000
 - **Southwest Region** (Grays Harbor, Lewis, Mason, Thurston, Pierce, Clark, Cowlitz, Skamania, Wahkiakum, Clallam, Jefferson, Pacific): (360) 407-6300

These numbers and a link to the ERTS reporting page are also listed at the following website: <http://www.ecy.wa.gov/programs/wq/stormwater/construction/index.html>.

- ii. Immediately begin the process to fully implement and maintain appropriate source control and/or treatment BMPs as soon as possible, addressing the problems within 10 days of the date the discharge exceeded the benchmark. If installation of necessary treatment BMPs is not feasible within 10 days, Ecology may approve additional time when the Permittee requests an extension within the initial 10-day response period.
- iii. Sample discharges daily until:
 - a) Turbidity is 25 NTUs (or lower); or
 - b) Transparency is 33 cm (or greater); or
 - c) The Permittee has demonstrated compliance with the water quality standard for turbidity:
 - 1) No more than 5 NTUs over background turbidity, if background is less than 50 NTUs, or
 - 2) No more than 10% over background turbidity, if background is 50 NTUs or greater; or

*Note: background turbidity in the receiving water must be measured immediately upstream (upgradient) or outside of the area of influence of the discharge.
 - d) The discharge stops or is eliminated.
- iv. Review the SWPPP for compliance with Special Condition S9 and make appropriate revisions within seven (7) days of the date the discharge exceeded the benchmark.

- v. Document BMP implementation and maintenance in the site log book.

Compliance with these requirements does not relieve the Permittee from responsibility to maintain continuous compliance with permit benchmarks.

D. pH Sampling Requirements – Significant Concrete Work or Engineered Soils

If construction activity results in the disturbance of 1 acre or more, *and* involves significant concrete work (significant concrete work means greater than 1000 cubic yards placed or poured concrete or recycled concrete used over the life of a project) or the use of engineered soils (soil amendments including but not limited to Portland cement-treated base [CTB], cement kiln dust [CKD], or fly ash), and stormwater from the affected area drains to surface waters of the State or to a storm sewer system that drains to surface waters of the State, the Permittee must conduct pH sampling as set forth below. Note: In addition, discharges to segments of water bodies on Washington State's 303(d) list (Category 5) for high pH are subject to a numeric effluent limit for pH; refer to Special Condition S8.

1. The Permittee must perform pH analysis on site with a calibrated pH meter, pH test kit, or wide range pH indicator paper. The Permittee must record pH sampling results in the site log book.
2. During the applicable pH monitoring period defined below, the Permittee must obtain a representative sample of stormwater and conduct pH analysis at least once per week.
 - a. For sites with significant concrete work, the Permittee must begin the pH sampling period when the concrete is first placed or poured and exposed to precipitation, and continue weekly throughout and after the concrete placement, pour and curing period, until stormwater pH is in the range of 6.5 to 8.5 (su).
 - b. For sites with recycled concrete where monitoring is required, the Permittee must begin the weekly pH sampling period when the recycled concrete is first exposed to precipitation and must continue until the recycled concrete is fully stabilized with the stormwater pH in the range of 6.5 to 8.5 (su).
 - c. For sites with engineered soils, the Permittee must begin the pH sampling period when the soil amendments are first exposed to precipitation and must continue until the area of engineered soils is fully stabilized.
3. The Permittee must sample pH in the sediment trap/pond(s) or other locations that receive stormwater runoff from the area of significant concrete work or engineered soils before the stormwater discharges to surface waters.
4. The benchmark value for pH is 8.5 standard units. Anytime sampling indicates that pH is 8.5 or greater, the Permittee must either:
 - a. Prevent the high pH water (8.5 or above) from entering storm sewer systems or surface waters of the state; *or*
 - b. If necessary, adjust or neutralize the high pH water until it is in the range of pH 6.5 to 8.5 (su) using an appropriate treatment BMP such as carbon dioxide (CO₂) sparging, dry ice or food grade vinegar. The Permittee must obtain written approval from Ecology before using any form of chemical treatment other than CO₂ sparging, dry ice or food grade vinegar.

S5. REPORTING AND RECORDKEEPING REQUIREMENTS

A. High Turbidity Reporting

Anytime sampling performed in accordance with Special Condition S4.C indicates turbidity has reached the 250 NTUs or more (or transparency less than or equal to 6 cm), high turbidity reporting level, the Permittee must notify Ecology within 24 hours of analysis either by calling the applicable Ecology Region's Environmental Report Tracking System (ERTS) number by phone or by submitting an electronic ERTS report (through Ecology's Water Quality Permitting Portal (WQWebPortal) – Permit Submittals when the form is available). See the CSWGP website for links to ERTS and the WQWebPortal. (<http://www.ecy.wa.gov/programs/wq/stormwater/construction/index.html>) Also, see phone numbers in Special Condition S4.C.5.b.i.

B. Discharge Monitoring Reports (DMRs)

Permittees required to conduct water quality sampling in accordance with Special Conditions S4.C (Turbidity/Transparency), S4.D (pH), S8 (303[d]/TMDL sampling), and/or G12 (Additional Sampling) must submit the results to Ecology.

Permittees must submit monitoring data using Ecology's WQWebDMR web application accessed through Ecology's Water Quality Permitting Portal.

Permittees unable to submit electronically (for example, those who do not have an internet connection) must contact Ecology to request a waiver and obtain instructions on how to obtain a paper copy DMR at:

Department of Ecology
Water Quality Program - Construction Stormwater
PO Box 47696
Olympia, WA 98504-7696

Permittees who obtain a waiver not to use WQWebDMR must use the forms provided to them by Ecology; submittals must be mailed to the address above. Permittees must submit DMR forms to be received by Ecology within 15 days following the end of each month.

If there was no discharge during a given monitoring period, all Permittees must submit a DMR as required with "no discharge" entered in place of the monitoring results. DMRs are required for the full duration of permit coverage (from the first full month following the effective date of permit coverage up until Ecology has approved termination of the coverage). For more information, contact Ecology staff using information provided at the following website: www.ecy.wa.gov/programs/wq/permits/paris/contacts.html.

C. Records Retention

The Permittee must retain records of all monitoring information (site log book, sampling results, inspection reports/checklists, etc.), Stormwater Pollution Prevention Plan, copy of the permit coverage letter (including Transfer of Coverage documentation) and any other documentation of compliance with permit requirements for the entire life of the construction project and for a minimum of five (5) years following the termination of permit coverage. Such information must include all calibration and maintenance records, and records of all data used to complete the application for this permit. This period of retention must be extended during

the course of any unresolved litigation regarding the discharge of pollutants by the Permittee or when requested by Ecology.

D. Recording Results

For each measurement or sample taken, the Permittee must record the following information:

1. Date, place, method, and time of sampling or measurement.
2. The first and last name of the individual who performed the sampling or measurement.
3. The date(s) the analyses were performed.
4. The first and last name of the individual who performed the analyses.
5. The analytical techniques or methods used.
6. The results of all analyses.

E. Additional Monitoring by the Permittee

If the Permittee samples or monitors any pollutant more frequently than required by this permit using test procedures specified by Special Condition S4 of this permit, the sampling results for this monitoring must be included in the calculation and reporting of the data submitted in the Permittee's DMR.

F. Noncompliance Notification

In the event the Permittee is unable to comply with any part of the terms and conditions of this permit, and the resulting noncompliance may cause a threat to human health or the environment (such as but not limited to spills or fuels or other materials, catastrophic pond or slope failure, and discharges that violate water quality standards), or exceed numeric effluent limitations (see S8 – Discharges to 303(d) or TMDL Waterbodies), the Permittee must, upon becoming aware of the circumstance:

1. Notify Ecology within 24 hours of the failure to comply by calling the applicable Regional office ERTS phone number (refer to Special Condition S4.C.5.b.i, or go to <https://ecology.wa.gov/About-us/Get-involved/Report-an-environmental-issue> to find contact information for the regional offices.)
2. Immediately take action to prevent the discharge/pollution, or otherwise stop or correct the noncompliance, and, if applicable, repeat sampling and analysis of any noncompliance immediately and submit the results to Ecology within five (5) days of becoming aware of the violation (See S5.F.3, below, for details on submitting results in a report).
3. Submit a detailed written report to Ecology within five (5) days of the time the Permittee becomes aware of the circumstances, unless requested earlier by Ecology. The report must be submitted using Ecology's Water Quality Permitting Portal (WQWebPortal) – Permit Submittals, unless a waiver from electronic reporting has been granted according to S5.B. The report must contain a description of the noncompliance, including exact dates and times, and if the noncompliance has not been corrected, the anticipated time it is expected to continue; and the steps taken or planned to reduce, eliminate, and prevent reoccurrence of the noncompliance.

The Permittee must report any unanticipated bypass and/or upset that exceeds any effluent limit in the permit in accordance with the 24-hour reporting requirement contained in 40 C.F.R. 122.41(l)(6).

Compliance with these requirements does not relieve the Permittee from responsibility to maintain continuous compliance with the terms and conditions of this permit or the resulting liability for failure to comply. Upon request of the Permittee, Ecology may waive the requirement for a written report on a case-by-case basis, if the immediate notification is received by Ecology within 24 hours.

G. Access to Plans and Records

1. The Permittee must retain the following permit documentation (plans and records) on site, or within reasonable access to the site, for use by the operator or for on-site review by Ecology or the local jurisdiction:
 - a. General Permit
 - b. Permit Coverage Letter
 - c. Stormwater Pollution Prevention Plan (SWPPP)
 - d. Site Log Book
 - e. Erosivity Waiver (if applicable)
2. The Permittee must address written requests for plans and records listed above (Special Condition S5.G.1) as follows:
 - a. The Permittee must provide a copy of plans and records to Ecology within 14 days of receipt of a written request from Ecology.
 - b. The Permittee must provide a copy of plans and records to the public when requested in writing. Upon receiving a written request from the public for the Permittee's plans and records, the Permittee must either:
 - i. Provide a copy of the plans and records to the requester within 14 days of a receipt of the written request; *or*
 - ii. Notify the requester within 10 days of receipt of the written request of the location and times within normal business hours when the plans and records may be viewed; and provide access to the plans and records within 14 days of receipt of the written request; *or*

Within 14 days of receipt of the written request, the Permittee may submit a copy of the plans and records to Ecology for viewing and/or copying by the requester at an Ecology office, or a mutually agreed location. If plans and records are viewed and/or copied at a location other than at an Ecology office, the Permittee will provide reasonable access to copying services for which a reasonable fee may be charged. The Permittee must notify the requester within 10 days of receipt of the request where the plans and records may be viewed and/or copied.

S6. PERMIT FEES

The Permittee must pay permit fees assessed by Ecology. Fees for stormwater discharges covered under this permit are established by Chapter 173-224 WAC. Ecology continues to assess permit fees until the permit is terminated in accordance with Special Condition S10 or revoked in accordance with General Condition G5.

S7. SOLID AND LIQUID WASTE DISPOSAL

The Permittee must handle and dispose of solid and liquid wastes generated by construction activity, such as demolition debris, construction materials, contaminated materials, and waste materials from maintenance activities, including liquids and solids from cleaning catch basins and other stormwater facilities, in accordance with:

- A. Special Condition S3, Compliance with Standards.
- B. WAC 173-216-110.
- C. Other applicable regulations.

S8. DISCHARGES TO 303(d) OR TMDL WATERBODIES

A. Sampling and Numeric Effluent Limits For Certain Discharges to 303(d)-Listed Water Bodies

1. Permittees who discharge to segments of water bodies listed as impaired by the State of Washington under Section 303(d) of the Clean Water Act for turbidity, fine sediment, high pH, or phosphorus, must conduct water quality sampling according to the requirements of this section, and Special Conditions S4.C.2.b-f and S4.C.3.b-d, and must comply with the applicable numeric effluent limitations in S8.C and S8.D.
2. All references and requirements associated with Section 303(d) of the Clean Water Act mean the most current listing by Ecology of impaired waters (Category 5) that exists on January 1, 2021, or the date when the operator's complete permit application is received by Ecology, whichever is later.

B. Limits on Coverage for New Discharges to TMDL or 303(d)-Listed Waters

Construction sites that discharge to a TMDL or 303(d)-listed waterbody are not eligible for coverage under this permit *unless* the operator:

1. Prevents exposing stormwater to pollutants for which the waterbody is impaired, and retains documentation in the SWPPP that details procedures taken to prevent exposure on site; *or*
2. Documents that the pollutants for which the waterbody is impaired are not present at the site, and retains documentation of this finding within the SWPPP; *or*
3. Provides Ecology with data indicating the discharge is not expected to cause or contribute to an exceedance of a water quality standard, and retains such data on site with the SWPPP. The operator must provide data and other technical information to Ecology that sufficiently demonstrate:
 - a. For discharges to waters without an EPA-approved or -established TMDL, that the discharge of the pollutant for which the water is impaired will meet in-stream water quality criteria at the point of discharge to the waterbody; *or*
 - b. For discharges to waters with an EPA-approved or -established TMDL, that there is sufficient remaining wasteload allocation in the TMDL to allow construction stormwater discharge and that existing dischargers to the waterbody are subject to compliance schedules designed to bring the waterbody into attainment with water quality standards.

Operators of construction sites are eligible for coverage under this permit only after Ecology makes an affirmative determination that the *discharge will not cause or contribute to the existing impairment or exceed the TMDL*.

C. Sampling and Numeric Effluent Limits for Discharges to Water Bodies on the 303(d) List for Turbidity, Fine Sediment, or Phosphorus

1. Permittees who discharge to segments of water bodies on the 303(d) list (Category 5) for turbidity, fine sediment, or phosphorus must conduct turbidity sampling in accordance with Special Condition S4.C.2 and comply with either of the numeric effluent limits noted in Table 5 below.
2. As an alternative to the 25 NTUs effluent limit noted in Table 5 below (applied at the point where stormwater [or authorized non-stormwater] is discharged off-site), Permittees may choose to comply with the surface water quality standard for turbidity. The standard is: no more than 5 NTUs over background turbidity when the background turbidity is 50 NTUs or less, or no more than a 10% increase in turbidity when the background turbidity is more than 50 NTUs. In order to use the water quality standard requirement, the sampling must take place at the following locations:
 - a. Background turbidity in the 303(d)-listed receiving water immediately upstream (upgradient) or outside the area of influence of the discharge.
 - b. Turbidity at the point of discharge into the 303(d)-listed receiving water, inside the area of influence of the discharge.
3. Discharges that exceed the numeric effluent limit for turbidity constitute a violation of this permit.
4. Permittees whose discharges exceed the numeric effluent limit must sample discharges daily until the violation is corrected and comply with the non-compliance notification requirements in Special Condition S5.F.

Table 5 Turbidity, Fine Sediment & Phosphorus Sampling and Limits for 303(d)-Listed Waters

Parameter identified in 303(d) listing	Parameter Sampled	Unit	Analytical Method	Sampling Frequency	Numeric Effluent Limit ¹
- Turbidity - Fine Sediment - Phosphorus	Turbidity	NTU	SM2130	Weekly, if discharging	25 NTUs, at the point where stormwater is discharged from the site; OR In compliance with the surface water quality standard for turbidity (S8.C.2.a)

¹ Permittees subject to a numeric effluent limit for turbidity may, at their discretion, choose either numeric effluent limitation based on site-specific considerations including, but not limited to, safety, access and convenience.

D. Discharges to Water Bodies on the 303(d) List for High pH

1. Permittees who discharge to segments of water bodies on the 303(d) list (Category 5) for high pH must conduct pH sampling in accordance with the table below, and comply with the numeric effluent limit of pH 6.5 to 8.5 su (Table 6).

Table 6 pH Sampling and Limits for 303(d)-Listed Waters

Parameter identified in 303(d) listing	Parameter Sampled/Units	Analytical Method	Sampling Frequency	Numeric Effluent Limit
High pH	pH /Standard Units	pH meter	Weekly, if discharging	In the range of 6.5 – 8.5 su

2. At the Permittee's discretion, compliance with the limit shall be assessed at one of the following locations:
 - a. Directly in the 303(d)-listed waterbody segment, inside the immediate area of influence of the discharge; *or*
 - b. Alternatively, the Permittee may measure pH at the point where the discharge leaves the construction site, rather than in the receiving water.
3. Discharges that exceed the numeric effluent limit for pH (outside the range of 6.5 – 8.5 su) constitute a violation of this permit.
4. Permittees whose discharges exceed the numeric effluent limit must sample discharges daily until the violation is corrected and comply with the non-compliance notification requirements in Special Condition S5.F.

E. Sampling and Limits for Sites Discharging to Waters Covered by a TMDL or another Pollution Control Plan

1. Discharges to a waterbody that is subject to a Total Maximum Daily Load (TMDL) for turbidity, fine sediment, high pH, or phosphorus must be consistent with the TMDL. Refer to <http://www.ecy.wa.gov/programs/wq/tmdl/TMDLsbyWria/TMDLbyWria.html> for more information on TMDLs.
 - a. Where an applicable TMDL sets specific waste load allocations or requirements for discharges covered by this permit, discharges must be consistent with any specific waste load allocations or requirements established by the applicable TMDL.
 - i. The Permittee must sample discharges weekly, unless otherwise specified by the TMDL, to evaluate compliance with the specific waste load allocations or requirements.
 - ii. Analytical methods used to meet the monitoring requirements must conform to the latest revision of the *Guidelines Establishing Test Procedures for the Analysis of Pollutants* contained in 40 CFR Part 136.
 - iii. Turbidity and pH methods need not be accredited or registered unless conducted at a laboratory which must otherwise be accredited or registered.
 - b. Where an applicable TMDL has established a general waste load allocation for construction stormwater discharges, but has not identified specific requirements, compliance with Special Conditions S4 (Monitoring) and S9 (SWPPPs) will constitute compliance with the approved TMDL.
 - c. Where an applicable TMDL has not specified a waste load allocation for construction stormwater discharges, but has not excluded these discharges, compliance with Special Conditions S4 (Monitoring) and S9 (SWPPPs) will constitute compliance with the approved TMDL.
 - d. Where an applicable TMDL specifically precludes or prohibits discharges from construction activity, the operator is not eligible for coverage under this permit.

S9. STORMWATER POLLUTION PREVENTION PLAN

The Permittee must prepare and properly implement an adequate Stormwater Pollution Prevention Plan (SWPPP) for construction activity in accordance with the requirements of this permit beginning with initial soil disturbance and until final stabilization.

A. The Permittee's SWPPP must meet the following objectives:

1. To identify best management practices (BMPs) which prevent erosion and sedimentation, and to reduce, eliminate or prevent stormwater contamination and water pollution from construction activity.
2. To prevent violations of surface water quality, groundwater quality, or sediment management standards.
3. To control peak volumetric flow rates and velocities of stormwater discharges.

B. General Requirements

1. The SWPPP must include a narrative and drawings. All BMPs must be clearly referenced in the narrative and marked on the drawings. The SWPPP narrative must include documentation to explain and justify the pollution prevention decisions made for the project. Documentation must include:
 - a. Information about existing site conditions (topography, drainage, soils, vegetation, etc.).
 - b. Potential erosion problem areas.
 - c. The 13 elements of a SWPPP in Special Condition S9.D.1-13, including BMPs used to address each element.
 - d. Construction phasing/sequence and general BMP implementation schedule.
 - e. The actions to be taken if BMP performance goals are not achieved—for example, a contingency plan for additional treatment and/or storage of stormwater that would violate the water quality standards if discharged.
 - f. Engineering calculations for ponds, treatment systems, and any other designed structures. When a treatment system requires engineering calculations, these calculations must be included in the SWPPP. Engineering calculations do not need to be included in the SWPPP for treatment systems that do not require such calculations.
2. The Permittee must modify the SWPPP if, during inspections or investigations conducted by the owner/operator, or the applicable local or state regulatory authority, it is determined that the SWPPP is, or would be, ineffective in eliminating or significantly minimizing pollutants in stormwater discharges from the site. The Permittee must then:
 - a. Review the SWPPP for compliance with Special Condition S9 and make appropriate revisions within 7 days of the inspection or investigation.
 - b. Immediately begin the process to fully implement and maintain appropriate source control and/or treatment BMPs as soon as possible, addressing the problems no later than 10 days from the inspection or investigation. If installation of necessary treatment BMPs is not feasible within 10 days, Ecology may approve additional time when an extension is requested by a Permittee within the initial 10-day response period.
 - c. Document BMP implementation and maintenance in the site log book.

The Permittee must modify the SWPPP whenever there is a change in design, construction, operation, or maintenance at the construction site that has, or could have, a significant effect on the discharge of pollutants to waters of the State.

C. Stormwater Best Management Practices (BMPs)

BMPs must be consistent with:

1. *Stormwater Management Manual for Western Washington* (most current approved edition at the time this permit was issued), for sites west of the crest of the Cascade Mountains; *or*

2. *Stormwater Management Manual for Eastern Washington* (most current approved edition at the time this permit was issued), for sites east of the crest of the Cascade Mountains; *or*
3. Revisions to the manuals listed in Special Condition S9.C.1 & 2, or other stormwater management guidance documents or manuals which provide an equivalent level of pollution prevention, that are approved by Ecology and incorporated into this permit in accordance with the permit modification requirements of WAC 173-226-230; *or*
4. Documentation in the SWPPP that the BMPs selected provide an equivalent level of pollution prevention, compared to the applicable stormwater management manuals, including:
 - a. The technical basis for the selection of all stormwater BMPs (scientific, technical studies, and/or modeling) that support the performance claims for the BMPs being selected.
 - b. An assessment of how the selected BMP will satisfy AKART requirements and the applicable federal technology-based treatment requirements under 40 CFR part 125.3.

D. SWPPP – Narrative Contents and Requirements

The Permittee must include each of the 13 elements below in Special Condition S9.D.1-13 in the narrative of the SWPPP and implement them unless site conditions render the element unnecessary and the exemption from that element is clearly justified in the SWPPP.

1. Preserve Vegetation/Mark Clearing Limits
 - a. Before beginning land-disturbing activities, including clearing and grading, clearly mark all clearing limits, sensitive areas and their buffers, and trees that are to be preserved within the construction area.
 - b. Retain the duff layer, native topsoil, and natural vegetation in an undisturbed state to the maximum degree practicable.
2. Establish Construction Access
 - a. Limit construction vehicle access and exit to one route, if possible.
 - b. Stabilize access points with a pad of quarry spalls, crushed rock, or other equivalent BMPs, to minimize tracking sediment onto roads.
 - c. Locate wheel wash or tire baths on site, if the stabilized construction entrance is not effective in preventing tracking sediment onto roads.
 - d. If sediment is tracked off site, clean the affected roadway thoroughly at the end of each day, or more frequently as necessary (for example, during wet weather). Remove sediment from roads by shoveling, sweeping, or pickup and transport of the sediment to a controlled sediment disposal area.
 - e. Conduct street washing only after sediment removal in accordance with Special Condition S9.D.2.d.
 - f. Control street wash wastewater by pumping back on site or otherwise preventing it from discharging into systems tributary to waters of the State.

3. Control Flow Rates

- a. Protect properties and waterways downstream of construction sites from erosion and the associated discharge of turbid waters due to increases in the velocity and peak volumetric flow rate of stormwater runoff from the project site, as required by local plan approval authority.
- b. Where necessary to comply with Special Condition S9.D.3.a, construct stormwater infiltration or detention BMPs as one of the first steps in grading. Assure that detention BMPs function properly before constructing site improvements (for example, impervious surfaces).
- c. If permanent infiltration ponds are used for flow control during construction, protect these facilities from sedimentation during the construction phase.

4. Install Sediment Controls

The Permittee must design, install and maintain effective erosion controls and sediment controls to minimize the discharge of pollutants. At a minimum, the Permittee must:

- a. Construct sediment control BMPs (sediment ponds, traps, filters, infiltration facilities, etc.) as one of the first steps in grading. These BMPs must be functional before other land disturbing activities take place.
- b. Minimize sediment discharges from the site. The design, installation and maintenance of erosion and sediment controls must address factors such as the amount, frequency, intensity and duration of precipitation, the nature of resulting stormwater runoff, and soil characteristics, including the range of soil particle sizes expected to be present on the site.
- c. Direct stormwater runoff from disturbed areas through a sediment pond or other appropriate sediment removal BMP, before the runoff leaves a construction site or before discharge to an infiltration facility. Runoff from fully stabilized areas may be discharged without a sediment removal BMP, but must meet the flow control performance standard of Special Condition S9.D.3.a.
- d. Locate BMPs intended to trap sediment on site in a manner to avoid interference with the movement of juvenile salmonids attempting to enter off-channel areas or drainages.
- e. Provide and maintain natural buffers around surface waters, direct stormwater to vegetated areas to increase sediment removal and maximize stormwater infiltration, unless infeasible.
- f. Where feasible, design outlet structures that withdraw impounded stormwater from the surface to avoid discharging sediment that is still suspended lower in the water column.

5. Stabilize Soils

- a. The Permittee must stabilize exposed and unworked soils by application of effective BMPs that prevent erosion. Applicable BMPs include, but are not limited to: temporary and permanent seeding, sodding, mulching, plastic covering, erosion

control fabrics and matting, soil application of polyacrylamide (PAM), the early application of gravel base on areas to be paved, and dust control.

- b. The Permittee must control stormwater volume and velocity within the site to minimize soil erosion.
- c. The Permittee must control stormwater discharges, including both peak flow rates and total stormwater volume, to minimize erosion at outlets and to minimize downstream channel and stream bank erosion.
- d. Depending on the geographic location of the project, the Permittee must not allow soils to remain exposed and unworked for more than the time periods set forth below to prevent erosion.

West of the Cascade Mountains Crest

During the dry season (May 1 - September 30): 7 days

During the wet season (October 1 - April 30): 2 days

East of the Cascade Mountains Crest, except for Central Basin*

During the dry season (July 1 - September 30): 10 days

During the wet season (October 1 - June 30): 5 days

The Central Basin*, East of the Cascade Mountains Crest

During the dry Season (July 1 - September 30): 30 days

During the wet season (October 1 - June 30): 15 days

***Note: The Central Basin** is defined as the portions of Eastern Washington with mean annual precipitation of less than 12 inches.

- e. The Permittee must stabilize soils at the end of the shift before a holiday or weekend if needed based on the weather forecast.
- f. The Permittee must stabilize soil stockpiles from erosion, protected with sediment trapping measures, and where possible, be located away from storm drain inlets, waterways, and drainage channels.
- g. The Permittee must minimize the amount of soil exposed during construction activity.
- h. The Permittee must minimize the disturbance of steep slopes.
- i. The Permittee must minimize soil compaction and, unless infeasible, preserve topsoil.

6. Protect Slopes

- a. The Permittee must design and construct cut-and-fill slopes in a manner to minimize erosion. Applicable practices include, but are not limited to, reducing continuous length of slope with terracing and diversions, reducing slope steepness, and roughening slope surfaces (for example, track walking).
- b. The Permittee must divert off-site stormwater (run-on) or groundwater away from slopes and disturbed areas with interceptor dikes, pipes, and/or swales. Off-site stormwater should be managed separately from stormwater generated on the site.
- c. At the top of slopes, collect drainage in pipe slope drains or protected channels to prevent erosion.

- i. West of the Cascade Mountains Crest: Temporary pipe slope drains must handle the peak 10-minute flow rate from a Type 1A, 10-year, 24-hour frequency storm for the developed condition. Alternatively, the 10-year, 1-hour flow rate predicted by an approved continuous runoff model, increased by a factor of 1.6, may be used. The hydrologic analysis must use the existing land cover condition for predicting flow rates from tributary areas outside the project limits. For tributary areas on the project site, the analysis must use the temporary or permanent project land cover condition, whichever will produce the highest flow rates. If using the Western Washington Hydrology Model (WWHM) to predict flows, bare soil areas should be modeled as "landscaped area."
 - ii. East of the Cascade Mountains Crest: Temporary pipe slope drains must handle the expected peak flow rate from a 6-month, 3-hour storm for the developed condition, referred to as the short duration storm.
- d. Place excavated material on the uphill side of trenches, consistent with safety and space considerations.
- e. Place check dams at regular intervals within constructed channels that are cut down a slope.
- 7. Protect Drain Inlets
 - a. Protect all storm drain inlets made operable during construction so that stormwater runoff does not enter the conveyance system without first being filtered or treated to remove sediment.
 - b. Clean or remove and replace inlet protection devices when sediment has filled one-third of the available storage (unless a different standard is specified by the product manufacturer).
- 8. Stabilize Channels and Outlets
 - a. Design, construct and stabilize all on-site conveyance channels to prevent erosion from the following expected peak flows:
 - i. West of the Cascade Mountains Crest: Channels must handle the peak 10-minute flow rate from a Type 1A, 10-year, 24-hour frequency storm for the developed condition. Alternatively, the 10-year, 1-hour flow rate indicated by an approved continuous runoff model, increased by a factor of 1.6, may be used. The hydrologic analysis must use the existing land cover condition for predicting flow rates from tributary areas outside the project limits. For tributary areas on the project site, the analysis must use the temporary or permanent project land cover condition, whichever will produce the highest flow rates. If using the WWHM to predict flows, bare soil areas should be modeled as "landscaped area."
 - ii. East of the Cascade Mountains Crest: Channels must handle the expected peak flow rate from a 6-month, 3-hour storm for the developed condition, referred to as the short duration storm.
 - b. Provide stabilization, including armoring material, adequate to prevent erosion of outlets, adjacent stream banks, slopes, and downstream reaches at the outlets of all conveyance systems.

9. Control Pollutants

Design, install, implement and maintain effective pollution prevention measures to minimize the discharge of pollutants. The Permittee must:

- a. Handle and dispose of all pollutants, including waste materials and demolition debris that occur on site in a manner that does not cause contamination of stormwater.
- b. Provide cover, containment, and protection from vandalism for all chemicals, liquid products, petroleum products, and other materials that have the potential to pose a threat to human health or the environment. Minimize storage of hazardous materials on-site. Safety Data Sheets (SDS) should be supplied for all materials stored. Chemicals should be kept in their original labeled containers. On-site fueling tanks must include secondary containment. Secondary containment means placing tanks or containers within an impervious structure capable of containing 110% of the volume of the largest tank within the containment structure. Double-walled tanks do not require additional secondary containment.
- c. Conduct maintenance, fueling, and repair of heavy equipment and vehicles using spill prevention and control measures. Clean contaminated surfaces immediately following any spill incident.
- d. Discharge wheel wash or tire bath wastewater to a separate on-site treatment system that prevents discharge to surface water, such as closed-loop recirculation or upland land application, or to the sanitary sewer with local sewer district approval.
- e. Apply fertilizers and pesticides in a manner and at application rates that will not result in loss of chemical to stormwater runoff. Follow manufacturers' label requirements for application rates and procedures.
- f. Use BMPs to prevent contamination of stormwater runoff by pH-modifying sources. The sources for this contamination include, but are not limited to: bulk cement, cement kiln dust, fly ash, new concrete washing and curing waters, recycled concrete stockpiles, waste streams generated from concrete grinding and sawing, exposed aggregate processes, dewatering concrete vaults, concrete pumping and mixer washout waters. (Also refer to the definition for "concrete wastewater" in Appendix A – Definitions.)
- g. Adjust the pH of stormwater or authorized non-stormwater if necessary to prevent an exceedance of groundwater and/or surface water quality standards.
- h. Assure that washout of concrete trucks is performed off-site or in designated concrete washout areas only. Do not wash out concrete truck drums onto the ground, or into storm drains, open ditches, streets, or streams. Washout of small concrete handling equipment may be disposed of in a formed area awaiting concrete where it will not contaminate surface or groundwater. Do not dump excess concrete on site, except in designated concrete washout areas. Concrete spillage or concrete discharge directly to groundwater or surface waters of the State is

prohibited. At no time shall concrete be washed off into the footprint of an area where an infiltration BMP will be installed.

- i. Obtain written approval from Ecology before using any chemical treatment, with the exception of CO₂, dry ice or food grade vinegar, to adjust pH.
- j. Uncontaminated water from water-only based shaft drilling for construction of building, road, and bridge foundations may be infiltrated provided the wastewater is managed in a way that prohibits discharge to surface waters. Prior to infiltration, water from water-only based shaft drilling that comes into contact with curing concrete must be neutralized until pH is in the range of 6.5 to 8.5 (su).

10. Control Dewatering

- a. Permittees must discharge foundation, vault, and trench dewatering water, which have characteristics similar to stormwater runoff at the site, in conjunction with BMPs to reduce sedimentation before discharge to a sediment trap or sediment pond.
- b. Permittees may discharge clean, non-turbid dewatering water, such as well-point groundwater, to systems tributary to, or directly into surface waters of the State, as specified in Special Condition S9.D.8, provided the dewatering flow does not cause erosion or flooding of receiving waters. Do not route clean dewatering water through stormwater sediment ponds. Note that "surface waters of the State" may exist on a construction site as well as off site; for example, a creek running through a site.
- c. Other dewatering treatment or disposal options may include:
 - i. Infiltration
 - ii. Transport off site in a vehicle, such as a vacuum flush truck, for legal disposal in a manner that does not pollute state waters.
 - iii. Ecology-approved on-site chemical treatment or other suitable treatment technologies (See S9.D.9.i, regarding chemical treatment written approval).
 - iv. Sanitary or combined sewer discharge with local sewer district approval, if there is no other option.
 - v. Use of a sedimentation bag with discharge to a ditch or swale for small volumes of localized dewatering.
- d. Permittees must handle highly turbid or contaminated dewatering water separately from stormwater.

11. Maintain BMPs

- a. Permittees must maintain and repair all temporary and permanent erosion and sediment control BMPs as needed to assure continued performance of their intended function in accordance with BMP specifications.
- b. Permittees must remove all temporary erosion and sediment control BMPs within 30 days after achieving final site stabilization or after the temporary BMPs are no longer needed.

12. Manage the Project

- a. Phase development projects to the maximum degree practicable and take into account seasonal work limitations.
- b. Inspect, maintain and repair all BMPs as needed to assure continued performance of their intended function. Conduct site inspections and monitoring in accordance with Special Condition S4.
- c. Maintain, update, and implement the SWPPP in accordance with Special Conditions S3, S4, and S9.

13. Protect Low Impact Development (LID) BMPs

The primary purpose of on-site LID Stormwater Management is to reduce the disruption of the natural site hydrology through infiltration. LID BMPs are permanent facilities.

- a. Permittees must protect all LID BMPs (including, but not limited to, Bioretention and Rain Garden facilities) from sedimentation through installation and maintenance of erosion and sediment control BMPs on portions of the site that drain into the Bioretention and/or Rain Garden facilities. Restore the BMPs to their fully functioning condition if they accumulate sediment during construction. Restoring the facility must include removal of sediment and any sediment-laden bioretention/ rain garden soils, and replacing the removed soils with soils meeting the design specification.
- b. Permittees must maintain the infiltration capabilities of LID BMPs by protecting against compaction by construction equipment and foot traffic. Protect completed lawn and landscaped areas from compaction due to construction equipment.
- c. Permittees must control erosion and avoid introducing sediment from surrounding land uses onto permeable pavements. Do not allow muddy construction equipment on the base material or pavement. Do not allow sediment-laden runoff onto permeable pavements or base materials.
- d. Permittees must clean permeable pavements fouled with sediments or no longer passing an initial infiltration test using local stormwater manual methodology or the manufacturer's procedures.
- e. Permittees must keep all heavy equipment off existing soils under LID BMPs that have been excavated to final grade to retain the infiltration rate of the soils.

E. SWPPP – Map Contents and Requirements

The Permittee's SWPPP must also include a vicinity map or general location map (for example, a USGS quadrangle map, a portion of a county or city map, or other appropriate map) with enough detail to identify the location of the construction site and receiving waters within one mile of the site.

The SWPPP must also include a legible site map (or maps) showing the entire construction site. The following features must be identified, unless not applicable due to site conditions.

1. The direction of north, property lines, and existing structures and roads.
2. Cut and fill slopes indicating the top and bottom of slope catch lines.

3. Approximate slopes, contours, and direction of stormwater flow before and after major grading activities.
4. Areas of soil disturbance and areas that will not be disturbed.
5. Locations of structural and nonstructural controls (BMPs) identified in the SWPPP.
6. Locations of off-site material, stockpiles, waste storage, borrow areas, and vehicle/equipment storage areas.
7. Locations of all surface water bodies, including wetlands.
8. Locations where stormwater or non-stormwater discharges off-site and/or to a surface waterbody, including wetlands.
9. Location of water quality sampling station(s), if sampling is required by state or local permitting authority.
10. Areas where final stabilization has been accomplished and no further construction-phase permit requirements apply.
11. Location or proposed location of LID facilities.

S10. NOTICE OF TERMINATION

Partial terminations of permit coverage are not authorized.

A. The site is eligible for termination of coverage when it has met any of the following conditions:

1. The site has undergone final stabilization, the Permittee has removed all temporary BMPs (except biodegradable BMPs clearly manufactured with the intention for the material to be left in place and not interfere with maintenance or land use), and all stormwater discharges associated with construction activity have been eliminated; *or*
2. All portions of the site that have not undergone final stabilization per Special Condition S10.A.1 have been sold and/or transferred (per Special Condition S2.A), and the Permittee no longer has operational control of the construction activity; *or*
3. For residential construction only, the Permittee has completed temporary stabilization and the homeowners have taken possession of the residences.

B. When the site is eligible for termination, the Permittee must submit a complete and accurate Notice of Termination (NOT) form, signed in accordance with General Condition G2, to:

Department of Ecology
Water Quality Program - Construction Stormwater
PO Box 47696
Olympia, WA 98504-7696

When an electronic termination form is available, the Permittee may choose to submit a complete and accurate Notice of Termination (NOT) form through the Water Quality Permitting Portal rather than mailing a hardcopy as noted above.

The termination is effective on the 31st calendar day following the date Ecology receives a complete NOT form, unless Ecology notifies the Permittee that termination request is denied because the Permittee has not met the eligibility requirements in Special Condition S10.A.

Permittees are required to comply with all conditions and effluent limitations in the permit until the permit has been terminated.

Permittees transferring the property to a new property owner or operator/Permittee are required to complete and submit the Notice of Transfer form to Ecology, but are not required to submit a Notice of Termination form for this type of transaction.

GENERAL CONDITIONS

G1. DISCHARGE VIOLATIONS

All discharges and activities authorized by this general permit must be consistent with the terms and conditions of this general permit. Any discharge of any pollutant more frequent than or at a level in excess of that identified and authorized by the general permit must constitute a violation of the terms and conditions of this permit.

G2. SIGNATORY REQUIREMENTS

- A. All permit applications must bear a certification of correctness to be signed:
 - 1. In the case of corporations, by a responsible corporate officer.
 - 2. In the case of a partnership, by a general partner of a partnership.
 - 3. In the case of sole proprietorship, by the proprietor.
 - 4. In the case of a municipal, state, or other public facility, by either a principal executive officer or ranking elected official.
- B. All reports required by this permit and other information requested by Ecology (including NOIs, NOTs, and Transfer of Coverage forms) must be signed by a person described above or by a duly authorized representative of that person. A person is a duly authorized representative only if:
 - 1. The authorization is made in writing by a person described above and submitted to Ecology.
 - 2. The authorization specifies either an individual or a position having responsibility for the overall operation of the regulated facility, such as the position of plant manager, superintendent, position of equivalent responsibility, or an individual or position having overall responsibility for environmental matters.
- C. Changes to authorization. If an authorization under paragraph G2.B.2 above is no longer accurate because a different individual or position has responsibility for the overall operation of the facility, a new authorization satisfying the requirements of paragraph G2.B.2 above must be submitted to Ecology prior to or together with any reports, information, or applications to be signed by an authorized representative.
- D. Certification. Any person signing a document under this section must make the following certification:

I certify under penalty of law, that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gathered and evaluated the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.

G3. RIGHT OF INSPECTION AND ENTRY

The Permittee must allow an authorized representative of Ecology, upon the presentation of credentials and such other documents as may be required by law:

- A.** To enter upon the premises where a discharge is located or where any records are kept under the terms and conditions of this permit.
- B.** To have access to and copy, at reasonable times and at reasonable cost, any records required to be kept under the terms and conditions of this permit.
- C.** To inspect, at reasonable times, any facilities, equipment (including monitoring and control equipment), practices, methods, or operations regulated or required under this permit.
- D.** To sample or monitor, at reasonable times, any substances or parameters at any location for purposes of assuring permit compliance or as otherwise authorized by the Clean Water Act.

G4. GENERAL PERMIT MODIFICATION AND REVOCATION

This permit may be modified, revoked and reissued, or terminated in accordance with the provisions of Chapter 173-226 WAC. Grounds for modification, revocation and reissuance, or termination include, but are not limited to, the following:

- A.** When a change occurs in the technology or practices for control or abatement of pollutants applicable to the category of dischargers covered under this permit.
- B.** When effluent limitation guidelines or standards are promulgated pursuant to the CWA or Chapter 90.48 RCW, for the category of dischargers covered under this permit.
- C.** When a water quality management plan containing requirements applicable to the category of dischargers covered under this permit is approved, or
- D.** When information is obtained that indicates cumulative effects on the environment from dischargers covered under this permit are unacceptable.

G5. REVOCATION OF COVERAGE UNDER THE PERMIT

Pursuant to Chapter 43.21B RCW and Chapter 173-226 WAC, the Director may terminate coverage for any discharger under this permit for cause. Cases where coverage may be terminated include, but are not limited to, the following:

- A.** Violation of any term or condition of this permit.
- B.** Obtaining coverage under this permit by misrepresentation or failure to disclose fully all relevant facts.
- C.** A change in any condition that requires either a temporary or permanent reduction or elimination of the permitted discharge.
- D.** Failure or refusal of the Permittee to allow entry as required in RCW 90.48.090.
- E.** A determination that the permitted activity endangers human health or the environment, or contributes to water quality standards violations.
- F.** Nonpayment of permit fees or penalties assessed pursuant to RCW 90.48.465 and Chapter 173-224 WAC.

- G.** Failure of the Permittee to satisfy the public notice requirements of WAC 173-226-130(5), when applicable.

The Director may require any discharger under this permit to apply for and obtain coverage under an individual permit or another more specific general permit. Permittees who have their coverage revoked for cause according to WAC 173-226-240 may request temporary coverage under this permit during the time an individual permit is being developed, provided the request is made within ninety (90) days from the time of revocation and is submitted along with a complete individual permit application form.

G6. REPORTING A CAUSE FOR MODIFICATION

The Permittee must submit a new application, or a supplement to the previous application, whenever a material change to the construction activity or in the quantity or type of discharge is anticipated which is not specifically authorized by this permit. This application must be submitted at least sixty (60) days prior to any proposed changes. Filing a request for a permit modification, revocation and reissuance, or termination, or a notification of planned changes or anticipated noncompliance does not relieve the Permittee of the duty to comply with the existing permit until it is modified or reissued.

G7. COMPLIANCE WITH OTHER LAWS AND STATUTES

Nothing in this permit will be construed as excusing the Permittee from compliance with any applicable federal, state, or local statutes, ordinances, or regulations.

G8. DUTY TO REAPPLY

The Permittee must apply for permit renewal at least 180 days prior to the specified expiration date of this permit. The Permittee must reapply using the electronic application form (NOI) available on Ecology's website. Permittees unable to submit electronically (for example, those who do not have an internet connection) must contact Ecology to request a waiver and obtain instructions on how to obtain a paper NOI.

Department of Ecology
Water Quality Program - Construction Stormwater
PO Box 47696
Olympia, WA 98504-7696

G9. REMOVED SUBSTANCE

The Permittee must not re-suspend or reintroduce collected screenings, grit, solids, sludges, filter backwash, or other pollutants removed in the course of treatment or control of stormwater to the final effluent stream for discharge to state waters.

G10. DUTY TO PROVIDE INFORMATION

The Permittee must submit to Ecology, within a reasonable time, all information that Ecology may request to determine whether cause exists for modifying, revoking and reissuing, or terminating this permit or to determine compliance with this permit. The Permittee must also submit to Ecology, upon request, copies of records required to be kept by this permit [40 CFR 122.41(h)].

G11. OTHER REQUIREMENTS OF 40 CFR

All other requirements of 40 CFR 122.41 and 122.42 are incorporated in this permit by reference.

G12. ADDITIONAL MONITORING

Ecology may establish specific monitoring requirements in addition to those contained in this permit by administrative order or permit modification.

G13. PENALTIES FOR VIOLATING PERMIT CONDITIONS

Any person who is found guilty of willfully violating the terms and conditions of this permit shall be deemed guilty of a crime, and upon conviction thereof shall be punished by a fine of up to ten thousand dollars (\$10,000) and costs of prosecution, or by imprisonment at the discretion of the court. Each day upon which a willful violation occurs may be deemed a separate and additional violation.

Any person who violates the terms and conditions of a waste discharge permit shall incur, in addition to any other penalty as provided by law, a civil penalty in the amount of up to ten thousand dollars (\$10,000) for every such violation. Each and every such violation shall be a separate and distinct offense, and in case of a continuing violation, every day's continuance shall be deemed to be a separate and distinct violation.

G14. UPSET

Definition – "Upset" means an exceptional incident in which there is unintentional and temporary noncompliance with technology-based permit effluent limitations because of factors beyond the reasonable control of the Permittee. An upset does not include noncompliance to the extent caused by operational error, improperly designed treatment facilities, inadequate treatment facilities, lack of preventive maintenance, or careless or improper operation.

An upset constitutes an affirmative defense to an action brought for noncompliance with such technology-based permit effluent limitations if the requirements of the following paragraph are met.

A Permittee who wishes to establish the affirmative defense of upset must demonstrate, through properly signed, contemporaneous operating logs or other relevant evidence that: 1) an upset occurred and that the Permittee can identify the cause(s) of the upset; 2) the permitted facility was being properly operated at the time of the upset; 3) the Permittee submitted notice of the upset as required in Special Condition S5.F, and; 4) the Permittee complied with any remedial measures required under this permit.

In any enforcement proceeding, the Permittee seeking to establish the occurrence of an upset has the burden of proof.

G15. PROPERTY RIGHTS

This permit does not convey any property rights of any sort, or any exclusive privilege.

G16. DUTY TO COMPLY

The Permittee must comply with all conditions of this permit. Any permit noncompliance constitutes a violation of the Clean Water Act and is grounds for enforcement action; for permit termination, revocation and reissuance, or modification; or denial of a permit renewal application.

G17. TOXIC POLLUTANTS

The Permittee must comply with effluent standards or prohibitions established under Section 307(a) of the Clean Water Act for toxic pollutants within the time provided in the regulations that establish those standards or prohibitions, even if this permit has not yet been modified to incorporate the requirement.

G18. PENALTIES FOR TAMPERING

The Clean Water Act provides that any person who falsifies, tampers with, or knowingly renders inaccurate any monitoring device or method required to be maintained under this permit shall, upon conviction, be punished by a fine of not more than \$10,000 per violation, or by imprisonment for not more than two years per violation, or by both. If a conviction of a person is for a violation committed after a first conviction of such person under this condition, punishment shall be a fine of not more than \$20,000 per day of violation, or imprisonment of not more than four (4) years, or both.

G19. REPORTING PLANNED CHANGES

The Permittee must, as soon as possible, give notice to Ecology of planned physical alterations, modifications or additions to the permitted construction activity. The Permittee should be aware that, depending on the nature and size of the changes to the original permit, a new public notice and other permit process requirements may be required. Changes in activities that require reporting to Ecology include those that will result in:

- A.** The permitted facility being determined to be a new source pursuant to 40 CFR 122.29(b).
- B.** A significant change in the nature or an increase in quantity of pollutants discharged, including but not limited to: a 20% or greater increase in acreage disturbed by construction activity.
- C.** A change in or addition of surface water(s) receiving stormwater or non-stormwater from the construction activity.
- D.** A change in the construction plans and/or activity that affects the Permittee's monitoring requirements in Special Condition S4.

Following such notice, permit coverage may be modified, or revoked and reissued pursuant to 40 CFR 122.62(a) to specify and limit any pollutants not previously limited. Until such modification is effective, any new or increased discharge in excess of permit limits or not specifically authorized by this permit constitutes a violation.

G20. REPORTING OTHER INFORMATION

Where the Permittee becomes aware that it failed to submit any relevant facts in a permit application, or submitted incorrect information in a permit application or in any report to Ecology, it must promptly submit such facts or information.

G21. REPORTING ANTICIPATED NON-COMPLIANCE

The Permittee must give advance notice to Ecology by submission of a new application or supplement thereto at least forty-five (45) days prior to commencement of such discharges, of any facility expansions, production increases, or other planned changes, such as process modifications, in the permitted facility or activity which may result in noncompliance with permit limits or conditions. Any maintenance of facilities, which might necessitate unavoidable interruption of

operation and degradation of effluent quality, must be scheduled during non-critical water quality periods and carried out in a manner approved by Ecology.

G22. REQUESTS TO BE EXCLUDED FROM COVERAGE UNDER THE PERMIT

Any discharger authorized by this permit may request to be excluded from coverage under the general permit by applying for an individual permit. The discharger must submit to the Director an application as described in WAC 173-220-040 or WAC 173-216-070, whichever is applicable, with reasons supporting the request. These reasons will fully document how an individual permit will apply to the applicant in a way that the general permit cannot. Ecology may make specific requests for information to support the request. The Director will either issue an individual permit or deny the request with a statement explaining the reason for the denial. When an individual permit is issued to a discharger otherwise subject to the construction stormwater general permit, the applicability of the construction stormwater general permit to that Permittee is automatically terminated on the effective date of the individual permit.

G23. APPEALS

- A.** The terms and conditions of this general permit, as they apply to the appropriate class of dischargers, are subject to appeal by any person within 30 days of issuance of this general permit, in accordance with Chapter 43.21B RCW, and Chapter 173-226 WAC.
- B.** The terms and conditions of this general permit, as they apply to an individual discharger, are appealable in accordance with Chapter 43.21B RCW within 30 days of the effective date of coverage of that discharger. Consideration of an appeal of general permit coverage of an individual discharger is limited to the general permit's applicability or nonapplicability to that individual discharger.
- C.** The appeal of general permit coverage of an individual discharger does not affect any other dischargers covered under this general permit. If the terms and conditions of this general permit are found to be inapplicable to any individual discharger(s), the matter shall be remanded to Ecology for consideration of issuance of an individual permit or permits.

G24. SEVERABILITY

The provisions of this permit are severable, and if any provision of this permit, or application of any provision of this permit to any circumstance, is held invalid, the application of such provision to other circumstances, and the remainder of this permit shall not be affected thereby.

G25. BYPASS PROHIBITED

A. Bypass Procedures

Bypass, which is the intentional diversion of waste streams from any portion of a treatment facility, is prohibited for stormwater events below the design criteria for stormwater management. Ecology may take enforcement action against a Permittee for bypass unless one of the following circumstances (1, 2, 3 or 4) is applicable.

- 1. Bypass of stormwater is consistent with the design criteria and part of an approved management practice in the applicable stormwater management manual.
- 2. Bypass for essential maintenance without the potential to cause violation of permit limits or conditions.

Bypass is authorized if it is for essential maintenance and does not have the potential to cause violations of limitations or other conditions of this permit, or adversely impact public health.

3. Bypass of stormwater is unavoidable, unanticipated, and results in noncompliance of this permit.

This bypass is permitted only if:

- a. Bypass is unavoidable to prevent loss of life, personal injury, or severe property damage. "Severe property damage" means substantial physical damage to property, damage to the treatment facilities which would cause them to become inoperable, or substantial and permanent loss of natural resources which can reasonably be expected to occur in the absence of a bypass.
 - b. There are no feasible alternatives to the bypass, such as the use of auxiliary treatment facilities, retention of untreated wastes, maintenance during normal periods of equipment downtime (but not if adequate backup equipment should have been installed in the exercise of reasonable engineering judgment to prevent a bypass which occurred during normal periods of equipment downtime or preventative maintenance), or transport of untreated wastes to another treatment facility.
 - c. Ecology is properly notified of the bypass as required in Special Condition S5.F of this permit.
4. A planned action that would cause bypass of stormwater and has the potential to result in noncompliance of this permit during a storm event.

The Permittee must notify Ecology at least thirty (30) days before the planned date of bypass. The notice must contain:

- a. A description of the bypass and its cause
 - b. An analysis of all known alternatives which would eliminate, reduce, or mitigate the need for bypassing.
 - c. A cost-effectiveness analysis of alternatives including comparative resource damage assessment.
 - d. The minimum and maximum duration of bypass under each alternative.
 - e. A recommendation as to the preferred alternative for conducting the bypass.
 - f. The projected date of bypass initiation.
 - g. A statement of compliance with SEPA.
 - h. A request for modification of water quality standards as provided for in WAC 173-201A-110, if an exceedance of any water quality standard is anticipated.
 - i. Steps taken or planned to reduce, eliminate, and prevent reoccurrence of the bypass.
5. For probable construction bypasses, the need to bypass is to be identified as early in the planning process as possible. The analysis required above must be considered during

preparation of the Stormwater Pollution Prevention Plan (SWPPP) and must be included to the extent practical. In cases where the probable need to bypass is determined early, continued analysis is necessary up to and including the construction period in an effort to minimize or eliminate the bypass.

Ecology will consider the following before issuing an administrative order for this type bypass:

- a. If the bypass is necessary to perform construction or maintenance-related activities essential to meet the requirements of this permit.
- b. If there are feasible alternatives to bypass, such as the use of auxiliary treatment facilities, retention of untreated wastes, stopping production, maintenance during normal periods of equipment down time, or transport of untreated wastes to another treatment facility.
- c. If the bypass is planned and scheduled to minimize adverse effects on the public and the environment.

After consideration of the above and the adverse effects of the proposed bypass and any other relevant factors, Ecology will approve, conditionally approve, or deny the request. The public must be notified and given an opportunity to comment on bypass incidents of significant duration, to the extent feasible. Approval of a request to bypass will be by administrative order issued by Ecology under RCW 90.48.120.

B. Duty to Mitigate

The Permittee is required to take all reasonable steps to minimize or prevent any discharge or sludge use or disposal in violation of this permit that has a reasonable likelihood of adversely affecting human health or the environment.

APPENDIX A – DEFINITIONS

AKART is an acronym for “**All Known, Available, and Reasonable** methods of prevention, control, and Treatment.” AKART represents the most current methodology that can be reasonably required for preventing, controlling, or abating the pollutants and controlling pollution associated with a discharge.

Applicable TMDL means a TMDL for turbidity, fine sediment, high pH, or phosphorus, which was completed and approved by EPA before January 1, 2021, or before the date the operator’s complete permit application is received by Ecology, whichever is later. TMDLs completed after a complete permit application is received by Ecology become applicable to the Permittee only if they are imposed through an administrative order by Ecology, or through a modification of permit coverage.

Applicant means an *operator* seeking coverage under this permit.

Benchmark means a pollutant concentration used as a permit threshold, below which a pollutant is considered unlikely to cause a water quality violation, and above which it may. When pollutant concentrations exceed benchmarks, corrective action requirements take effect. Benchmark values are not water quality standards and are not numeric effluent limitations; they are indicator values.

Best Management Practices (BMPs) means schedules of activities, prohibitions of practices, maintenance procedures, and other physical, structural and/or managerial practices to prevent or reduce the pollution of waters of the State. BMPs include treatment systems, operating procedures, and practices to control stormwater associated with construction activity, spillage or leaks, sludge or waste disposal, or drainage from raw material storage.

Buffer means an area designated by a local jurisdiction that is contiguous to and intended to protect a sensitive area.

Bypass means the intentional diversion of waste streams from any portion of a treatment facility.

Calendar Day A period of 24 consecutive hours starting at 12:00 midnight and ending the following 12:00 midnight.

Calendar Week (same as **Week**) means a period of seven consecutive days starting at 12:01 a.m. (0:01 hours) on Sunday.

Certified Erosion and Sediment Control Lead (CESCL) means a person who has current certification through an approved erosion and sediment control training program that meets the minimum training standards established by Ecology (See BMP C160 in the SWMM).

Chemical Treatment means the addition of chemicals to stormwater and/or authorized non-stormwater prior to filtration and discharge to surface waters.

Clean Water Act (CWA) means the Federal Water Pollution Control Act enacted by Public Law 92-500, as amended by Public Laws 95-217, 95-576, 96-483, and 97-117; USC 1251 et seq.

Combined Sewer means a sewer which has been designed to serve as a sanitary sewer and a storm sewer, and into which inflow is allowed by local ordinance.

Common Plan of Development or Sale means a site where multiple separate and distinct construction activities may be taking place at different times on different schedules and/or by different contractors, but still under a single plan. Examples include: 1) phased projects and projects with multiple filings or lots, even if the separate phases or filings/lots will be constructed under separate contract or by separate owners (e.g., a development where lots are sold to separate builders); 2) a development plan that may be phased over multiple years, but is still under a consistent plan for long-term development; 3) projects in a contiguous area that may be unrelated but still under the same contract, such as construction of a building extension and a new parking lot at the same facility; and 4) linear projects such as roads, pipelines, or utilities. If the project is part of a common plan of development or sale, the disturbed area of the entire plan must be used in determining permit requirements.

Composite Sample means a mixture of grab samples collected at the same sampling point at different times, formed either by continuous sampling or by mixing discrete samples. May be "time-composite" (collected at constant time intervals) or "flow-proportional" (collected either as a constant sample volume at time intervals proportional to stream flow, or collected by increasing the volume of each aliquot as the flow increases while maintaining a constant time interval between the aliquots).

Concrete Wastewater means any water used in the production, pouring and/or clean-up of concrete or concrete products, and any water used to cut, grind, wash, or otherwise modify concrete or concrete products. Examples include water used for or resulting from concrete truck/mixer/pumper/tool/chute rinsing or washing, concrete saw cutting and surfacing (sawing, coring, grinding, roughening, hydro-demolition, bridge and road surfacing). When stormwater comes in contact with concrete wastewater, the resulting water is considered concrete wastewater and must be managed to prevent discharge to waters of the State, including groundwater.

Construction Activity means land disturbing operations including clearing, grading or excavation which disturbs the surface of the land (including off-site disturbance acreage related to construction-support activity). Such activities may include road construction, construction of residential houses, office buildings, or industrial buildings, site preparation, soil compaction, movement and stockpiling of topsoils, and demolition activity.

Construction Support Activity means off-site acreage that will be disturbed as a direct result of the construction project and will discharge stormwater. For example, off-site equipment staging yards, material storage areas, borrow areas, and parking areas.

Contaminant means any hazardous substance that does not occur naturally or occurs at greater than natural background levels. See definition of "hazardous substance" and WAC 173-340-200.

Contaminated soil means soil which contains contaminants, pollutants, or hazardous substances that do not occur naturally or occur at levels greater than natural background.

Contaminated groundwater means groundwater which contains contaminants, pollutants, or hazardous substances that do not occur naturally or occur at levels greater than natural background.

Demonstrably Equivalent means that the technical basis for the selection of all stormwater BMPs is documented within a SWPPP, including:

1. The method and reasons for choosing the stormwater BMPs selected.
2. The pollutant removal performance expected from the BMPs selected.

3. The technical basis supporting the performance claims for the BMPs selected, including any available data concerning field performance of the BMPs selected.
4. An assessment of how the selected BMPs will comply with state water quality standards.
5. An assessment of how the selected BMPs will satisfy both applicable federal technology-based treatment requirements and state requirements to use all known, available, and reasonable methods of prevention, control, and treatment (AKART).

Department means the Washington State Department of Ecology.

Detention means the temporary storage of stormwater to improve quality and/or to reduce the mass flow rate of discharge.

Dewatering means the act of pumping groundwater or stormwater away from an active construction site.

Director means the Director of the Washington State Department of Ecology or his/her authorized representative.

Discharger means an owner or operator of any facility or activity subject to regulation under Chapter 90.48 RCW or the Federal Clean Water Act.

Domestic Wastewater means water carrying human wastes, including kitchen, bath, and laundry wastes from residences, buildings, industrial establishments, or other places, together with such groundwater infiltration or surface waters as may be present.

Ecology means the Washington State Department of Ecology.

Engineered Soils means the use of soil amendments including, but not limited, to Portland cement treated base (CTB), cement kiln dust (CKD), or fly ash to achieve certain desirable soil characteristics.

Equivalent BMPs means operational, source control, treatment, or innovative BMPs which result in equal or better quality of stormwater discharge to surface water or to groundwater than BMPs selected from the SWMM.

Erosion means the wearing away of the land surface by running water, wind, ice, or other geological agents, including such processes as gravitational creep.

Erosion and Sediment Control BMPs means BMPs intended to prevent erosion and sedimentation, such as preserving natural vegetation, seeding, mulching and matting, plastic covering, filter fences, sediment traps, and ponds. Erosion and sediment control BMPs are synonymous with stabilization and structural BMPs.

Federal Operator is an entity that meets the definition of "Operator" in this permit and is either any department, agency or instrumentality of the executive, legislative, and judicial branches of the Federal government of the United States, or another entity, such as a private contractor, performing construction activity for any such department, agency, or instrumentality.

Final Stabilization (same as **fully stabilized** or **full stabilization**) means the completion of all soil disturbing activities at the site and the establishment of permanent vegetative cover, or equivalent permanent stabilization measures (such as pavement, riprap, gabions, or geotextiles) which will prevent erosion. See the applicable Stormwater Management Manual for more information on vegetative cover expectations and equivalent permanent stabilization measures.

Groundwater means water in a saturated zone or stratum beneath the land surface or a surface waterbody.

Hazardous Substance means any dangerous or extremely hazardous waste as defined in RCW 70.105.010 (5) and (6), or any dangerous or extremely dangerous waste as designated by rule under chapter 70.105 RCW; any hazardous sub-stance as defined in RCW 70.105.010(14) or any hazardous substance as defined by rule under chapter 70.105 RCW; any substance that, on the effective date of this section, is a hazardous substance under section 101(14) of the federal cleanup law, 42U.S.C., Sec. 9601(14); petroleum or petroleum products; and any substance or category of substances, including solid waste decomposition products, determined by the director by rule to present a threat to human health or the environment if released into the environment. The term hazardous substance does not include any of the following when contained in an underground storage tank from which there is not a release: crude oil or any fraction thereof or petroleum, if the tank is in compliance with all applicable federal, state, and local law.

Injection Well means a well that is used for the subsurface emplacement of fluids. (See **Well**.)

Jurisdiction means a political unit such as a city, town or county; incorporated for local self-government.

National Pollutant Discharge Elimination System (NPDES) means the national program for issuing, modifying, revoking and reissuing, terminating, monitoring, and enforcing permits, and imposing and enforcing pretreatment requirements, under sections 307, 402, 318, and 405 of the Federal Clean Water Act, for the discharge of pollutants to surface waters of the State from point sources. These permits are referred to as NPDES permits and, in Washington State, are administered by the Washington State Department of Ecology.

Notice of Intent (NOI) means the application for, or a request for coverage under this general permit pursuant to WAC 173-226-200.

Notice of Termination (NOT) means a request for termination of coverage under this general permit as specified by Special Condition S10 of this permit.

Operator means any party associated with a construction project that meets either of the following two criteria:

- The party has operational control over construction plans and specifications, including the ability to make modifications to those plans and specifications; or
- The party has day-to-day operational control of those activities at a project that are necessary to ensure compliance with a SWPPP for the site or other permit conditions (e.g., they are authorized to direct workers at a site to carry out activities required by the SWPPP or comply with other permit conditions).

Permittee means individual or entity that receives notice of coverage under this general permit.

pH means a liquid's measure of acidity or alkalinity. A pH of 7 is defined as neutral. Large variations above or below this value are considered harmful to most aquatic life.

pH Monitoring Period means the time period in which the pH of stormwater runoff from a site must be tested a minimum of once every seven days to determine if stormwater pH is between 6.5 and 8.5.

Point Source means any discernible, confined, and discrete conveyance, including but not limited to, any pipe, ditch, channel, tunnel, conduit, well, discrete fissure, and container from which pollutants are or may be discharged to surface waters of the State. This term does not include return flows from irrigated agriculture. (See the Fact Sheet for further explanation)

Pollutant means dredged spoil, solid waste, incinerator residue, filter backwash, sewage, garbage, domestic sewage sludge (biosolids), munitions, chemical wastes, biological materials, radioactive materials, heat, wrecked or discarded equipment, rock, sand, cellar dirt, and industrial, municipal, and agricultural waste. This term does not include sewage from vessels within the meaning of section 312 of the CWA, nor does it include dredged or fill material discharged in accordance with a permit issued under section 404 of the CWA.

Pollution means contamination or other alteration of the physical, chemical, or biological properties of waters of the State; including change in temperature, taste, color, turbidity, or odor of the waters; or such discharge of any liquid, gaseous, solid, radioactive or other substance into any waters of the State as will or is likely to create a nuisance or render such waters harmful, detrimental or injurious to the public health, safety or welfare; or to domestic, commercial, industrial, agricultural, recreational, or other legitimate beneficial uses; or to livestock, wild animals, birds, fish or other aquatic life.

Process Wastewater means any non-stormwater which, during manufacturing or processing, comes into direct contact with or results from the production or use of any raw material, intermediate product, finished product, byproduct, or waste product. If stormwater commingles with process wastewater, the commingled water is considered process wastewater.

Receiving Water means the waterbody at the point of discharge. If the discharge is to a storm sewer system, either surface or subsurface, the receiving water is the waterbody to which the storm system discharges. Systems designed primarily for other purposes such as for groundwater drainage, redirecting stream natural flows, or for conveyance of irrigation water/return flows that coincidentally convey stormwater are considered the receiving water.

Representative means a stormwater or wastewater sample which represents the flow and characteristics of the discharge. Representative samples may be a grab sample, a time-proportionate *composite sample*, or a flow proportionate sample. Ecology's Construction Stormwater Monitoring Manual provides guidance on representative sampling.

Responsible Corporate Officer for the purpose of signatory authority means: (i) a president, secretary, treasurer, or vice-president of the corporation in charge of a principal business function, or any other person who performs similar policy- or decision-making functions for the corporation, or (ii) the manager of one or more manufacturing, production, or operating facilities, provided, the manager is authorized to make management decisions which govern the operation of the regulated facility including having the explicit or implicit duty of making major capital investment recommendations, and initiating and directing other comprehensive measures to assure long term environmental compliance with environmental laws and regulations; the manager can ensure that the necessary systems are established or actions taken to gather complete and accurate information for permit application requirements; and where authority to sign documents has been assigned or delegated to the manager in accordance with corporate procedures (40 CFR 122.22).

Sanitary Sewer means a sewer which is designed to convey domestic wastewater.

Sediment means the fragmented material that originates from the weathering and erosion of rocks or unconsolidated deposits, and is transported by, suspended in, or deposited by water.

Sedimentation means the depositing or formation of sediment.

Sensitive Area means a waterbody, wetland, stream, aquifer recharge area, or channel migration zone.

SEPA (State Environmental Policy Act) means the Washington State Law, RCW 43.21C.020, intended to prevent or eliminate damage to the environment.

Significant Amount means an amount of a pollutant in a discharge that is amenable to available and reasonable methods of prevention or treatment; or an amount of a pollutant that has a reasonable potential to cause a violation of surface or groundwater quality or sediment management standards.

Significant Concrete Work means greater than 1000 cubic yards placed or poured concrete or recycled concrete used over the life of a project.

Significant Contributor of Pollutants means a facility determined by Ecology to be a contributor of a significant amount(s) of a pollutant(s) to waters of the State of Washington.

Site means the land or water area where any "facility or activity" is physically located or conducted.

Source Control BMPs means physical, structural or mechanical devices or facilities that are intended to prevent pollutants from entering stormwater. A few examples of source control BMPs are erosion control practices, maintenance of stormwater facilities, constructing roofs over storage and working areas, and directing wash water and similar discharges to the sanitary sewer or a dead end sump.

Stabilization means the application of appropriate BMPs to prevent the erosion of soils, such as, temporary and permanent seeding, vegetative covers, mulching and matting, plastic covering and sodding. See also the definition of Erosion and Sediment Control BMPs.

Storm Drain means any drain which drains directly into a *storm sewer system*, usually found along roadways or in parking lots.

Storm Sewer System means a means a conveyance, or system of conveyances (including roads with drainage systems, municipal streets, catch basins, curbs, gutters, ditches, manmade channels, or storm drains designed or used for collecting or conveying stormwater. This does not include systems which are part of a *combined sewer* or Publicly Owned Treatment Works (POTW), as defined at 40 CFR 122.2.

Stormwater means that portion of precipitation that does not naturally percolate into the ground or evaporate, but flows via overland flow, interflow, pipes, and other features of a stormwater drainage system into a defined surface waterbody, or a constructed infiltration facility.

Stormwater Management Manual (SWMM) or Manual means the technical Manual published by Ecology for use by local governments that contain descriptions of and design criteria for BMPs to prevent, control, or treat pollutants in stormwater.

Stormwater Pollution Prevention Plan (SWPPP) means a documented plan to implement measures to identify, prevent, and control the contamination of point source discharges of stormwater.

Surface Waters of the State includes lakes, rivers, ponds, streams, inland waters, salt waters, and all other surface waters and water courses within the jurisdiction of the state of Washington.

Temporary Stabilization means the exposed ground surface has been covered with appropriate materials to provide temporary stabilization of the surface from water or wind erosion. Materials include, but are not limited to, mulch, riprap, erosion control mats or blankets and temporary cover crops. Seeding alone is not considered stabilization. Temporary stabilization is not a substitute for the more permanent “final stabilization.”

Total Maximum Daily Load (TMDL) means a calculation of the maximum amount of a pollutant that a waterbody can receive and still meet state water quality standards. Percentages of the total maximum daily load are allocated to the various pollutant sources. A TMDL is the sum of the allowable loads of a single pollutant from all contributing point and nonpoint sources. The TMDL calculations must include a "margin of safety" to ensure that the waterbody can be protected in case there are unforeseen events or unknown sources of the pollutant. The calculation must also account for seasonable variation in water quality.

Transfer of Coverage (TOC) means a request for transfer of coverage under this general permit as specified by Special Condition S2.A of this permit.

Treatment BMPs means BMPs that are intended to remove pollutants from stormwater. A few examples of treatment BMPs are detention ponds, oil/water separators, biofiltration, and constructed wetlands.

Transparency means a measurement of water clarity in centimeters (cm), using a 60 cm transparency tube. The transparency tube is used to estimate the relative clarity or transparency of water by noting the depth at which a black and white Secchi disc becomes visible when water is released from a value in the bottom of the tube. A transparency tube is sometimes referred to as a “turbidity tube.”

Turbidity means the clarity of water expressed as nephelometric turbidity units (NTUs) and measured with a calibrated turbidimeter.

Uncontaminated means free from any contaminant. See definition of “contaminant” and WAC 173-340-200.

Upset means an exceptional incident in which there is unintentional and temporary noncompliance with technology-based permit effluent limitations because of factors beyond the reasonable control of the Permittee. An upset does not include noncompliance to the extent caused by operational error, improperly designed treatment facilities, inadequate treatment facilities, lack of preventive maintenance, or careless or improper operation.

Waste Load Allocation (WLA) means the portion of a receiving water’s loading capacity that is allocated to one of its existing or future point sources of pollution. WLAs constitute a type of water quality based effluent limitation (40 CFR 130.2[h]).

Water-Only Based Shaft Drilling is a shaft drilling process that uses water only and no additives are involved in the drilling of shafts for construction of building, road, or bridge foundations.

Water Quality means the chemical, physical, and biological characteristics of water, usually with respect to its suitability for a particular purpose.

Waters of the State includes those waters as defined as "waters of the United States" in 40 CFR Subpart 122.2 within the geographic boundaries of Washington State and "waters of the State" as defined in Chapter 90.48 RCW, which include lakes, rivers, ponds, streams, inland waters, underground waters, salt

waters, and all other surface waters and water courses within the jurisdiction of the state of Washington.

Well means a bored, drilled or driven shaft, or dug hole whose depth is greater than the largest surface dimension. (See **Injection Well**.)

Wheel Wash Wastewater means any water used in, or resulting from the operation of, a tire bath or wheel wash (BMP C106: Wheel Wash), or other structure or practice that uses water to physically remove mud and debris from vehicles leaving a construction site and prevent track-out onto roads. When stormwater comes in contact with wheel wash wastewater, the resulting water is considered wheel wash wastewater and must be managed according to Special Condition S9.D.9.

APPENDIX B – ACRONYMS

AKART	All Known, Available, and Reasonable Methods of Prevention, Control, and Treatment
BMP	Best Management Practice
CESCL	Certified Erosion and Sediment Control Lead
CFR	Code of Federal Regulations
CKD	Cement Kiln Dust
cm	Centimeters
CPD	Common Plan of Development
CTB	Cement-Treated Base
CWA	Clean Water Act
DMR	Discharge Monitoring Report
EPA	Environmental Protection Agency
ERTS	Environmental Report Tracking System
ESC	Erosion and Sediment Control
FR	Federal Register
LID	Low Impact Development
NOI	Notice of Intent
NOT	Notice of Termination
NPDES	National Pollutant Discharge Elimination System
NTU	Nephelometric Turbidity Unit
RCW	Revised Code of Washington
SEPA	State Environmental Policy Act
SWMM	Stormwater Management Manual
SWPPP	Stormwater Pollution Prevention Plan
TMDL	Total Maximum Daily Load
UIC	Underground Injection Control
USC	United States Code
USEPA	United States Environmental Protection Agency
WAC	Washington Administrative Code
WQ	Water Quality
WWHM	Western Washington Hydrology Model

This page left intentionally blank.

APPENDIX D

PSE UTILITY POWER DESIGN

THIS PAGE INTENTIONALLY LEFT BLANK

SITE PLAN
SCALE: 1" = 50'

SITE SPECIFIC NOTES

P01: 624628-154983					
REPL EXIST 4" STEEL RISER W/ 4" SEC RISER	RIS4CSS	6042.1000	2-45		
ACTUAL RISER FOOTAGE REMOVED= _____					
ACTUAL RISER FOOTAGE INST= _____					
INST 4" SEC RISERS ON NEW 18" S/O BRACKETS	RIS4CSS	6042.1000	2-45		
ACTUAL RISER FOOTAGE INST= _____					


HH1:			
REPL EXIST 3030 CONC HH W/ 233 CONC SEC HH ANTI-SKID	HH38500AS	6050.2100	3-22
W#12-500 (4) 8-POS CONN BARS			
INST GROUND TO STEEL LID			
RECONNECT EXIST 2-RUNS OF 4/0 UG SVC			
CONNECT & TAG CUSTOMER OWNED CONDUCTOR			
(2-RUNS OF 350KCMIL)			

M01: NEW 600A CT

SPAN SPECIFIC NOTES

P01-HH1:
 REMOVE EXIST 4/0 UG SEC ±55'
 ACTUAL SEC FOOTAGE REMOVED= _____' 2-54A(55')
 INST (2) PARALLEL 350 UG QUAD, ±55' IN PSE PROVIDED (2) 4" DB120
 CONDUIT W/ 3/8" POLY PULL ROPE 3-6(2)
 ACTUAL SEC FOOTAGE INST= _____'
 ACTUAL SEC CONDUIT INST= _____'

HH1-M01:
CONNECT & TAG CUSTOMER OWNED CONDUCTOR
(2-RUNS OF 350KCMIL)



CONDUIT RISER PLACEMENT DETAIL

POWER GENERAL NOTES - COMMERCIAL PROJECT


1. All materials to be installed in accordance with Puget Sound Energy's (PSE) standards. Any deviation from this work sketch must be AUTHORIZED by PSE's Project Manager and NOTED on the Foreman's Copy.
2. All switching arrangements and/or outage arrangements are to be made with the Project Manager at least three (3) working days in advance.
3. Contact the Utilities Underground Location Center (1-800-424-5555) at least 48 hours prior to commencing work to get the underground facilities located.
4. STAKING: The customer will provide all staking (transformer, handhole, trench, grade, lot, pole, sidewalk, etc.). See sketch and details for locations. Equipment locations must be approved by the Project Manager.
5. SITE PREPARATION: The work area will be at or near finished grade, clear of trench spoils or construction materials which would restrict construction and/or equipment access, before work can begin.
6. Roads shall be paved or have a compacted , crushed rock base in place.
7. CLEARANCES: Transformers require a minimum of 6 feet from fire fighting equipment, 10 feet from combustible walls, overhangs, doors, and windows, and a minimum of 5 feet from the back of curb (or guard posts will be required per PSE standards). All conduits and vaults are to be at least 5 feet away from water, storm and sewer lines when paralleling them in the right of way, and at least 1 foot when crossing them.
8. All work is to be done in accordance with local municipal and county permit requirements as applicable.
9. Customer/Developer is responsible to provide, install and maintain all secondary service cables, conduits and crossings from the individual unit's meter base to the designated connection point.
10. Inclement weather conditions may cause delays in construction times and dates.
11. EXCAVATION: The customer is to provide all trenching, backfill, vault excavations, compaction and restoration per this sketch and per PSE standards. A minimum protective cover of 36" is required over PSE's primary voltage equipment and 24" is required of PSE's secondary voltage equipment. The customer will provide any and all shoring or they will side slope the trench to 1:1.

CIRCUIT LOADING TABLE

CIRCUIT: BHL-15				
AS OF	12/7/2020	A PHASE	B PHASE	C PHASE
EXIST. PEAK LOAD		401	379	299
EST. NEW LOAD		7.41	7.41	7.41
TOTAL		408.41	386.41	306.41

SECONDARY CABLE & CONDUIT TABLE



LOCATION		CABLE		QTY	Assumed Lot Corner to Meter(ft)	CONDUIT							VOLTAGE DROP	VOLTAGE FLICKER	ASBUILT INFORMATION
		SIZE	LENGTH Design (ft)			SIZE	LENGTH Design (ft)	QTY	BENDS						Foreman - Complete
FROM	TO	(1/0,4/0,350)				(in)			90°	45°	22°	11°	(Percent)	(Percent)	Actual Amount Installed (Conduit & Cable)
P01	HH1	350 QUAD	55	2		4	20	2	2				3.6	5.0	



HH1

THREE PHASE SECONDARY CONCRETE HANDHOLE

Not to scale 6050.2100-2



OVERHEAD CIRCUIT MAP

FOREMAN (CHECK BOX WHEN COMPLETED)	
☐	PSE Equipment <u>LOCKED/SECURED</u> & Work Area left in <u>CLEAN/SAFE</u> Condition.
☐	Grid, Cable, and Switch numbers <u>INSTALLED & VERIFIED</u> .
☐	Field Changes <u>RED-LINED</u> on As-built.
☐	Material <u>VERIFIED</u> and <u>CHANGES</u> noted on Paperwork.
☐	Only <u>PRIMARY</u> Cable noted on As-built.
☐	Company ID's <u>RECORDED</u> in correct location on As-built.
☐	Indicate correct <u>FUSE SIZE</u> on As-built & <u>VERIFY</u> proper <u>PHASE</u> .
☐	Deviations noted on the As-built and their reason.
☐ I certify that the work performed meets PSE's standards and procedures and that all quality requirements are met.	
Foreman's Signature _____ Date _____	

PROJECT PHASE	NOTIF#	ORDER#
PWR Superior	509714292	1050956780
Removal		108123823
UG Maintenance		594137918
Perm. Service	509983186	104329012
Temporary	N/A	N/A
Job Order	N/A	N/A
GAS Distribution	N/A	N/A
Service Stubs	N/A	N/A
HP Svc/MSA	N/A	N/A

CABLE TV	PHONE

Project Manager Contact Information:

Manager: Alfred Warren
 Cell Phone: (253) 259-4494

Owner / Developer Contact Info

Kitsap County Public Works
 614 Division St, MS-26
 Port Orchard, WA 98366
 ATTN: Nathanael Palmatier

(206) 357-9954 office

Developer Yes ☐ Yes ☐ PSE			
Yes ☐ No ☐ No ☐			
Yes ☐ No ☐ No ☐			
Yes ☐ No ☐ No ☐			
3	N/A	N/A	N/A
2	N/A	N/A	N/A
1	N/A	N/A	N/A
REV#	DATE	BY	DESCRIPTION
COUNTY KITSAP		Emer Sect N/A	Gas Wk Ctr N/A
1/4 SEC		OP MAP	POWER WK CTR QSSPE
SE 1/4 SEC 15 T25 R1E		N/A	N/A
U-MAP NO (POWER)		OH CKT MAP 2501E088	UG CKT MAP 2501E080
			CIRCUIT NO BHL-15

JOINT FACILITIES ARRANGEMENTS			
UTILITIES	N/A	N/A	N/A
CONTACT	N/A	N/A	N/A
PHONE#	N/A	N/A	N/A

PUMP STATION 19

REPL UG SEC L/E & HH

9390 NELS NELSON RD NW

INCIDENT N/A	MAOP N/A
Gas Order N/A	Elect Order 105095780
SCALE AS NOTED	PAGE 1 of 4

THIS PAGE INTENTIONALLY BLANK.

APPENDIX E

MANUFACTURER'S "NOT TO EXCEED" PRICE FOR SUBMERSIBLE WASTEWATER PUMPS

THIS PAGE INTENTIONALLY LEFT BLANK



WECI

Whitney Equipment Company, Inc

16120 Woodinville-Redmond Road NE, Suite 3
Woodinville, WA 98072 Phone: (425) 486-9499

2501 Columbia Way Suite 300
Vancouver, WA 98661 Phone: (360) 694-9175

March 23, 2021

Bidding Contractors

PROJECT NAME – Pump Station 19 and 31

LOCATION – Kitsap County, WA

QUOTATION: 35991

To Whom It May Concern:

The following is Whitney Equipment Company's proposal for equipment we can furnish for the above referenced project. A detailed list of the equipment and services included in this proposal is shown in the following Scope of Supply. Only items listed in the Scope of Supply are included in this proposal. The conditions of sale associated with this proposal are attached.

Engineering calculations and design services are included only when specifically listed in the Scope of Supply. Unless specifically listed in the following Scope of Supply, we do not include haulage, unloading including provision of lifting equipment, permits, bonds, insurance, installation, sales or use taxes or duties of any kind, power, chemicals, water, concrete, grout, anchor bolts, controls, wire, conduit, lights, fans, piping, valves, fittings, drains, meters, gauges, signs, safety equipment, labor, tools, field paint, lubricants, or any other items not listed as included.

We do include one (1) each initial and final bookmarked and searchable PDF submittal and O&M and two (2) hard copies of O&M's. If additional field or onsite assistance is needed beyond what is included in the Scope of Supply, it can be supplied at a rate of \$140.00/hour at the job site, plus travel time and expense.

Prices quoted herein are FOB factory, with full freight estimated to the job location and net cash 30 days after shipment. Purchaser must also pay any costs incurred for additional field or onsite assistance no later than 30 days after receipt of an invoice for field or onsite services from Whitney Equipment Company.

Equipment will be prepared for shipment per the manufacturers' standard packing procedure. The purchaser is responsible for receiving all items including promptly inspecting for damage, noting damages, and filing for all missing or damaged items in a timely manner. Freight shall be standard ground unless otherwise listed. The purchaser is responsible for proper storage and handling of the equipment per the manufacturer's recommendations prior to installation to ensure warranty coverage. Warranty coverage shall be manufacturer's standard warranty unless specifically listed in the Scope of Supply.

Notes:

Submittals: 3-4 weeks after receipt of purchase order.

Lead Time: Equipment will be delivered approximately 12-14 weeks after submittal approval.

Payment Terms: 20% upon approved submittals, 70% upon delivery, 10% upon startup & training

Sales Tax is not included

This job is being handled by Laura Haggard, phone (206) 459-7841. Quote valid through December 31, 2021. Please call if you need further information or prices.



16120 Woodinville-Redmond Road Suite 3 Woodinville, WA 98072 www.weci.com 800-255-2580

SCOPE OF SUPPLY

FLYGT SUBMERSIBLE PUMPS

Pump Station 19 Quotation #35991
Duplex Station Sized for 1440gpm at 96ft TDH

Pumps

- 2ea FLYGT NP 3302.095, 6", 60 HP Submersible Sewage Pumps with
w/ 458 Hard Iron Impellers, Stainless Steel Cooling Jackets, thermal and fluid leak sensor
- 2ea 60 HP FM Rated Explosion Proof Submersible Motors, 460 Volt, 3 Phase, 1800 RPM
- 2ea 65' Shielded Subcab Power Cables, 460V, 3ph
- 2ea External Epoxy Coating

Pump Mounting Accessories

- 4ea FLYGT Mini Cas Thermal Leakage Relay with Mounting Socket
- 2ea 6" Cast Iron Discharge Elbows
- 2ea 3" 316 Stainless Steel Guide Rails 2" x 20ft for a total of 80ft
- 2ea 3" 316 Stainless Steel Upper Guide Bar brackets
- 2ea 20ft Lifting assembly including 1ft lifting chain with spectra guide line and shackles
- 1ea Grip Eye Lifting Device
- 1ea Cable Holder

Required Spare Parts

- 2ea Basic Repair Kits (includes mechanical seals, bearings, and o'rings)
- 2ea Spare Hard Iron kit including: 458 impeller, insert ring, washer, sleeve and impeller bolt

Additional Specification Requirements

- 1ea 5-Year 100% Pump Warranty (includes 5 year annual maintenance by Whitney Equipment)
- 1ea 10-Year Limited Lifting System Warranty
- 1ea Flygt Pump 1 year Clog Free Guarantee
- 1ea Factory Vibration Test
- 1ea Factory Plotted Performance Curve Test
- 1ea Factory Hydraulic Performance Test
- 1ea 1-Day Manufacturers start up and training performed by Whitney Equipment Company
- 1ea Freight, FOB Factory Ocean Freight from Sweden

PS 19 PRE-NEGOTIATED PUMP PRICE: \$172,713.00

Valid Until December 31, 2021

Price does not include Sales Tax

FLYGT SUBMERSIBLE PUMPS
Pump Station 31 Quotation #35991
Duplex Station Sized for 150gpm at 28ft TDH

Pumps

2ea FLYGT NP 3069.070, 3", 3.2 HP Submersible Sewage Pumps with
w/ 432 Adaptive Hard Iron Impellers, thermal and fluid leak sensor
2ea 3.2 HP FM Rated Explosion Proof Submersible Motors, 208 Volt, 3 Phase, 1800 RPM
2ea 65' Shielded Subcab Power Cables, 208V, 3ph
2ea External Epoxy Coating

Pump Mounting Accessories

4ea FLYGT Mini Cas Thermal Leakage Relay with Mounting Socket
2ea 3" Cast Iron Discharge Elbows
2ea 2" 316 Stainless Steel Guide Rails 2" x 20ft for a total of 80ft
2ea 2" 316 Stainless Steel Upper Guide Bar brackets
2ea 20ft Lifting assembly including 1ft lifting chain with spectra guide line and shackles
1ea Grip Eye Lifting Device
1ea Cable Holder

Required Spare Parts

2ea Basic Repair Kits (includes mechanical seals, bearings, and o'rings)
2ea Spare Adaptive Hard Iron kit including: 432 adaptive impeller, suction cover and impeller bolt

Additional Specification Requirements

1ea 5-Year 100% Pump Warranty (includes 5 year annual maintenance by Whitney Equipment)
1ea 10-Year Limited Lifting System Warranty
1ea Flygt Pump 1 year Clog Free Guarantee
1ea Factory Vibration Test
1ea Factory Plotted Performance Curve Test
1ea Factory Hydraulic Performance Test
1ea 1-Day Manufacturers start up and training performed by Whitney Equipment Company
1ea Freight, FOB Factory Ocean Freight from Sweden

PS 31 PRE-NEGOTIATED PUMP PRICE: \$40,246.00

Valid Until December 31, 2021

Price does not include Sales Tax

Point of Delivery

FOB Factory

Full Ocean/Standard Freight Included to Jobsite

1. Price does not include installation, piping, fittings, valves, flow meters, pressure gauges, level control, concrete pedestals, field testing, or any electrical equipment not listed.

Sincerely,

Laura Haggard
Whitney Equipment Company, Inc.

A Commitment to Quality and Service

NP 3202 HT 3~ 458


Patented self cleaning semi-open channel impeller, ideal for pumping in waste water applications. Possible to be upgraded with Guide-pin® for even better clogging resistance. Modular based design with high adaptation grade.



Technical specification



Curves according to: Water, pure ,39.2 °F,62.42 lb/ft³,1.6891E-5 ft²/s



Configuration

Motor number N3202.095 30-24-4AA-W 60hp	Installation type P - Semi permanent, Wet
Impeller diameter 310 mm	Discharge diameter 150 inch

Pump information

Impeller diameter 310 mm
Discharge diameter 150 inch
Inlet diameter 200 mm
Maximum operating speed 1775 rpm
Number of blades 2
Max. fluid temperature 40 °C

Materials

Impeller Hard-Iron™

Project
Block

Created by Laura Haggard
Created on 3/23/2021 Last update 3/23/2021

NP 3202 HT 3~ 458

Technical specification



Motor - General

Motor number N3202.095 30-24-4AA-W 60hp	Phases 3~	Rated speed 1775 rpm	Rated power 60 hp
ATEX approved FM	Number of poles 4	Rated current 69 A	Stator variant 4
Frequency 60 Hz	Rated voltage 460 V	Insulation class H	Type of Duty S1
Version code 095			

Motor - Technical

Power factor - 1/1 Load 0.89	Motor efficiency - 1/1 Load 91.5 %	Total moment of inertia 8.94 lb ft ²	Starts per hour max. 30
Power factor - 3/4 Load 0.86	Motor efficiency - 3/4 Load 92.5 %	Starting current, direct starting 470 A	
Power factor - 1/2 Load 0.78	Motor efficiency - 1/2 Load 92.0 %	Starting current, star-delta 157 A	

Project
Block

Created by Laura Haggard
Created on 3/23/2021 **Last update** 3/23/2021

NP 3202 HT 3~ 458


Performance curve



Duty point

Flow
1500 US g.p.m.

Head
103 ft



Project
Block


Created by Laura Haggard
Created on 3/23/2021 Last update 3/23/2021

NP 3202 HT 3~ 458

Duty Analysis



Curves according to: Water, pure, 39.2 °F, 62.42 lb/ft³, 1.6891E-5 ft²/s



Operating characteristics

Pumps / Systems	Flow	Head	Shaft power	Flow	Head	Shaft power	Hydr.eff.	Specific Energy	NPSHre
1	1500 US g.p.m	103 ft	53.4 hp	1500 US g.p.m	103 ft	53.4 hp	73.4 %	478 kWh/US M	21 ft

Project
Block


Created by Laura Haggard
Created on 3/23/2021 Last update 3/23/2021

NP 3202 HT 3~ 458

VFD Curve



Curves according to: Water, pure, 39.2 °F, 62.42 lb/ft³, 1.6891E-5 ft²/s




Curve: ISO 9906

Project
Block

Created by Laura Haggard
Created on 3/23/2021 Last update 3/23/2021

VFD Analysis




Operating characteristics

Pumps / Systems	Frequency	Flow	Head	Shaft power	Flow	Head	Shaft power	Hydr.eff.	Specific Energy	NPSHre
1	60 Hz	1500 US g.p.m	103 ft	53.4 hp	1500 US g.p.m	103 ft	53.4 hp	73.4 %	478 kWh/US M	21 ft
1	55 Hz	1360 US g.p.m	87.8 ft	41.1 hp	1360 US g.p.m	87.8 ft	41.1 hp	73.5 %	405 kWh/US M	17.9 ft
1	50 Hz	1210 US g.p.m	73.6 ft	30.6 hp	1210 US g.p.m	73.6 ft	30.6 hp	73.5 %	341 kWh/US M	15 ft
1	45 Hz	1050 US g.p.m	60.7 ft	22 hp	1050 US g.p.m	60.7 ft	22 hp	73.5 %	284 kWh/US M	12.3 ft
1	40 Hz	894 US g.p.m.	49.3 ft	15.2 hp	894 US g.p.m.	49.3 ft	15.2 hp	73.5 %	236 kWh/US M	9.82 ft

Project	Created by	Laura Haggard		
Block	Created on	3/23/2021	Last update	3/23/2021

NP 3202 HT 3~ 458

Dimensional drawing



Weight (lbs)	Pump	Discharge
with cooling jacket	1260	180
without cooling jacket	1150	180



FP, NP 3202 HT
090, 095, 180, 185, 350, 390, 660, 670

Discharge Ø6"	Scale 1:40	Date 200605
Pump outlet Ø6"	Drawing number 6664300	Revision 10
Pump inlet		
Suction inlet		

Project
Block

Created by Laura Haggard
Created on 3/23/2021 Last update 3/23/2021

NP 3069 MT 3~ Adaptive 432


Patented self cleaning semi-open channel impeller, ideal for pumping in waste water applications. Possible to be upgraded with Guide-pin® for even better clogging resistance. Modular based design with high adaptation grade.



Technical specification



Curves according to: Water, pure [100%], 39.2 °F, 62.42 lb/ft³, 1.6891E-5 ft²/s



Configuration

Motor number N3069.190 13-10-4BB-W 3.2hp	Installation type P - Semi permanent, Wet
Impeller diameter 166 mm	Discharge diameter 80 inch

Pump information

Impeller diameter 166 mm
Discharge diameter 80 inch
Inlet diameter 113 mm
Maximum operating speed 1670 rpm
Number of blades 2
Max. fluid temperature 40 °C

Materials

Impeller Grey cast iron
Stator housing material Grey cast iron

Project
Block

Created by Laura Haggard
Created on 3/22/2021 Last update 3/22/2021

NP 3069 MT 3~ Adaptive 432

Technical specification



Motor - General

Motor number N3069.190 13-10-4BB-W 3.2hp	Phases 3~	Rated speed 1670 rpm	Rated power 3.2 hp
ATEX approved FM	Number of poles 4	Rated current 11 A	Stator variant 7
Frequency 60 Hz	Rated voltage 208 V	Insulation class F	Type of Duty S1
Version code 190			

Motor - Technical

Power factor - 1/1 Load 0.81	Motor efficiency - 1/1 Load 73.8 %	Total moment of inertia 0.313 lb ft ²	Starts per hour max. 15
Power factor - 3/4 Load 0.72	Motor efficiency - 3/4 Load 74.8 %	Starting current, direct starting 53 A	
Power factor - 1/2 Load 0.59	Motor efficiency - 1/2 Load 72.3 %	Starting current, star-delta 17.7 A	

Project
Block

Created by Laura Haggard
Created on 3/22/2021 **Last update** 3/22/2021

NP 3069 MT 3~ Adaptive 432


Performance curve



Duty point

Flow
152 US g.p.m.

Head
28.4 ft



Project
Block

Created by Laura Haggard
Created on 3/22/2021 Last update 3/22/2021


Curve: ISO 9906

NP 3069 MT 3~ Adaptive 432

Duty Analysis



Curves according to: Water, pure [100%] ; 39.2°F; 62.42lb/ft³; 1.6891E-5ft²/s




Operating characteristics

Pumps / Systems	Flow	Head	Shaft power	Flow	Head	Shaft power	Hydr.eff.	Specific Energy	NPSHre
1	152 US g.p.m.	28.4 ft	2.73 hp	152 US g.p.m.	28.4 ft	2.73 hp	39.9 %	299 kWh/US Mcf	16.5 ft

Project
Block

Created by Laura Haggard
Created on 3/22/2021 Last update 3/22/2021

Dimensional drawing



Created by Laura Haggard
Created on 3/22/2021 Last update 3/22/2021

WHITNEY EQUIPMENT CO., INC.
WOODINVILLE, WA
STANDARD CONDITIONS OF SALE

These are Whitney Equipment Co., Inc., the Seller, Standard Terms and Conditions and the basis of our offer to the Buyer, unless specifically altered in writing as permitted herein. Any changes may affect the quoted price. These Standard Terms and Conditions and the bid quote, purchase order, or other order form to which they are attached (the "Bid Quote") form a contract between Buyer and Seller for the sale of products described in the Bid Quote (the "Contract").

ACCEPTANCE: Submission of this Contract to Buyer constitutes Seller's offer to the Buyer and on acceptance becomes a binding contract on the terms set forth herein. Buyer's acceptance is expressly limited to the terms of this Contract. Seller rejects all terms included in any response by the Buyer to this Contract that are in conflict with, inconsistent with, or in addition to the terms and conditions contained herein. But if a conflict arises between the terms of a purchase order first issued by Buyer and the terms of this Contract, the terms of this Contract shall take precedence.

ENTIRE AGREEMENT: The Contract comprises the entire agreement between the Buyer and the Seller, and supersedes all prior or contemporaneous understandings, agreements, negotiations, representations and warranties, and communications, both written and oral. This Contract prevails over any terms and conditions of purchase provided by Buyer, regardless whether or when the Buyer has submitted its purchase order or such terms. In addition implied terms and conditions from the Buyer's contracts with other entities are not valid or enforceable with respect this Contract. Fulfillment of the Buyer's order does not constitute acceptance of any of Buyer's terms and conditions and does not serve to modify or amend this Contract.

GOVERNING LAWS: Seller will comply with all laws applicable to Seller during sale of the products. Buyer will comply with all laws applicable to Buyer during operation or use of the products. The laws of the State of Washington shall govern the validity, interpretation and enforcement of any order of which these provisions are a part, without giving effect to any rules governing the conflict of laws. Assignment may be made only with written consent of both parties. Buyer shall be liable to the Seller for any attorney's fees and costs incurred by Seller in enforcing any of its rights hereunder. Unless otherwise specified, any reference to Buyer's order is for identification only.

JURISDICTION AND VENUE: Any legal suit, action or proceeding arising out of relating to this Contract shall be commenced in federal or state court located King County, Washington and Seller and Buyer (i) irrevocably submit to the exclusive jurisdiction and venue of any such court in any such suit, action or proceeding and (ii) irrevocably waive (to the extent permitted by applicable law) any objection which they now or hereafter may have to the laying of venue of any such action or proceeding brought in any of the foregoing courts in and of the State of Washington, and any objection on the ground that any such action or proceeding in any such court has been brought in an inconvenient forum.

ATTORNEYS FEES AND EXPERT COSTS: The prevailing party in any legal suit, action, or proceeding arising out of relating to the Contract shall be awarded its reasonable attorneys' fees and experts costs.

WARRANTY:

THE SELLER MAKES NO WARRANTIES ON ANY PRODUCTS OR SERVICES PROVIDED UNDER THIS CONTRACT, INCLUDING ANY (A) WARRANTY OF MERCHANTABILITY, (B) WARRANTY OF FITNESS FOR A PARTICULAR PURPOSE, OR (C) WARRANTY AGAINST INFRINGEMENT OF INTELLECTUAL PROPERTY RIGHTS OF A THIRD PARTY, WHETHER EXPRESS OR IMPLIED BY LAW, COURSE OF DEALING, COURSE OF PERFORMANCE, USAGE OF TRADE OR OTHERWISE. BUT THE BUYER SHALL RECEIVE WARRANTIES, IF ANY, PROVIDED BY THE MANUFACTURER OF THE PRODUCTS SOLD UNDER THIS CONTRACT. THE SELLER IS EXPRESSLY EXCLUDED FROM ANY WARRANTY AND ALL CHARGES, FOR LABOR, INSTALLATION, REMOVAL, REPAIR, REINSTALLATION, SHIPPING, UTILITIES, EQUIPMENT RENTAL, OTHER REQUIRED MATERIALS, OR ANY OTHER ITEMS. THE PARTIES AGREE THAT THE BUYER'S SOLE AND EXCLUSIVE REMEDIES SHALL BE AGAINST THE PRODUCT MANUFACTURER AS PROVIDED HEREIN. THE BUYER AGREES THAT NO OTHER REMEDY (INCLUDING, BUT NOT LIMITED TO, INCIDENTAL OR CONSEQUENTIAL DAMAGES FOR LOST PROFITS, LOST SALES, DOWNTIME, OPERATING OR MAINTENANCE COSTS, INJURY TO PERSONS OR PROPERTY, OR ANY OTHER SPECIAL, INDIRECT, INCIDENTAL OR CONSEQUENTIAL LOSS) SHALL BE AVAILABLE TO BUYER. BUYER SHALL FOLLOW ALL STORAGE, OPERATION, AND MAINTENANCE PROCEDURES SPECIFIED BY THE MANUFACTURER FOR WARRANTY COVERAGE, FAILURE TO FOLLOW THESE PROCEDURES INCLUDING DOCUMENTATION MAY RESULT IN LOSS OF WARRANTY COVERAGE.

TAXES: Seller does not include any Federal, State, City, County, or other sales, custom duties, or taxes such as sales, use, excise, retailer's, occupation or similar taxes and fees, in the Contract Price unless otherwise explicitly stated in writing. Any taxes not included in the Bid Quote will be added to the Contract Price. In lieu of paying such taxes to the Seller, the Buyer may furnish the Seller with a Tax Exemption Certificate or other legal and appropriate taxing authorities at any time.

PAYMENT TERMS: All quotations or proposals are in US Dollars unless explicitly stated otherwise in writing. Seller shall submit invoices for payment to Buyer for percentages of the Contract Price as described in Bid Quote. Buyer must pay all invoices submitted by Seller no later than 30 days after the date of the invoice. If the shipment is delayed by the Buyer, date of readiness for shipment shall be deemed the date of shipment for payment purposes. The Seller may require advance payment or a certificate of deposit, or may otherwise modify credit terms, should the Buyer's credit standing not meet the Seller's requirements. A service charge of 2.5% per month on the unpaid balance will be charged on all overdue monies payable. Buyer shall not assign or transfer their contract or any interest in it, or monies payable under it, without the written consent of Seller and any assignment made without such consent shall be null and void. Buyer agrees to pay all collection costs and costs of suit, including reasonable attorney fees, in the event Seller institutes collection action for overdue account. Seller expressly reserves all available lien rights in connection with any transaction between the parties. Unless explicitly agreed upon in writing, retainage against the contract amount is not allowed. The Seller reserves the right to re-possess all equipment that is not paid for in full per this Contract's payment terms.

CREDIT CARD PAYMENTS: All credit card payments will require an additional 2% surcharge in addition to the Contract Price listed in the Contract. All credit card payments over \$5000.00 require written pre-approval by the Seller prior to processing; approval is not guaranteed.

CREDIT: Buyer is required to provide all necessary credit information to Seller with each order, including bank reference, bonding company, or other necessary information with complete names, addresses, phone numbers, personal references, and account and bond numbers. The Seller will determine, in its sole discretion, what is acceptable and what credit rating is required for the Seller to allow a purchase on credit.

PRICE: The prices specified are in U.S. currency, payable free of all expense to the Seller for collection charges.

STARTUP PAYMENTS: If startup services are included in this Contract, the pre-agreed upon payment amount shall be due when startup is complete. If startup is delayed more than 90 days after equipment delivery, payment for startup shall be due 90 days after equipment delivery prior to the startup occurring. Delaying in paying this portion of the contract is subject to the PAYMENT TERMS above.

SHIPMENTS AND DELIVERY: Delivery and shipping times are Seller's best estimate and do not include product approval time or order processing time. Seller is not liable for any damages, fees, costs, expenses or penalties arising from (1) loss of or damage to product in transit or (2) delays in shipping or delivery of the product, including all delays caused by an accident; riots; insurrections; national emergency; labor disputes of every kind however caused; embargoes; non-delivery by suppliers; delays of carriers or postal authorities; or governmental restrictions, prohibitions, or requirements. Seller may, in its sole discretion, without liability or penalty, make partial shipments of products to Buyer. Each shipment will constitute a separate sale, and Buyer shall pay for the units shipped whether such shipment is in whole or partial fulfillment of Buyer's order. Cost of handling and freight is only included when it is explicitly listed in this Contract.

NON-DELIVERY: The quantity of any installment of products as recorded by Seller on dispatch from Seller's place of business is conclusive evidence of the quantity received by Buyer on delivery unless Buyer can provide conclusive evidence proving the contrary. Any liability of Seller for non-delivery of the products shall be limited to replacing the products within a reasonable time or adjusting the invoice respecting such products to reflect the actual quantity delivered.

APPROVALS: Buyer is responsible for obtaining approval on products from project owners and engineers. The Seller represents only that products are as described in this Contract. The Seller does not warrant that the products described will be approved or otherwise satisfactory to project owners or engineers, or that products meet project specifications. Seller does not guarantee compliance with any codes or laws unless explicitly stated in this Contract. Performance of the overall system that incorporates the products is not guaranteed.

OCCUPATIONAL SAFETY AND HEALTH ACT OF 1970 – Seller does not warrant or represent that any of Seller's products by themselves or in a system or with other equipment will conform to or comply with the provisions of the Occupational Safety and Health Act of 1970 and the standards and regulations issued thereunder, or any other federal, state, or local law or regulation of the same or similar nature.

LIMITATION OF LIABILITY - NEITHER SELLER, NOR ITS SUPPLIERS SHALL BE LIABLE, WHETHER IN CONTRACT, WARRANTY, FAILURE OF A REMEDY TO ACHIEVE ITS INTENDED OR ESSENTIAL PURPOSES, TORT (INCLUDING NEGLIGENCE), STRICT LIABILITY, INDEMNITY OR ANY OTHER LEGAL THEORY, FOR LOSS OF USE, REVENUE OR PROFIT, OR FOR COSTS OF CAPITAL OR OF SUBSTITUTE USE OR PERFORMANCE, OR FOR INDIRECT, SPECIAL, LIQUIDATED, INCIDENTAL OR CONSEQUENTIAL DAMAGES, OR FOR ANY OTHER LOSS OR COST OF A SIMILAR TYPE, OR FOR CLAIMS BY BUYER FOR DAMAGES OF BUYER'S CUSTOMERS. SELLER'S AGGREGATE LIABILITY ARISING OUT OF OR RELATING TO THIS CONTRACT SHALL NOT EXCEED THE CONTRACT PRICE, PROVIDED HOWEVER, IF THE BID QUOTE INCLUDES FIELD OR STARTUP SERVICE, SELLER'S LIABILITY FOR SAID SERVICES SHALL BE LIMITED TO THE VALUE OF THE SERVICES. BUYER AND SELLER AGREE THAT THE EXCLUSIONS AND LIMITATIONS SET FORTH IN THIS ARTICLE ARE SEPARATE AND INDEPENDENT FROM ANY REMEDIES WHICH BUYER MAY HAVE HEREUNDER AND SHALL BE GIVEN FULL FORCE AND EFFECT REGARDLESS OF WHETHER ANY OR ALL SUCH REMEDIES SHALL BE DEEMED TO HAVE FAILED OF THEIR ESSENTIAL PURPOSE.

STORAGE – If for any reason Buyer fails to accept products that have been delivered by Seller, or if Seller is unable to deliver the products because Buyer has not provided appropriate instructions, documents, licenses or authorizations, then Seller may place the products in storage at Buyer's cost and expense, which includes the cost of storage, shipping fees, insurance and other incidental expenses. The Buyer carries risk of loss for products in storage.

TITLE - Title to the products and risk of loss or damage passes to Buyer upon delivery of the products at the Point of Delivery listed in the Bid Quote. As collateral security for the payment of the Contract Price for the products, Buyer hereby grants to Seller a lien on and security interest in and to all of the right, title and interest of Buyer in, to, and under the products, wherever located, and whether now existing or hereafter arising or acquired from time to time, and in all accessions thereto and replacements or modifications thereof, as well as all proceeds (including insurance proceeds) of the foregoing. The security interest granted under this provision constitutes a purchase money security interest under the Washington Uniform Commercial Code. Buyer agrees to perform all additional acts necessary to perfect and maintain said security interest.

INSURANCE: Buyer shall, at its own expense, purchase, maintain and carry adequate insurance for the products to protect against loss or damage from any external cause, including losses from fire, wind, water or other causes. Insurance coverage must be maintained with insurance companies legally authorized to do business where said products are located in an amount at least equal to the value of said products until the products are accepted and paid for in full. Upon Seller's request, Buyer shall provide Seller with a certificate of insurance from Buyer's insurer evidencing the insurance coverage that is satisfactory to Seller. The certificate of insurance must name Seller as an additional insured. In no case does the Contract Price, even if inclusive of freight, cover the cost of insurance beyond the Point of Delivery specified in the Bid Quote

CANCELLATION: The Buyer may cancel its order only upon written notice, and in turn will make payment to Seller of reasonable cancellation charges specified by Seller.

ORAL STATEMENTS: The Seller's personnel may have made oral statements about the products described in this Contract during the sales process. Such statements do not constitute warranties or guarantees, and shall not be relied on by the Buyer. The entire contract is embodied in this writing. This writing constitutes the final expression of the parties' agreement, and it is a complete and exclusive statement of the terms of that agreement.

CHANGES: Seller reserve the right to make changes and to substitute other material as needed to make shipments and fulfill orders under this Contract.

ERRORS: Seller reserves the right to correct clerical or stenographic errors or omissions.

STATUTE OF LIMITATIONS - To the extent permitted by applicable law, any lawsuit for breach of contract, including breach of warranty, arising out of the transactions covered by this order, must be commenced by the Buyer not later than twelve (12) months from the delivery of Seller's Products or the last day Seller performed any services, whichever is earlier.

INSPECTION: Buyer shall inspect Seller's Products upon receipt, and if Buyer's inspection reveals any defects in the Products, Buyer shall notify the Seller within three (3) days after receipt of the Products of any claim Buyer might have concerning such defects in the Products discovered by Buyer. Buyer's failure to notify Seller within such a three (3) day period shall constitute a waiver by Buyer of all claims covering such defects in the Products. It is the Buyer's responsibility to inspect for shipping damage upon delivery and to initiate a damage claim with the freight carrier. Damage occurring in-transit by the freight carrier must be claimed by the Buyer, and is not the Seller's responsibility.

NOT INCLUDED: Seller does not include any item not specifically listed as included. References to specifications and drawings in the Scope of Supply section of the Bid Quote does not indicate that all items in those documents are included in the Scope of Supply. Unless clearly included in this Contract, engineering and design services are not included in this Contract.

FREIGHT: Prices quoted are F.O.B. point of manufacture and do not include freight unless specifically listed as included. Title passed to the Buyer at the Point of Delivery listed in the Bid Quote and all freight claims are the responsibility of the Buyer.

BACKCHARGES will not be accepted unless approved by Seller, in writing, before any work is done.

DELAYS: Price and terms and conditions are subject to revision if manufacture is not released at time of order placement or drawings for approval are not returned within 30 days from receipt by customer, or manufacture is released and subsequently held or delayed by the customer for more than 30 days, or customer requests longer than quoted shipment. If Seller suffers delay in performance due to any cause beyond its control, including but not limited to act of God, war, pandemic, act or failure to act of government, act or omission of Buyer, fire, flood, strike or labor troubles, sabotage, or delay in obtaining from others suitable services, materials, components, equipment or transportation, the time of performance shall be extended a period of time equal to the period of the delay and its consequences. Seller will give Buyer notice in writing within a reasonable time after the Seller becomes aware of any such delay.

DECOMPOSITION AND WEAR: Decomposition by chemical action and wear caused by the presence of abrasive materials shall not constitute defects.

BUYER DATA - Timely performance is contingent upon the Buyer supplying to the Seller, when needed, all required technical information, including drawing and submittal approval, and all required commercial documentation. The Buyer shall also supply and complete all shipping delivery information, pre-delivery checklists, and pre-startup checklists in a timely manner or the overall schedule of the project may be impacted at no cost to the Seller regardless of any potential agreed upon damages.

BUYER SUPPLIED COMPONENTS - Buyer acknowledges that the products purchased by Buyer under this Contract may contain products supplied by the Buyer or supplied by a third party at the Buyer's direction ("Buyer Supplied Components"). Buyer Supplied Components are not covered by any warranty or guarantee in this Contract. For the avoidance of doubt, Seller makes no representations or warranties with respect to any Buyer Supplied Components. Seller disclaims any liability arising from Buyer Supplied Components delivered late, damaged, defective, or nonconforming. In no event shall Seller be liable for consequential, indirect, incidental, special, exemplary, punitive damages, or lost profits, arising out of or relating to late delivery of or defective Buyer Supplied Components. Subject to the terms and conditions of this Contract, Buyer shall indemnify, defend and hold harmless Seller and its representatives/officers, directors, employees, agents, affiliates, successors and permitted assigns ("Indemnified Party") against any and all losses, damages, liabilities, deficiencies, claims, actions, judgments, settlements, interest, awards, penalties, fines, costs, or expenses of whatever kind, including attorney and expert fees, fees and costs of enforcing any right to indemnification under this Contract, and the cost of pursuing any insurance providers, incurred by Indemnified Party in a final judgment relating to any third-party claims arising from defective Buyer Supplied Components.

APPENDIX F

CONTRACTING AGENCY-FURNISHED PERMITS

THIS PAGE INTENTIONALLY LEFT BLANK



Kitsap County Department of Community Development

May 3, 2021

Stella Vakarcs, PE, svakarcs@co.kitsap.wa.us
Barbara Zaroff, PE, BZaroff@co.kitsap.wa.us
Kitsap County Public Works
614 Division ST, MS 26
Port Orchard, WA 98366

**RE: Pump Station 19 Upgrade, SDAP
20-03420 PLAN ACCEPTANCE**

We have reviewed and accept for construction the civil site plans for the above referenced project. This permit must be issued within **365** days from the date of approval letter, per Kitsap County Code 12.10.055. Per the Department of Community Development/Public Works (DCD/PW) SDAP Procedure, the following documents must be uploaded to SMARTGov prior to KCPW self-issuing the permit:


1. Final Approved Plan Set
2. Final Approved Drainage Report, if revised after 90% design stage
3. Construction Stormwater Pollution Prevention Plan (SWPPP)
4. Certificate of Liability Insurance

After construction is complete the following must be uploaded to SMARTGov in order for DCD to complete the permit close-out:

1. Inspection Dates
2. Project As-builts
3. Photo-documentation of required critical area planting.

This letter follows the SDAP procedure established between the two departments; please refer to the Site Development Activity Permit for Capital Projects Process Procedure document for more information on the process. If we can be of further assistance, please contact **Jenifer Lawrence** at (360) 337-5777.

Sincerely,



Jenifer Lawrence, Project Lead

04/30/2021
Date



Samantha Long, Development Services and Engineering
Supervisor

04/30/2021
Date

Cc: Tony Carroll, tcarroll@co.kitsap.wa.us



Kitsap County Department of Community Development

May 3, 2021

Stella Vakarcs, PE, svakarcs@co.kitsap.wa.us
Barbara Zaroff, PE, BZaroff@co.kitsap.wa.us
Kitsap County Public Works
614 Division ST, MS 26
Port Orchard, WA 98366

**RE: Pump Station 31 Upgrade, SDAP
20-03419 PLAN ACCEPTANCE**

We have reviewed and accept for construction the civil site plans for the above referenced project. This permit must be issued within **365** days from the date of approval letter, per Kitsap County Code 12.10.055. Per the Department of Community Development/Public Works (DCD/PW) SDAP Procedure, the following documents must be uploaded to SMARTGov prior to KCPW self-issuing the permit:

1. Final Approved Plan Set
2. Final Approved Drainage Report, if revised after 90% design stage
3. Construction Stormwater Pollution Prevention Plan (SWPPP)
4. Certificate of Liability Insurance

After construction is complete the following must be uploaded to SMARTGov in order for DCD to complete the permit close-out:

1. Inspection Dates
2. Project As-builts
3. Photo-documentation of required critical area planting.

This letter follows the SDAP procedure established between the two departments; please refer to the Site Development Activity Permit for Capital Projects Process Procedure document for more information on the process. If we can be of further assistance, please contact **Jenifer Lawrence** at (360) 337-5777.

Sincerely,



Jenifer Lawrence, Project Lead

04/30/2021
Date



Samantha Long, Development Services and Engineering
Supervisor

04/30/2021
Date

Cc: Tony Carroll, tcarroll@co.kitsap.wa.us

Issuance Date: November 18, 2020
Effective Date: January 1, 2021
Expiration Date: December 31, 2025

CONSTRUCTION STORMWATER GENERAL PERMIT

National Pollutant Discharge Elimination System (NPDES) and State Waste Discharge
General Permit for Stormwater Discharges Associated with Construction Activity

State of Washington
Department of Ecology
Olympia, Washington 98504

In compliance with the provisions of
Chapter 90.48 Revised Code of Washington
(State of Washington Water Pollution Control Act)
and
Title 33 United States Code, Section 1251 et seq.
The Federal Water Pollution Control Act (The Clean Water Act)

Until this permit expires, is modified, or revoked, Permittees that have properly
obtained coverage under this general permit are authorized to discharge in accordance
with the special and general conditions that follow.



Vincent McGowan, P.E.
Water Quality Program Manager
Washington State Department of Ecology

TABLE OF CONTENTS

LIST OF TABLES	ii
SUMMARY OF PERMIT REPORT SUBMITTALS.....	1
SPECIAL CONDITIONS	3
S1. Permit Coverage	3
S2. Application Requirements	7
S3. Compliance with Standards	9
S4. Monitoring Requirements, Benchmarks, and Reporting Triggers	10
S5. Reporting and Recordkeeping Requirements.....	17
S6. Permit Fees	20
S7. Solid and Liquid Waste Disposal	20
S8. Discharges to 303(D) or TMDL Waterbodies	20
S9. Stormwater Pollution Prevention Plan	23
S10. Notice Of Termination	32
GENERAL CONDITIONS	34
G1. Discharge Violations.....	34
G2. Signatory Requirements	34
G3. Right of Inspection and Entry.....	35
G4. General Permit Modification and Revocation	35
G5. Revocation of Coverage Under tPermit.....	35
G6. Reporting a Cause for Modification	36
G7. Compliance with Other Laws and Statutes.....	36
G8. Duty to Reapply.....	36
G9. Removed Substance.....	36
G10. Duty to Provide Information	36
G11. Other Requirements of 40 CFR	37
G12. Additional Monitoring.....	37
G13. Penalties for Violating Permit Conditions.....	37
G14. Upset.....	37
G15. Property Rights	37
G16. Duty to Comply	37
G17. Toxic Pollutants.....	38
G18. Penalties for Tampering.....	38
G19. Reporting Planned Changes.....	38
G20. Reporting Other Information.....	38
G21. Reporting Anticipated Non-Compliance	38

G22.	Requests to Be Excluded From Coverage Under the Permit	39
G23.	Appeals.....	39
G24.	Severability.....	39
G25.	Bypass Prohibited	39
APPENDIX A – DEFINITIONS.....		42
APPENDIX B – ACRONYMS.....		50

LIST OF TABLES

Table 1	Summary of Required Submittals.....	1
Table 2	Summary of Required On-site Documentation	2
Table 3	Summary of Primary Monitoring Requirements	12
Table 4	Monitoring and Reporting Requirements	14
Table 5	Turbidity, Fine Sediment & Phosphorus Sampling and Limits for 303(d)-Listed Waters	22
Table 6	pH Sampling and Limits for 303(d)-Listed Waters.....	22

SUMMARY OF PERMIT REPORT SUBMITTALS

Refer to the Special and General Conditions within this permit for additional submittal requirements. Appendix A provides a list of definitions. Appendix B provides a list of acronyms.

Table 1 Summary of Required Submittals

Permit Section	Submittal	Frequency	First Submittal Date
S5.A and S8	High Turbidity/Transparency Phone Reporting	As Necessary	Within 24 hours
S5.B	Discharge Monitoring Report	Monthly*	Within 15 days following the end of each month
S5.F and S8	Noncompliance Notification – Telephone Notification	As necessary	Within 24 hours
S5.F	Noncompliance Notification – Written Report	As necessary	Within 5 Days of non-compliance
S9.D	Request for Chemical Treatment Form	As necessary	Written approval from Ecology is required prior to using chemical treatment (with the exception of dry ice, CO ₂ or food grade vinegar to adjust pH)
G2	Notice of Change in Authorization	As necessary	
G6	Permit Application for Substantive Changes to the Discharge	As necessary	
G8	Application for Permit Renewal	1/permit cycle	No later than 180 days before expiration
S2.A	Notice of Permit Transfer	As necessary	
G19	Notice of Planned Changes	As necessary	
G21	Reporting Anticipated Non-compliance	As necessary	

NOTE: *Permittees must submit electronic Discharge Monitoring Reports (DMRs) to the Washington State Department of Ecology monthly, regardless of site discharge, for the full duration of permit coverage. Refer to Section S5.B of this General Permit for more specific information regarding DMRs.

Table 2 Summary of Required On-site Documentation

Document Title	Permit Conditions
Permit Coverage Letter	See Conditions S2, S5
Construction Stormwater General Permit (CSWGP)	See Conditions S2, S5
Site Log Book	See Conditions S4, S5
Stormwater Pollution Prevention Plan (SWPPP)	See Conditions S5, S9
Site Map	See Conditions S5, S9

SPECIAL CONDITIONS

S1. PERMIT COVERAGE

A. Permit Area

This Construction Stormwater General Permit (CSWGP) covers all areas of Washington State, except for federal operators and Indian Country as specified in Special Condition S1.E.3 and 4.

B. Operators Required to Seek Coverage Under this General Permit

1. Operators of the following construction activities are required to seek coverage under this CSWGP:
 - a. Clearing, grading and/or excavation that results in the disturbance of one or more acres (including off-site disturbance acreage related to construction-support activity as authorized in S1.C.2) and discharges stormwater to surface waters of the State; and clearing, grading and/or excavation on sites smaller than one acre that are part of a larger common plan of development or sale, if the common plan of development or sale will ultimately disturb one acre or more and discharge stormwater to surface waters of the State.
 - i. This category includes forest practices (including, but not limited to, class IV conversions) that are part of a construction activity that will result in the disturbance of one or more acres, and discharge to surface waters of the State (that is, forest practices that prepare a site for construction activities); and
 - b. Any size construction activity discharging stormwater to waters of the State that the Washington State Department of Ecology (Ecology):
 - i. Determines to be a significant contributor of pollutants to waters of the State of Washington.
 - ii. Reasonably expects to cause a violation of any water quality standard.
2. Operators of the following activities are not required to seek coverage under this CSWGP (unless specifically required under Special Condition S1.B.1.b, above):
 - a. Construction activities that discharge all stormwater and non-stormwater to groundwater, sanitary sewer, or combined sewer, and have no point source discharge to either surface water or a storm sewer system that drains to surface waters of the State.
 - b. Construction activities covered under an Erosivity Waiver (Special Condition S1.F).
 - c. Routine maintenance that is performed to maintain the original line and grade, hydraulic capacity, or original purpose of a facility.

C. Authorized Discharges

1. ***Stormwater Associated with Construction Activity.*** Subject to compliance with the terms and conditions of this permit, Permittees are authorized to discharge stormwater associated with construction activity to surface waters of the State or to a storm sewer system that drains to surface waters of the State. (Note that “surface waters of the

State” may exist on a construction site as well as off site; for example, a creek running through a site.)

2. ***Stormwater Associated with Construction Support Activity.*** This permit also authorizes stormwater discharge from support activities related to the permitted construction site (for example, an on-site portable rock crusher, off-site equipment staging yards, material storage areas, borrow areas, etc.) provided:
 - a. The support activity relates directly to the permitted construction site that is required to have an NPDES permit; and
 - b. The support activity is not a commercial operation serving multiple unrelated construction projects, and does not operate beyond the completion of the construction activity; and
 - c. Appropriate controls and measures are identified in the Stormwater Pollution Prevention Plan (SWPPP) for the discharges from the support activity areas.
3. ***Non-Stormwater Discharges.*** The categories and sources of non-stormwater discharges identified below are authorized conditionally, provided the discharge is consistent with the terms and conditions of this permit:
 - a. Discharges from fire-fighting activities.
 - b. Fire hydrant system flushing.
 - c. Potable water, including uncontaminated water line flushing.
 - d. Hydrostatic test water.
 - e. Uncontaminated air conditioning or compressor condensate.
 - f. Uncontaminated groundwater or spring water.
 - g. Uncontaminated excavation dewatering water (in accordance with S9.D.10).
 - h. Uncontaminated discharges from foundation or footing drains.
 - i. Uncontaminated or potable water used to control dust. Permittees must minimize the amount of dust control water used.
 - j. Routine external building wash down that does not use detergents.
 - k. Landscape irrigation water.

The SWPPP must adequately address all authorized non-stormwater discharges, except for discharges from fire-fighting activities, and must comply with Special Condition S3. At a minimum, discharges from potable water (including water line flushing), fire hydrant system flushing, and pipeline hydrostatic test water must undergo the following: dechlorination to a concentration of 0.1 parts per million (ppm) or less, and pH adjustment to within 6.5 – 8.5 standard units (su), if necessary.

D. Prohibited Discharges

The following discharges to waters of the State, including groundwater, are prohibited:

1. Concrete wastewater
2. Wastewater from washout and clean-up of stucco, paint, form release oils, curing compounds and other construction materials.
3. Process wastewater as defined by 40 Code of Federal Regulations (CFR) 122.2 (See Appendix A of this permit).
4. Slurry materials and waste from shaft drilling, including process wastewater from shaft drilling for construction of building, road, and bridge foundations unless managed according to Special Condition S9.D.9.j.
5. Fuels, oils, or other pollutants used in vehicle and equipment operation and maintenance.
6. Soaps or solvents used in vehicle and equipment washing.
7. Wheel wash wastewater, unless managed according to Special Condition S9.D.9.
8. Discharges from dewatering activities, including discharges from dewatering of trenches and excavations, unless managed according to Special Condition S9.D.10.

E. Limits on Coverage

Ecology may require any discharger to apply for and obtain coverage under an individual permit or another more specific general permit. Such alternative coverage will be required when Ecology determines that this CSWGP does not provide adequate assurance that water quality will be protected, or there is a reasonable potential for the project to cause or contribute to a violation of water quality standards.

The following stormwater discharges are not covered by this permit:

1. Post-construction stormwater discharges that originate from the site after completion of construction activities and the site has undergone final stabilization.
2. Non-point source silvicultural activities such as nursery operations, site preparation, reforestation and subsequent cultural treatment, thinning, prescribed burning, pest and fire control, harvesting operations, surface drainage, or road construction and maintenance, from which there is natural runoff as excluded in 40 CFR Subpart 122.
3. Stormwater from any federal operator.
4. Stormwater from facilities located on **Indian Country** as defined in 18 U.S.C. §1151, except portions of the Puyallup Reservation as noted below.

Indian Country includes:

- a. All land within any Indian Reservation notwithstanding the issuance of any patent, and, including rights-of-way running through the reservation. This includes all federal, tribal, and Indian and non-Indian privately owned land within the reservation.
- b. All off-reservation Indian allotments, the Indian titles to which have not been extinguished, including rights-of-way running through the same.
- c. All off-reservation federal trust lands held for Native American Tribes.

Puyallup Exception: Following the *Puyallup Tribes of Indians Land Settlement Act of 1989*, 25 U.S.C. §1773; the permit does apply to land within the Puyallup Reservation except for discharges to surface water on land held in trust by the federal government.

5. Stormwater from any site covered under an existing NPDES individual permit in which stormwater management and/or treatment requirements are included for all stormwater discharges associated with construction activity.
6. Stormwater from a site where an applicable Total Maximum Daily Load (TMDL) requirement specifically precludes or prohibits discharges from construction activity.

F. Erosivity Waiver

Construction site operators may qualify for an Erosivity Waiver from the CSWGP if the following conditions are met:

1. The site will result in the disturbance of fewer than five (5) acres and the site is not a portion of a common plan of development or sale that will disturb five (5) acres or greater.
2. Calculation of Erosivity “R” Factor and Regional Timeframe:
 - a. The project’s calculated rainfall erosivity factor (“R” Factor) must be less than five (5) during the period of construction activity, (See the CSWGP homepage <http://www.ecy.wa.gov/programs/wq/stormwater/construction/index.html> for a link to the EPA’s calculator and step by step instructions on computing the “R” Factor in the *EPA Erosivity Waiver Fact Sheet*). The period of construction activity starts when the land is first disturbed and ends with final stabilization. In addition:
 - b. The entire period of construction activity must fall within the following timeframes:
 - i. For sites west of the Cascades Crest: June 15 – September 15.
 - ii. For sites east of the Cascades Crest, excluding the Central Basin: June 15 – October 15.
 - iii. For sites east of the Cascades Crest, within the Central Basin: no timeframe restrictions apply. The Central Basin is defined as the portions of Eastern Washington with mean annual precipitation of less than 12 inches. For a map of the Central Basin (Average Annual Precipitation Region 2), refer to: <http://www.ecy.wa.gov/programs/wq/stormwater/construction/resourcesguidance.html>.
3. Construction site operators must submit a complete Erosivity Waiver certification form at least one week before disturbing the land. Certification must include statements that the operator will:
 - a. Comply with applicable local stormwater requirements; and
 - b. Implement appropriate erosion and sediment control BMPs to prevent violations of water quality standards.
4. This waiver is not available for facilities declared significant contributors of pollutants as defined in Special Condition S1.B.1.b or for any size construction activity that could

reasonably expect to cause a violation of any water quality standard as defined in Special Condition S1.B.1.b.ii.

5. This waiver does not apply to construction activities which include non-stormwater discharges listed in Special Condition S1.C.3.
6. If construction activity extends beyond the certified waiver period for any reason, the operator must either:
 - a. Recalculate the rainfall erosivity “R” factor using the original start date and a new projected ending date and, if the “R” factor is still under 5 *and* the entire project falls within the applicable regional timeframe in Special Condition S1.F.2.b, complete and submit an amended waiver certification form before the original waiver expires; *or*
 - b. Submit a complete permit application to Ecology in accordance with Special Condition S2.A and B before the end of the certified waiver period.

S2. APPLICATION REQUIREMENTS

A. Permit Application Forms

1. *Notice of Intent Form*

- a. Operators of new or previously unpermitted construction activities must submit a complete and accurate permit application (Notice of Intent, or NOI) to Ecology.
- b. Operators must apply using the electronic application form (NOI) available on Ecology’s website (<http://ecy.wa.gov/programs/wq/stormwater/construction/index.html>). Permittees unable to submit electronically (for example, those who do not have an internet connection) must contact Ecology to request a waiver and obtain instructions on how to obtain a paper NOI.

Department of Ecology
Water Quality Program - Construction Stormwater
PO Box 47696
Olympia, Washington 98504-7696

- c. The operator must submit the NOI at least 60 days before discharging stormwater from construction activities and must submit it prior to the date of the first public notice (See Special Condition S2.B, below, for details). The 30-day public comment period begins on the publication date of the second public notice. Unless Ecology responds to the complete application in writing, coverage under the general permit will automatically commence on the 31st day following receipt by Ecology of a *completed* NOI, or the issuance date of this permit, whichever is later; unless Ecology specifies a later date in writing as required by WAC173-226-200(2). See S8.B for Limits on Coverage for New Discharges to TMDL or 303(d)-Listed Waters.
- d. If an applicant intends to use a Best Management Practice (BMP) selected on the basis of Special Condition S9.C.4 (“demonstrably equivalent” BMPs), the applicant must notify Ecology of its selection as part of the NOI. In the event the applicant selects BMPs after submission of the NOI, the applicant must provide notice of the

selection of an equivalent BMP to Ecology at least 60 days before intended use of the equivalent BMP.

- e. Applicants must notify Ecology if they are aware of contaminated soils and/or groundwater associated with the construction activity. Provide detailed information with the NOI (as known and readily available) on the nature and extent of the contamination (concentrations, locations, and depth), as well as pollution prevention and/or treatment BMPs proposed to control the discharge of soil and/or groundwater contaminants in stormwater. Examples of such detail may include, but are not limited to:
 - i. List or table of all known contaminants with laboratory test results showing concentration and depth,
 - ii. Map with sample locations,
 - iii. Related portions of the Stormwater Pollution Prevention Plan (SWPPP) that address the management of contaminated and potentially contaminated construction stormwater and dewatering water,
 - iv. Dewatering plan and/or dewatering contingency plan.

2. *Transfer of Coverage Form*

The Permittee can transfer current coverage under this permit to one or more new operators, including operators of sites within a Common Plan of Development, provided:

- i. The Permittee submits a complete Transfer of Coverage Form to Ecology, signed by the current and new discharger and containing a specific date for transfer of permit responsibility, coverage and liability (including any Administrative Orders associated with the permit); and
- ii. Ecology does not notify the current discharger and new discharger of intent to revoke coverage under the general permit. If this notice is not given, the transfer is effective on the date specified in the written agreement.

When a current discharger (Permittee) transfers a portion of a permitted site, the current discharger must also indicate the remaining permitted acreage after the transfer. Transfers do not require public notice.

3. *Modification of Coverage Form*

Permittees must notify Ecology regarding any changes to the information provided on the NOI by submitting an Update/Modification of Permit Coverage form in accordance with General Conditions G6 and G19. Examples of such changes include, but are not limited to:

- i. Changes to the Permittee's mailing address,
- ii. Changes to the on-site contact person information, and
- iii. Changes to the area/acreage affected by construction activity.

B. Public Notice

For new or previously unpermitted construction activities, the applicant must publish a public notice at least one time each week for two consecutive weeks, at least 7 days apart, in a newspaper with general circulation in the county where the construction is to take place. The notice must be run after the NOI has been submitted and must contain:

1. A statement that *“The applicant is seeking coverage under the Washington State Department of Ecology’s Construction Stormwater NPDES and State Waste Discharge General Permit.”*
2. The name, address, and location of the construction site.
3. The name and address of the applicant.
4. The type of construction activity that will result in a discharge (for example, residential construction, commercial construction, etc.), and the total number of acres to be disturbed over the lifetime of the project.
5. The name of the receiving water(s) (that is, the surface water(s) to which the site will discharge), or, if the discharge is through a storm sewer system, the name of the operator of the system and the receiving water(s) the system discharges to.
6. The statement: *Any persons desiring to present their views to the Washington State Department of Ecology regarding this application, or interested in Ecology’s action on this application, may notify Ecology in writing no later than 30 days of the last date of publication of this notice. Ecology reviews public comments and considers whether discharges from this project would cause a measurable change in receiving water quality, and, if so, whether the project is necessary and in the overriding public interest according to Tier II antidegradation requirements under WAC 173-201A-320. Comments can be submitted to: Department of Ecology, PO Box 47696, Olympia, Washington 98504-7696 Attn: Water Quality Program, Construction Stormwater.*

S3. COMPLIANCE WITH STANDARDS

- A. Discharges must not** cause or contribute to a violation of surface water quality standards (Chapter 173-201A WAC), groundwater quality standards (Chapter 173-200 WAC), sediment management standards (Chapter 173-204 WAC), and human health-based criteria in the Federal water quality criteria applicable to Washington. (40 CFR Part 131.45) Discharges that are not in compliance with these standards are prohibited.
- B. Prior to the discharge** of stormwater and non-stormwater to waters of the State, the Permittee must apply All Known, Available, and Reasonable methods of prevention, control, and Treatment (AKART). This includes the preparation and implementation of an adequate SWPPP, with all appropriate BMPs installed and maintained in accordance with the SWPPP and the terms and conditions of this permit.
- C. Ecology presumes** that a Permittee complies with water quality standards unless discharge monitoring data or other site-specific information demonstrates that a discharge causes or contributes to a violation of water quality standards, when the Permittee complies with the following conditions. The Permittee must fully:

1. Comply with all permit conditions, including; planning, sampling, monitoring, reporting, and recordkeeping conditions.
 2. Implement stormwater BMPs contained in stormwater management manuals published or approved by Ecology, or BMPs that are demonstrably equivalent to BMPs contained in stormwater management manuals published or approved by Ecology, including the proper selection, implementation, and maintenance of all applicable and appropriate BMPs for on-site pollution control. (For purposes of this section, the stormwater manuals listed in Appendix 10 of the *Phase I Municipal Stormwater Permit* are approved by Ecology.)
- D. Where construction sites** also discharge to groundwater, the groundwater discharges must also meet the terms and conditions of this CSWGP. Permittees who discharge to groundwater through an injection well must also comply with any applicable requirements of the Underground Injection Control (UIC) regulations, Chapter 173-218 WAC.

S4. MONITORING REQUIREMENTS, BENCHMARKS, AND REPORTING TRIGGERS

A. Site Log Book

The Permittee must maintain a site log book that contains a record of the implementation of the SWPPP and other permit requirements, including the installation and maintenance of BMPs, site inspections, and stormwater monitoring.

B. Site Inspections

Construction sites one (1) acre or larger that discharge stormwater to surface waters of the State must have site inspections conducted by a Certified Erosion and Sediment Control Lead (CESCL). Sites less than one (1) acre may have a person without CESCL certification conduct inspections. (See Special Conditions S4.B.3 and B.4, below, for detailed requirements of the Permittee's CESCL.)

Site inspections must include all areas disturbed by construction activities, all BMPs, and all stormwater discharge points under the Permittee's operational control.

1. The Permittee must have staff knowledgeable in the principles and practices of erosion and sediment control. The CESCL (sites one acre or more) or inspector (sites less than one acre) must have the skills to assess the:
 - a. Site conditions and construction activities that could impact the quality of stormwater; and
 - b. Effectiveness of erosion and sediment control measures used to control the quality of stormwater discharges. The SWPPP must identify the CESCL or inspector, who must be present on site or on-call at all times. The CESCL (sites one (1) acre or more) must obtain this certification through an approved erosion and sediment control training program that meets the minimum training standards established by Ecology. (See BMP C160 in the manual, referred to in Special Condition S9.C.1 and 2.)
2. The CESCL or inspector must examine stormwater visually for the presence of suspended sediment, turbidity, discoloration, and oil sheen. BMP effectiveness must be evaluated to

determine if it is necessary to install, maintain, or repair BMPs to improve the quality of stormwater discharges.

Based on the results of the inspection, the Permittee must correct the problems identified, by:

- a. Reviewing the SWPPP for compliance with Special Condition S9 and making appropriate revisions within 7 days of the inspection.
 - b. Immediately beginning the process of fully implementing and maintaining appropriate source control and/or treatment BMPs, within 10 days of the inspection. If installation of necessary treatment BMPs is not feasible within 10 days, Ecology may approve additional time when an extension is requested by a Permittee within the initial 10-day response period.
 - c. Documenting BMP implementation and maintenance in the site log book.
3. The CESCL or inspector must inspect all areas disturbed by construction activities, all BMPs, and all stormwater discharge points at least once every calendar week and within 24 hours of any discharge from the site. (For purposes of this condition, individual discharge events that last more than one (1) day do not require daily inspections. For example, if a stormwater pond discharges continuously over the course of a week, only one (1) inspection is required that week.) Inspection frequency may be reduced to once every calendar month for inactive sites that are temporarily stabilized.
4. The Permittee must summarize the results of each inspection in an inspection report or checklist and enter the report/checklist into, or attach it to, the site log book. At a minimum, each inspection report or checklist must include:
 - a. Inspection date and time.
 - b. Weather information.
 - c. The general conditions during inspection.
 - d. The approximate amount of precipitation since the last inspection.
 - e. The approximate amount of precipitation within the last 24 hours.
 - f. A summary or list of all implemented BMPs, including observations of all erosion/sediment control structures or practices.
 - g. A description of:
 - i. BMPs inspected (including location).
 - ii. BMPs that need maintenance and why.
 - iii. BMPs that failed to operate as designed or intended, and
 - iv. Where additional or different BMPs are needed, and why.
 - h. A description of stormwater discharged from the site. The Permittee must note the presence of suspended sediment, turbidity, discoloration, and oil sheen, as applicable.

- i. Any water quality monitoring performed during inspection.
- j. General comments and notes, including a brief description of any BMP repairs, maintenance, or installations made following the inspection.
- k. An implementation schedule for the remedial actions that the Permittee plans to take if the site inspection indicates that the site is out of compliance. The remedial actions taken must meet the requirements of the SWPPP and the permit.
- l. A summary report of the inspection.
- m. The name, title, and signature of the person conducting the site inspection, a phone number or other reliable method to reach this person, and the following statement:
I certify that this report is true, accurate, and complete to the best of my knowledge and belief.

Table 3 Summary of Primary Monitoring Requirements

Size of Soil Disturbance ¹	Weekly Site Inspections	Weekly Sampling w/ Turbidity Meter	Weekly Sampling w/ Transparency Tube	Weekly pH Sampling ²	CESCL Required for Inspections?
Sites that disturb less than 1 acre, but are part of a larger Common Plan of Development	Required	Not Required	Not Required	Not Required	No
Sites that disturb 1 acre or more, but fewer than 5 acres	Required	Sampling Required – either method ³		Required	Yes
Sites that disturb 5 acres or more	Required	Required	Not Required ⁴	Required	Yes

¹ Soil disturbance is calculated by adding together all areas that will be affected by construction activity. Construction activity means clearing, grading, excavation, and any other activity that disturbs the surface of the land, including ingress/egress from the site.

² If construction activity results in the disturbance of 1 acre or more, and involves significant concrete work (1,000 cubic yards of concrete or recycled concrete placed or poured over the life of a project) or the use of engineered soils (soil amendments including but not limited to Portland cement-treated base [CTB], cement kiln dust [CKD], or fly ash), and stormwater from the affected area drains to surface waters of the State or to a storm sewer stormwater collection system that drains to other surface waters of the State, the Permittee must conduct pH sampling in accordance with Special Condition S4.D.

³ Sites with one or more acres, but fewer than 5 acres of soil disturbance, must conduct turbidity or transparency sampling in accordance with Special Condition S4.C.4.a or b.

⁴ Sites equal to or greater than 5 acres of soil disturbance must conduct turbidity sampling using a turbidity meter in accordance with Special Condition S4.C.4.a.

C. Turbidity/Transparency Sampling Requirements

1. Sampling Methods

- a. If construction activity involves the disturbance of five (5) acres or more, the Permittee must conduct turbidity sampling per Special Condition S4.C.4.a, below.
- b. If construction activity involves one (1) acre or more but fewer than five (5) acres of soil disturbance, the Permittee must conduct either transparency sampling *or* turbidity sampling per Special Condition S4.C.4.a or b, below.

2. Sampling Frequency

- a. The Permittee must sample all discharge points at least once every calendar week when stormwater (or authorized non-stormwater) discharges from the site or enters any on-site surface waters of the state (for example, a creek running through a site); sampling is not required on sites that disturb less than an acre.
- b. Samples must be representative of the flow and characteristics of the discharge.
- c. Sampling is not required when there is no discharge during a calendar week.
- d. Sampling is not required outside of normal working hours or during unsafe conditions.
- e. If the Permittee is unable to sample during a monitoring period, the Permittee must include a brief explanation in the monthly Discharge Monitoring Report (DMR).
- f. Sampling is not required before construction activity begins.
- g. The Permittee may reduce the sampling frequency for temporarily stabilized, inactive sites to once every calendar month.

3. Sampling Locations

- a. Sampling is required at all points where stormwater associated with construction activity (or authorized non-stormwater) is discharged off site, including where it enters any on-site surface waters of the state (for example, a creek running through a site).
- b. The Permittee may discontinue sampling at discharge points that drain areas of the project that are fully stabilized to prevent erosion.
- c. The Permittee must identify all sampling point(s) in the SWPPP and on the site map and clearly mark these points in the field with a flag, tape, stake or other visible marker.
- d. Sampling is not required for discharge that is sent directly to sanitary or combined sewer systems.
- e. The Permittee may discontinue sampling at discharge points in areas of the project where the Permittee no longer has operational control of the construction activity.

4. Sampling and Analysis Methods

- a. The Permittee performs turbidity analysis with a calibrated turbidity meter (turbidimeter) either on site or at an accredited lab. The Permittee must record the results in the site log book in nephelometric turbidity units (NTUs).
- b. The Permittee performs transparency analysis on site with a 1¾ inch diameter, 60 centimeter (cm)-long transparency tube. The Permittee will record the results in the site log book in centimeters (cm).

Table 4 Monitoring and Reporting Requirements

Parameter	Unit	Analytical Method	Sampling Frequency	Benchmark Value
Turbidity	NTU	SM2130	Weekly, if discharging	25 NTUs
Transparency	Cm	Manufacturer instructions, or Ecology guidance	Weekly, if discharging	33 cm

5. Turbidity/Transparency Benchmark Values and Reporting Triggers

The benchmark value for turbidity is 25 NTUs. The benchmark value for transparency is 33 centimeters (cm). Note: Benchmark values do not apply to discharges to segments of water bodies on Washington State's 303(d) list (Category 5) for turbidity, fine sediment, or phosphorus; these discharges are subject to a numeric effluent limit for turbidity. Refer to Special Condition S8 for more information and follow S5.F – Noncompliance Notification for reporting requirements applicable to discharges which exceed the numeric effluent limit for turbidity.

- a. Turbidity 26 – 249 NTUs, or Transparency 32 – 7 cm:

If the discharge turbidity is 26 to 249 NTUs; or if discharge transparency is 32 to 7 cm, the Permittee must:

- i. Immediately begin the process to fully implement and maintain appropriate source control and/or treatment BMPs, and no later than 10 days of the date the discharge exceeded the benchmark. If installation of necessary treatment BMPs is not feasible within 10 days, Ecology may approve additional time when the Permittee requests an extension within the initial 10-day response period.
- ii. Review the SWPPP for compliance with Special Condition S9 and make appropriate revisions within 7 days of the date the discharge exceeded the benchmark.
- iii. Document BMP implementation and maintenance in the site log book.

- b. Turbidity 250 NTUs or greater, or Transparency 6 cm or less:

If a discharge point's turbidity is 250 NTUs or greater, or if discharge transparency is less than or equal to 6 cm, the Permittee must complete the reporting and adaptive

management process described below. For discharges which are subject to a numeric effluent limit for turbidity, see S5.F – Noncompliance Notification.

- i. Within 24 hours, telephone or submit an electronic report to the applicable Ecology Region's Environmental Report Tracking System (ERTS) number (or through Ecology's Water Quality Permitting Portal [WQWebPortal] – Permit Submittals when the form is available), in accordance with Special Condition S5.A.
 - **Central Region** (Okanogan, Chelan, Douglas, Kittitas, Yakima, Klickitat, Benton): (509) 575-2490
 - **Eastern Region** (Adams, Asotin, Columbia, Ferry, Franklin, Garfield, Grant, Lincoln, Pend Oreille, Spokane, Stevens, Walla Walla, Whitman): (509) 329-3400
 - **Northwest Region** (Kitsap, Snohomish, Island, King, San Juan, Skagit, Whatcom): (425) 649-7000
 - **Southwest Region** (Grays Harbor, Lewis, Mason, Thurston, Pierce, Clark, Cowlitz, Skamania, Wahkiakum, Clallam, Jefferson, Pacific): (360) 407-6300

These numbers and a link to the ERTS reporting page are also listed at the following website: <http://www.ecy.wa.gov/programs/wq/stormwater/construction/index.html>.

- ii. Immediately begin the process to fully implement and maintain appropriate source control and/or treatment BMPs as soon as possible, addressing the problems within 10 days of the date the discharge exceeded the benchmark. If installation of necessary treatment BMPs is not feasible within 10 days, Ecology may approve additional time when the Permittee requests an extension within the initial 10-day response period.
- iii. Sample discharges daily until:
 - a) Turbidity is 25 NTUs (or lower); or
 - b) Transparency is 33 cm (or greater); or
 - c) The Permittee has demonstrated compliance with the water quality standard for turbidity:
 - 1) No more than 5 NTUs over background turbidity, if background is less than 50 NTUs, or
 - 2) No more than 10% over background turbidity, if background is 50 NTUs or greater; or

*Note: background turbidity in the receiving water must be measured immediately upstream (upgradient) or outside of the area of influence of the discharge.
 - d) The discharge stops or is eliminated.
- iv. Review the SWPPP for compliance with Special Condition S9 and make appropriate revisions within seven (7) days of the date the discharge exceeded the benchmark.

- v. Document BMP implementation and maintenance in the site log book.

Compliance with these requirements does not relieve the Permittee from responsibility to maintain continuous compliance with permit benchmarks.

D. pH Sampling Requirements – Significant Concrete Work or Engineered Soils

If construction activity results in the disturbance of 1 acre or more, *and* involves significant concrete work (significant concrete work means greater than 1000 cubic yards placed or poured concrete or recycled concrete used over the life of a project) or the use of engineered soils (soil amendments including but not limited to Portland cement-treated base [CTB], cement kiln dust [CKD], or fly ash), and stormwater from the affected area drains to surface waters of the State or to a storm sewer system that drains to surface waters of the State, the Permittee must conduct pH sampling as set forth below. Note: In addition, discharges to segments of water bodies on Washington State's 303(d) list (Category 5) for high pH are subject to a numeric effluent limit for pH; refer to Special Condition S8.

1. The Permittee must perform pH analysis on site with a calibrated pH meter, pH test kit, or wide range pH indicator paper. The Permittee must record pH sampling results in the site log book.
2. During the applicable pH monitoring period defined below, the Permittee must obtain a representative sample of stormwater and conduct pH analysis at least once per week.
 - a. For sites with significant concrete work, the Permittee must begin the pH sampling period when the concrete is first placed or poured and exposed to precipitation, and continue weekly throughout and after the concrete placement, pour and curing period, until stormwater pH is in the range of 6.5 to 8.5 (su).
 - b. For sites with recycled concrete where monitoring is required, the Permittee must begin the weekly pH sampling period when the recycled concrete is first exposed to precipitation and must continue until the recycled concrete is fully stabilized with the stormwater pH in the range of 6.5 to 8.5 (su).
 - c. For sites with engineered soils, the Permittee must begin the pH sampling period when the soil amendments are first exposed to precipitation and must continue until the area of engineered soils is fully stabilized.
3. The Permittee must sample pH in the sediment trap/pond(s) or other locations that receive stormwater runoff from the area of significant concrete work or engineered soils before the stormwater discharges to surface waters.
4. The benchmark value for pH is 8.5 standard units. Anytime sampling indicates that pH is 8.5 or greater, the Permittee must either:
 - a. Prevent the high pH water (8.5 or above) from entering storm sewer systems or surface waters of the state; *or*
 - b. If necessary, adjust or neutralize the high pH water until it is in the range of pH 6.5 to 8.5 (su) using an appropriate treatment BMP such as carbon dioxide (CO₂) sparging, dry ice or food grade vinegar. The Permittee must obtain written approval from Ecology before using any form of chemical treatment other than CO₂ sparging, dry ice or food grade vinegar.

S5. REPORTING AND RECORDKEEPING REQUIREMENTS

A. High Turbidity Reporting

Anytime sampling performed in accordance with Special Condition S4.C indicates turbidity has reached the 250 NTUs or more (or transparency less than or equal to 6 cm), high turbidity reporting level, the Permittee must notify Ecology within 24 hours of analysis either by calling the applicable Ecology Region's Environmental Report Tracking System (ERTS) number by phone or by submitting an electronic ERTS report (through Ecology's Water Quality Permitting Portal (WQWebPortal) – Permit Submittals when the form is available). See the CSWGP website for links to ERTS and the WQWebPortal. (<http://www.ecy.wa.gov/programs/wq/stormwater/construction/index.html>) Also, see phone numbers in Special Condition S4.C.5.b.i.

B. Discharge Monitoring Reports (DMRs)

Permittees required to conduct water quality sampling in accordance with Special Conditions S4.C (Turbidity/Transparency), S4.D (pH), S8 (303[d]/TMDL sampling), and/or G12 (Additional Sampling) must submit the results to Ecology.

Permittees must submit monitoring data using Ecology's WQWebDMR web application accessed through Ecology's Water Quality Permitting Portal.

Permittees unable to submit electronically (for example, those who do not have an internet connection) must contact Ecology to request a waiver and obtain instructions on how to obtain a paper copy DMR at:

Department of Ecology
Water Quality Program - Construction Stormwater
PO Box 47696
Olympia, WA 98504-7696

Permittees who obtain a waiver not to use WQWebDMR must use the forms provided to them by Ecology; submittals must be mailed to the address above. Permittees must submit DMR forms to be received by Ecology within 15 days following the end of each month.

If there was no discharge during a given monitoring period, all Permittees must submit a DMR as required with "no discharge" entered in place of the monitoring results. DMRs are required for the full duration of permit coverage (from the first full month following the effective date of permit coverage up until Ecology has approved termination of the coverage). For more information, contact Ecology staff using information provided at the following website: www.ecy.wa.gov/programs/wq/permits/paris/contacts.html.

C. Records Retention

The Permittee must retain records of all monitoring information (site log book, sampling results, inspection reports/checklists, etc.), Stormwater Pollution Prevention Plan, copy of the permit coverage letter (including Transfer of Coverage documentation) and any other documentation of compliance with permit requirements for the entire life of the construction project and for a minimum of five (5) years following the termination of permit coverage. Such information must include all calibration and maintenance records, and records of all data used to complete the application for this permit. This period of retention must be extended during

the course of any unresolved litigation regarding the discharge of pollutants by the Permittee or when requested by Ecology.

D. Recording Results

For each measurement or sample taken, the Permittee must record the following information:

1. Date, place, method, and time of sampling or measurement.
2. The first and last name of the individual who performed the sampling or measurement.
3. The date(s) the analyses were performed.
4. The first and last name of the individual who performed the analyses.
5. The analytical techniques or methods used.
6. The results of all analyses.

E. Additional Monitoring by the Permittee

If the Permittee samples or monitors any pollutant more frequently than required by this permit using test procedures specified by Special Condition S4 of this permit, the sampling results for this monitoring must be included in the calculation and reporting of the data submitted in the Permittee's DMR.

F. Noncompliance Notification

In the event the Permittee is unable to comply with any part of the terms and conditions of this permit, and the resulting noncompliance may cause a threat to human health or the environment (such as but not limited to spills or fuels or other materials, catastrophic pond or slope failure, and discharges that violate water quality standards), or exceed numeric effluent limitations (see S8 – Discharges to 303(d) or TMDL Waterbodies), the Permittee must, upon becoming aware of the circumstance:

1. Notify Ecology within 24 hours of the failure to comply by calling the applicable Regional office ERTS phone number (refer to Special Condition S4.C.5.b.i, or go to <https://ecology.wa.gov/About-us/Get-involved/Report-an-environmental-issue> to find contact information for the regional offices.)
2. Immediately take action to prevent the discharge/pollution, or otherwise stop or correct the noncompliance, and, if applicable, repeat sampling and analysis of any noncompliance immediately and submit the results to Ecology within five (5) days of becoming aware of the violation (See S5.F.3, below, for details on submitting results in a report).
3. Submit a detailed written report to Ecology within five (5) days of the time the Permittee becomes aware of the circumstances, unless requested earlier by Ecology. The report must be submitted using Ecology's Water Quality Permitting Portal (WQWebPortal) – Permit Submittals, unless a waiver from electronic reporting has been granted according to S5.B. The report must contain a description of the noncompliance, including exact dates and times, and if the noncompliance has not been corrected, the anticipated time it is expected to continue; and the steps taken or planned to reduce, eliminate, and prevent reoccurrence of the noncompliance.

The Permittee must report any unanticipated bypass and/or upset that exceeds any effluent limit in the permit in accordance with the 24-hour reporting requirement contained in 40 C.F.R. 122.41(l)(6).

Compliance with these requirements does not relieve the Permittee from responsibility to maintain continuous compliance with the terms and conditions of this permit or the resulting liability for failure to comply. Upon request of the Permittee, Ecology may waive the requirement for a written report on a case-by-case basis, if the immediate notification is received by Ecology within 24 hours.

G. Access to Plans and Records

1. The Permittee must retain the following permit documentation (plans and records) on site, or within reasonable access to the site, for use by the operator or for on-site review by Ecology or the local jurisdiction:
 - a. General Permit
 - b. Permit Coverage Letter
 - c. Stormwater Pollution Prevention Plan (SWPPP)
 - d. Site Log Book
 - e. Erosivity Waiver (if applicable)
2. The Permittee must address written requests for plans and records listed above (Special Condition S5.G.1) as follows:
 - a. The Permittee must provide a copy of plans and records to Ecology within 14 days of receipt of a written request from Ecology.
 - b. The Permittee must provide a copy of plans and records to the public when requested in writing. Upon receiving a written request from the public for the Permittee's plans and records, the Permittee must either:
 - i. Provide a copy of the plans and records to the requester within 14 days of a receipt of the written request; *or*
 - ii. Notify the requester within 10 days of receipt of the written request of the location and times within normal business hours when the plans and records may be viewed; and provide access to the plans and records within 14 days of receipt of the written request; *or*

Within 14 days of receipt of the written request, the Permittee may submit a copy of the plans and records to Ecology for viewing and/or copying by the requester at an Ecology office, or a mutually agreed location. If plans and records are viewed and/or copied at a location other than at an Ecology office, the Permittee will provide reasonable access to copying services for which a reasonable fee may be charged. The Permittee must notify the requester within 10 days of receipt of the request where the plans and records may be viewed and/or copied.

S6. PERMIT FEES

The Permittee must pay permit fees assessed by Ecology. Fees for stormwater discharges covered under this permit are established by Chapter 173-224 WAC. Ecology continues to assess permit fees until the permit is terminated in accordance with Special Condition S10 or revoked in accordance with General Condition G5.

S7. SOLID AND LIQUID WASTE DISPOSAL

The Permittee must handle and dispose of solid and liquid wastes generated by construction activity, such as demolition debris, construction materials, contaminated materials, and waste materials from maintenance activities, including liquids and solids from cleaning catch basins and other stormwater facilities, in accordance with:

- A. Special Condition S3, Compliance with Standards.
- B. WAC 173-216-110.
- C. Other applicable regulations.

S8. DISCHARGES TO 303(d) OR TMDL WATERBODIES

A. Sampling and Numeric Effluent Limits For Certain Discharges to 303(d)-Listed Water Bodies

1. Permittees who discharge to segments of water bodies listed as impaired by the State of Washington under Section 303(d) of the Clean Water Act for turbidity, fine sediment, high pH, or phosphorus, must conduct water quality sampling according to the requirements of this section, and Special Conditions S4.C.2.b-f and S4.C.3.b-d, and must comply with the applicable numeric effluent limitations in S8.C and S8.D.
2. All references and requirements associated with Section 303(d) of the Clean Water Act mean the most current listing by Ecology of impaired waters (Category 5) that exists on January 1, 2021, or the date when the operator's complete permit application is received by Ecology, whichever is later.

B. Limits on Coverage for New Discharges to TMDL or 303(d)-Listed Waters

Construction sites that discharge to a TMDL or 303(d)-listed waterbody are not eligible for coverage under this permit *unless* the operator:

1. Prevents exposing stormwater to pollutants for which the waterbody is impaired, and retains documentation in the SWPPP that details procedures taken to prevent exposure on site; *or*
2. Documents that the pollutants for which the waterbody is impaired are not present at the site, and retains documentation of this finding within the SWPPP; *or*
3. Provides Ecology with data indicating the discharge is not expected to cause or contribute to an exceedance of a water quality standard, and retains such data on site with the SWPPP. The operator must provide data and other technical information to Ecology that sufficiently demonstrate:
 - a. For discharges to waters without an EPA-approved or -established TMDL, that the discharge of the pollutant for which the water is impaired will meet in-stream water quality criteria at the point of discharge to the waterbody; *or*
 - b. For discharges to waters with an EPA-approved or -established TMDL, that there is sufficient remaining wasteload allocation in the TMDL to allow construction stormwater discharge and that existing dischargers to the waterbody are subject to compliance schedules designed to bring the waterbody into attainment with water quality standards.

Operators of construction sites are eligible for coverage under this permit only after Ecology makes an affirmative determination that the *discharge will not cause or contribute to the existing impairment or exceed the TMDL*.

C. Sampling and Numeric Effluent Limits for Discharges to Water Bodies on the 303(d) List for Turbidity, Fine Sediment, or Phosphorus

1. Permittees who discharge to segments of water bodies on the 303(d) list (Category 5) for turbidity, fine sediment, or phosphorus must conduct turbidity sampling in accordance with Special Condition S4.C.2 and comply with either of the numeric effluent limits noted in Table 5 below.
2. As an alternative to the 25 NTUs effluent limit noted in Table 5 below (applied at the point where stormwater [or authorized non-stormwater] is discharged off-site), Permittees may choose to comply with the surface water quality standard for turbidity. The standard is: no more than 5 NTUs over background turbidity when the background turbidity is 50 NTUs or less, or no more than a 10% increase in turbidity when the background turbidity is more than 50 NTUs. In order to use the water quality standard requirement, the sampling must take place at the following locations:
 - a. Background turbidity in the 303(d)-listed receiving water immediately upstream (upgradient) or outside the area of influence of the discharge.
 - b. Turbidity at the point of discharge into the 303(d)-listed receiving water, inside the area of influence of the discharge.
3. Discharges that exceed the numeric effluent limit for turbidity constitute a violation of this permit.
4. Permittees whose discharges exceed the numeric effluent limit must sample discharges daily until the violation is corrected and comply with the non-compliance notification requirements in Special Condition S5.F.

Table 5 Turbidity, Fine Sediment & Phosphorus Sampling and Limits for 303(d)-Listed Waters

Parameter identified in 303(d) listing	Parameter Sampled	Unit	Analytical Method	Sampling Frequency	Numeric Effluent Limit ¹
- Turbidity - Fine Sediment - Phosphorus	Turbidity	NTU	SM2130	Weekly, if discharging	25 NTUs, at the point where stormwater is discharged from the site; OR In compliance with the surface water quality standard for turbidity (S8.C.2.a)

¹ Permittees subject to a numeric effluent limit for turbidity may, at their discretion, choose either numeric effluent limitation based on site-specific considerations including, but not limited to, safety, access and convenience.

D. Discharges to Water Bodies on the 303(d) List for High pH

1. Permittees who discharge to segments of water bodies on the 303(d) list (Category 5) for high pH must conduct pH sampling in accordance with the table below, and comply with the numeric effluent limit of pH 6.5 to 8.5 su (Table 6).

Table 6 pH Sampling and Limits for 303(d)-Listed Waters

Parameter identified in 303(d) listing	Parameter Sampled/Units	Analytical Method	Sampling Frequency	Numeric Effluent Limit
High pH	pH /Standard Units	pH meter	Weekly, if discharging	In the range of 6.5 – 8.5 su

2. At the Permittee's discretion, compliance with the limit shall be assessed at one of the following locations:
 - a. Directly in the 303(d)-listed waterbody segment, inside the immediate area of influence of the discharge; *or*
 - b. Alternatively, the Permittee may measure pH at the point where the discharge leaves the construction site, rather than in the receiving water.
3. Discharges that exceed the numeric effluent limit for pH (outside the range of 6.5 – 8.5 su) constitute a violation of this permit.
4. Permittees whose discharges exceed the numeric effluent limit must sample discharges daily until the violation is corrected and comply with the non-compliance notification requirements in Special Condition S5.F.

E. Sampling and Limits for Sites Discharging to Waters Covered by a TMDL or another Pollution Control Plan

1. Discharges to a waterbody that is subject to a Total Maximum Daily Load (TMDL) for turbidity, fine sediment, high pH, or phosphorus must be consistent with the TMDL. Refer to <http://www.ecy.wa.gov/programs/wq/tmdl/TMDLsbyWria/TMDLbyWria.html> for more information on TMDLs.
 - a. Where an applicable TMDL sets specific waste load allocations or requirements for discharges covered by this permit, discharges must be consistent with any specific waste load allocations or requirements established by the applicable TMDL.
 - i. The Permittee must sample discharges weekly, unless otherwise specified by the TMDL, to evaluate compliance with the specific waste load allocations or requirements.
 - ii. Analytical methods used to meet the monitoring requirements must conform to the latest revision of the *Guidelines Establishing Test Procedures for the Analysis of Pollutants* contained in 40 CFR Part 136.
 - iii. Turbidity and pH methods need not be accredited or registered unless conducted at a laboratory which must otherwise be accredited or registered.
 - b. Where an applicable TMDL has established a general waste load allocation for construction stormwater discharges, but has not identified specific requirements, compliance with Special Conditions S4 (Monitoring) and S9 (SWPPPs) will constitute compliance with the approved TMDL.
 - c. Where an applicable TMDL has not specified a waste load allocation for construction stormwater discharges, but has not excluded these discharges, compliance with Special Conditions S4 (Monitoring) and S9 (SWPPPs) will constitute compliance with the approved TMDL.
 - d. Where an applicable TMDL specifically precludes or prohibits discharges from construction activity, the operator is not eligible for coverage under this permit.

S9. STORMWATER POLLUTION PREVENTION PLAN

The Permittee must prepare and properly implement an adequate Stormwater Pollution Prevention Plan (SWPPP) for construction activity in accordance with the requirements of this permit beginning with initial soil disturbance and until final stabilization.

A. The Permittee's SWPPP must meet the following objectives:

1. To identify best management practices (BMPs) which prevent erosion and sedimentation, and to reduce, eliminate or prevent stormwater contamination and water pollution from construction activity.
2. To prevent violations of surface water quality, groundwater quality, or sediment management standards.
3. To control peak volumetric flow rates and velocities of stormwater discharges.

B. General Requirements

1. The SWPPP must include a narrative and drawings. All BMPs must be clearly referenced in the narrative and marked on the drawings. The SWPPP narrative must include documentation to explain and justify the pollution prevention decisions made for the project. Documentation must include:
 - a. Information about existing site conditions (topography, drainage, soils, vegetation, etc.).
 - b. Potential erosion problem areas.
 - c. The 13 elements of a SWPPP in Special Condition S9.D.1-13, including BMPs used to address each element.
 - d. Construction phasing/sequence and general BMP implementation schedule.
 - e. The actions to be taken if BMP performance goals are not achieved—for example, a contingency plan for additional treatment and/or storage of stormwater that would violate the water quality standards if discharged.
 - f. Engineering calculations for ponds, treatment systems, and any other designed structures. When a treatment system requires engineering calculations, these calculations must be included in the SWPPP. Engineering calculations do not need to be included in the SWPPP for treatment systems that do not require such calculations.
2. The Permittee must modify the SWPPP if, during inspections or investigations conducted by the owner/operator, or the applicable local or state regulatory authority, it is determined that the SWPPP is, or would be, ineffective in eliminating or significantly minimizing pollutants in stormwater discharges from the site. The Permittee must then:
 - a. Review the SWPPP for compliance with Special Condition S9 and make appropriate revisions within 7 days of the inspection or investigation.
 - b. Immediately begin the process to fully implement and maintain appropriate source control and/or treatment BMPs as soon as possible, addressing the problems no later than 10 days from the inspection or investigation. If installation of necessary treatment BMPs is not feasible within 10 days, Ecology may approve additional time when an extension is requested by a Permittee within the initial 10-day response period.
 - c. Document BMP implementation and maintenance in the site log book.

The Permittee must modify the SWPPP whenever there is a change in design, construction, operation, or maintenance at the construction site that has, or could have, a significant effect on the discharge of pollutants to waters of the State.

C. Stormwater Best Management Practices (BMPs)

BMPs must be consistent with:

1. *Stormwater Management Manual for Western Washington* (most current approved edition at the time this permit was issued), for sites west of the crest of the Cascade Mountains; *or*

2. *Stormwater Management Manual for Eastern Washington* (most current approved edition at the time this permit was issued), for sites east of the crest of the Cascade Mountains; *or*
3. Revisions to the manuals listed in Special Condition S9.C.1 & 2, or other stormwater management guidance documents or manuals which provide an equivalent level of pollution prevention, that are approved by Ecology and incorporated into this permit in accordance with the permit modification requirements of WAC 173-226-230; *or*
4. Documentation in the SWPPP that the BMPs selected provide an equivalent level of pollution prevention, compared to the applicable stormwater management manuals, including:
 - a. The technical basis for the selection of all stormwater BMPs (scientific, technical studies, and/or modeling) that support the performance claims for the BMPs being selected.
 - b. An assessment of how the selected BMP will satisfy AKART requirements and the applicable federal technology-based treatment requirements under 40 CFR part 125.3.

D. SWPPP – Narrative Contents and Requirements

The Permittee must include each of the 13 elements below in Special Condition S9.D.1-13 in the narrative of the SWPPP and implement them unless site conditions render the element unnecessary and the exemption from that element is clearly justified in the SWPPP.

1. Preserve Vegetation/Mark Clearing Limits
 - a. Before beginning land-disturbing activities, including clearing and grading, clearly mark all clearing limits, sensitive areas and their buffers, and trees that are to be preserved within the construction area.
 - b. Retain the duff layer, native topsoil, and natural vegetation in an undisturbed state to the maximum degree practicable.
2. Establish Construction Access
 - a. Limit construction vehicle access and exit to one route, if possible.
 - b. Stabilize access points with a pad of quarry spalls, crushed rock, or other equivalent BMPs, to minimize tracking sediment onto roads.
 - c. Locate wheel wash or tire baths on site, if the stabilized construction entrance is not effective in preventing tracking sediment onto roads.
 - d. If sediment is tracked off site, clean the affected roadway thoroughly at the end of each day, or more frequently as necessary (for example, during wet weather). Remove sediment from roads by shoveling, sweeping, or pickup and transport of the sediment to a controlled sediment disposal area.
 - e. Conduct street washing only after sediment removal in accordance with Special Condition S9.D.2.d.
 - f. Control street wash wastewater by pumping back on site or otherwise preventing it from discharging into systems tributary to waters of the State.

3. Control Flow Rates

- a. Protect properties and waterways downstream of construction sites from erosion and the associated discharge of turbid waters due to increases in the velocity and peak volumetric flow rate of stormwater runoff from the project site, as required by local plan approval authority.
- b. Where necessary to comply with Special Condition S9.D.3.a, construct stormwater infiltration or detention BMPs as one of the first steps in grading. Assure that detention BMPs function properly before constructing site improvements (for example, impervious surfaces).
- c. If permanent infiltration ponds are used for flow control during construction, protect these facilities from sedimentation during the construction phase.

4. Install Sediment Controls

The Permittee must design, install and maintain effective erosion controls and sediment controls to minimize the discharge of pollutants. At a minimum, the Permittee must:

- a. Construct sediment control BMPs (sediment ponds, traps, filters, infiltration facilities, etc.) as one of the first steps in grading. These BMPs must be functional before other land disturbing activities take place.
- b. Minimize sediment discharges from the site. The design, installation and maintenance of erosion and sediment controls must address factors such as the amount, frequency, intensity and duration of precipitation, the nature of resulting stormwater runoff, and soil characteristics, including the range of soil particle sizes expected to be present on the site.
- c. Direct stormwater runoff from disturbed areas through a sediment pond or other appropriate sediment removal BMP, before the runoff leaves a construction site or before discharge to an infiltration facility. Runoff from fully stabilized areas may be discharged without a sediment removal BMP, but must meet the flow control performance standard of Special Condition S9.D.3.a.
- d. Locate BMPs intended to trap sediment on site in a manner to avoid interference with the movement of juvenile salmonids attempting to enter off-channel areas or drainages.
- e. Provide and maintain natural buffers around surface waters, direct stormwater to vegetated areas to increase sediment removal and maximize stormwater infiltration, unless infeasible.
- f. Where feasible, design outlet structures that withdraw impounded stormwater from the surface to avoid discharging sediment that is still suspended lower in the water column.

5. Stabilize Soils

- a. The Permittee must stabilize exposed and unworked soils by application of effective BMPs that prevent erosion. Applicable BMPs include, but are not limited to: temporary and permanent seeding, sodding, mulching, plastic covering, erosion

control fabrics and matting, soil application of polyacrylamide (PAM), the early application of gravel base on areas to be paved, and dust control.

- b. The Permittee must control stormwater volume and velocity within the site to minimize soil erosion.
- c. The Permittee must control stormwater discharges, including both peak flow rates and total stormwater volume, to minimize erosion at outlets and to minimize downstream channel and stream bank erosion.
- d. Depending on the geographic location of the project, the Permittee must not allow soils to remain exposed and unworked for more than the time periods set forth below to prevent erosion.

West of the Cascade Mountains Crest

During the dry season (May 1 - September 30): 7 days

During the wet season (October 1 - April 30): 2 days

East of the Cascade Mountains Crest, except for Central Basin*

During the dry season (July 1 - September 30): 10 days

During the wet season (October 1 - June 30): 5 days

The Central Basin*, East of the Cascade Mountains Crest

During the dry Season (July 1 - September 30): 30 days

During the wet season (October 1 - June 30): 15 days

***Note: The Central Basin** is defined as the portions of Eastern Washington with mean annual precipitation of less than 12 inches.

- e. The Permittee must stabilize soils at the end of the shift before a holiday or weekend if needed based on the weather forecast.
- f. The Permittee must stabilize soil stockpiles from erosion, protected with sediment trapping measures, and where possible, be located away from storm drain inlets, waterways, and drainage channels.
- g. The Permittee must minimize the amount of soil exposed during construction activity.
- h. The Permittee must minimize the disturbance of steep slopes.
- i. The Permittee must minimize soil compaction and, unless infeasible, preserve topsoil.

6. Protect Slopes

- a. The Permittee must design and construct cut-and-fill slopes in a manner to minimize erosion. Applicable practices include, but are not limited to, reducing continuous length of slope with terracing and diversions, reducing slope steepness, and roughening slope surfaces (for example, track walking).
- b. The Permittee must divert off-site stormwater (run-on) or groundwater away from slopes and disturbed areas with interceptor dikes, pipes, and/or swales. Off-site stormwater should be managed separately from stormwater generated on the site.
- c. At the top of slopes, collect drainage in pipe slope drains or protected channels to prevent erosion.

- i. West of the Cascade Mountains Crest: Temporary pipe slope drains must handle the peak 10-minute flow rate from a Type 1A, 10-year, 24-hour frequency storm for the developed condition. Alternatively, the 10-year, 1-hour flow rate predicted by an approved continuous runoff model, increased by a factor of 1.6, may be used. The hydrologic analysis must use the existing land cover condition for predicting flow rates from tributary areas outside the project limits. For tributary areas on the project site, the analysis must use the temporary or permanent project land cover condition, whichever will produce the highest flow rates. If using the Western Washington Hydrology Model (WWHM) to predict flows, bare soil areas should be modeled as "landscaped area."
 - ii. East of the Cascade Mountains Crest: Temporary pipe slope drains must handle the expected peak flow rate from a 6-month, 3-hour storm for the developed condition, referred to as the short duration storm.
- d. Place excavated material on the uphill side of trenches, consistent with safety and space considerations.
- e. Place check dams at regular intervals within constructed channels that are cut down a slope.
- 7. Protect Drain Inlets
 - a. Protect all storm drain inlets made operable during construction so that stormwater runoff does not enter the conveyance system without first being filtered or treated to remove sediment.
 - b. Clean or remove and replace inlet protection devices when sediment has filled one-third of the available storage (unless a different standard is specified by the product manufacturer).
- 8. Stabilize Channels and Outlets
 - a. Design, construct and stabilize all on-site conveyance channels to prevent erosion from the following expected peak flows:
 - i. West of the Cascade Mountains Crest: Channels must handle the peak 10-minute flow rate from a Type 1A, 10-year, 24-hour frequency storm for the developed condition. Alternatively, the 10-year, 1-hour flow rate indicated by an approved continuous runoff model, increased by a factor of 1.6, may be used. The hydrologic analysis must use the existing land cover condition for predicting flow rates from tributary areas outside the project limits. For tributary areas on the project site, the analysis must use the temporary or permanent project land cover condition, whichever will produce the highest flow rates. If using the WWHM to predict flows, bare soil areas should be modeled as "landscaped area."
 - ii. East of the Cascade Mountains Crest: Channels must handle the expected peak flow rate from a 6-month, 3-hour storm for the developed condition, referred to as the short duration storm.
 - b. Provide stabilization, including armoring material, adequate to prevent erosion of outlets, adjacent stream banks, slopes, and downstream reaches at the outlets of all conveyance systems.

9. Control Pollutants

Design, install, implement and maintain effective pollution prevention measures to minimize the discharge of pollutants. The Permittee must:

- a. Handle and dispose of all pollutants, including waste materials and demolition debris that occur on site in a manner that does not cause contamination of stormwater.
- b. Provide cover, containment, and protection from vandalism for all chemicals, liquid products, petroleum products, and other materials that have the potential to pose a threat to human health or the environment. Minimize storage of hazardous materials on-site. Safety Data Sheets (SDS) should be supplied for all materials stored. Chemicals should be kept in their original labeled containers. On-site fueling tanks must include secondary containment. Secondary containment means placing tanks or containers within an impervious structure capable of containing 110% of the volume of the largest tank within the containment structure. Double-walled tanks do not require additional secondary containment.
- c. Conduct maintenance, fueling, and repair of heavy equipment and vehicles using spill prevention and control measures. Clean contaminated surfaces immediately following any spill incident.
- d. Discharge wheel wash or tire bath wastewater to a separate on-site treatment system that prevents discharge to surface water, such as closed-loop recirculation or upland land application, or to the sanitary sewer with local sewer district approval.
- e. Apply fertilizers and pesticides in a manner and at application rates that will not result in loss of chemical to stormwater runoff. Follow manufacturers' label requirements for application rates and procedures.
- f. Use BMPs to prevent contamination of stormwater runoff by pH-modifying sources. The sources for this contamination include, but are not limited to: bulk cement, cement kiln dust, fly ash, new concrete washing and curing waters, recycled concrete stockpiles, waste streams generated from concrete grinding and sawing, exposed aggregate processes, dewatering concrete vaults, concrete pumping and mixer washout waters. (Also refer to the definition for "concrete wastewater" in Appendix A – Definitions.)
- g. Adjust the pH of stormwater or authorized non-stormwater if necessary to prevent an exceedance of groundwater and/or surface water quality standards.
- h. Assure that washout of concrete trucks is performed off-site or in designated concrete washout areas only. Do not wash out concrete truck drums onto the ground, or into storm drains, open ditches, streets, or streams. Washout of small concrete handling equipment may be disposed of in a formed area awaiting concrete where it will not contaminate surface or groundwater. Do not dump excess concrete on site, except in designated concrete washout areas. Concrete spillage or concrete discharge directly to groundwater or surface waters of the State is

prohibited. At no time shall concrete be washed off into the footprint of an area where an infiltration BMP will be installed.

- i. Obtain written approval from Ecology before using any chemical treatment, with the exception of CO₂, dry ice or food grade vinegar, to adjust pH.
- j. Uncontaminated water from water-only based shaft drilling for construction of building, road, and bridge foundations may be infiltrated provided the wastewater is managed in a way that prohibits discharge to surface waters. Prior to infiltration, water from water-only based shaft drilling that comes into contact with curing concrete must be neutralized until pH is in the range of 6.5 to 8.5 (su).

10. Control Dewatering

- a. Permittees must discharge foundation, vault, and trench dewatering water, which have characteristics similar to stormwater runoff at the site, in conjunction with BMPs to reduce sedimentation before discharge to a sediment trap or sediment pond.
- b. Permittees may discharge clean, non-turbid dewatering water, such as well-point groundwater, to systems tributary to, or directly into surface waters of the State, as specified in Special Condition S9.D.8, provided the dewatering flow does not cause erosion or flooding of receiving waters. Do not route clean dewatering water through stormwater sediment ponds. Note that "surface waters of the State" may exist on a construction site as well as off site; for example, a creek running through a site.
- c. Other dewatering treatment or disposal options may include:
 - i. Infiltration
 - ii. Transport off site in a vehicle, such as a vacuum flush truck, for legal disposal in a manner that does not pollute state waters.
 - iii. Ecology-approved on-site chemical treatment or other suitable treatment technologies (See S9.D.9.i, regarding chemical treatment written approval).
 - iv. Sanitary or combined sewer discharge with local sewer district approval, if there is no other option.
 - v. Use of a sedimentation bag with discharge to a ditch or swale for small volumes of localized dewatering.
- d. Permittees must handle highly turbid or contaminated dewatering water separately from stormwater.

11. Maintain BMPs

- a. Permittees must maintain and repair all temporary and permanent erosion and sediment control BMPs as needed to assure continued performance of their intended function in accordance with BMP specifications.
- b. Permittees must remove all temporary erosion and sediment control BMPs within 30 days after achieving final site stabilization or after the temporary BMPs are no longer needed.

12. Manage the Project

- a. Phase development projects to the maximum degree practicable and take into account seasonal work limitations.
- b. Inspect, maintain and repair all BMPs as needed to assure continued performance of their intended function. Conduct site inspections and monitoring in accordance with Special Condition S4.
- c. Maintain, update, and implement the SWPPP in accordance with Special Conditions S3, S4, and S9.

13. Protect Low Impact Development (LID) BMPs

The primary purpose of on-site LID Stormwater Management is to reduce the disruption of the natural site hydrology through infiltration. LID BMPs are permanent facilities.

- a. Permittees must protect all LID BMPs (including, but not limited to, Bioretention and Rain Garden facilities) from sedimentation through installation and maintenance of erosion and sediment control BMPs on portions of the site that drain into the Bioretention and/or Rain Garden facilities. Restore the BMPs to their fully functioning condition if they accumulate sediment during construction. Restoring the facility must include removal of sediment and any sediment-laden bioretention/ rain garden soils, and replacing the removed soils with soils meeting the design specification.
- b. Permittees must maintain the infiltration capabilities of LID BMPs by protecting against compaction by construction equipment and foot traffic. Protect completed lawn and landscaped areas from compaction due to construction equipment.
- c. Permittees must control erosion and avoid introducing sediment from surrounding land uses onto permeable pavements. Do not allow muddy construction equipment on the base material or pavement. Do not allow sediment-laden runoff onto permeable pavements or base materials.
- d. Permittees must clean permeable pavements fouled with sediments or no longer passing an initial infiltration test using local stormwater manual methodology or the manufacturer's procedures.
- e. Permittees must keep all heavy equipment off existing soils under LID BMPs that have been excavated to final grade to retain the infiltration rate of the soils.

E. SWPPP – Map Contents and Requirements

The Permittee's SWPPP must also include a vicinity map or general location map (for example, a USGS quadrangle map, a portion of a county or city map, or other appropriate map) with enough detail to identify the location of the construction site and receiving waters within one mile of the site.

The SWPPP must also include a legible site map (or maps) showing the entire construction site. The following features must be identified, unless not applicable due to site conditions.

1. The direction of north, property lines, and existing structures and roads.
2. Cut and fill slopes indicating the top and bottom of slope catch lines.

3. Approximate slopes, contours, and direction of stormwater flow before and after major grading activities.
4. Areas of soil disturbance and areas that will not be disturbed.
5. Locations of structural and nonstructural controls (BMPs) identified in the SWPPP.
6. Locations of off-site material, stockpiles, waste storage, borrow areas, and vehicle/equipment storage areas.
7. Locations of all surface water bodies, including wetlands.
8. Locations where stormwater or non-stormwater discharges off-site and/or to a surface waterbody, including wetlands.
9. Location of water quality sampling station(s), if sampling is required by state or local permitting authority.
10. Areas where final stabilization has been accomplished and no further construction-phase permit requirements apply.
11. Location or proposed location of LID facilities.

S10. NOTICE OF TERMINATION

Partial terminations of permit coverage are not authorized.

A. The site is eligible for termination of coverage when it has met any of the following conditions:

1. The site has undergone final stabilization, the Permittee has removed all temporary BMPs (except biodegradable BMPs clearly manufactured with the intention for the material to be left in place and not interfere with maintenance or land use), and all stormwater discharges associated with construction activity have been eliminated; *or*
2. All portions of the site that have not undergone final stabilization per Special Condition S10.A.1 have been sold and/or transferred (per Special Condition S2.A), and the Permittee no longer has operational control of the construction activity; *or*
3. For residential construction only, the Permittee has completed temporary stabilization and the homeowners have taken possession of the residences.

B. When the site is eligible for termination, the Permittee must submit a complete and accurate Notice of Termination (NOT) form, signed in accordance with General Condition G2, to:

Department of Ecology
Water Quality Program - Construction Stormwater
PO Box 47696
Olympia, WA 98504-7696

When an electronic termination form is available, the Permittee may choose to submit a complete and accurate Notice of Termination (NOT) form through the Water Quality Permitting Portal rather than mailing a hardcopy as noted above.

The termination is effective on the 31st calendar day following the date Ecology receives a complete NOT form, unless Ecology notifies the Permittee that termination request is denied because the Permittee has not met the eligibility requirements in Special Condition S10.A.

Permittees are required to comply with all conditions and effluent limitations in the permit until the permit has been terminated.

Permittees transferring the property to a new property owner or operator/Permittee are required to complete and submit the Notice of Transfer form to Ecology, but are not required to submit a Notice of Termination form for this type of transaction.

GENERAL CONDITIONS

G1. DISCHARGE VIOLATIONS

All discharges and activities authorized by this general permit must be consistent with the terms and conditions of this general permit. Any discharge of any pollutant more frequent than or at a level in excess of that identified and authorized by the general permit must constitute a violation of the terms and conditions of this permit.

G2. SIGNATORY REQUIREMENTS

- A. All permit applications must bear a certification of correctness to be signed:
 - 1. In the case of corporations, by a responsible corporate officer.
 - 2. In the case of a partnership, by a general partner of a partnership.
 - 3. In the case of sole proprietorship, by the proprietor.
 - 4. In the case of a municipal, state, or other public facility, by either a principal executive officer or ranking elected official.
- B. All reports required by this permit and other information requested by Ecology (including NOIs, NOTs, and Transfer of Coverage forms) must be signed by a person described above or by a duly authorized representative of that person. A person is a duly authorized representative only if:
 - 1. The authorization is made in writing by a person described above and submitted to Ecology.
 - 2. The authorization specifies either an individual or a position having responsibility for the overall operation of the regulated facility, such as the position of plant manager, superintendent, position of equivalent responsibility, or an individual or position having overall responsibility for environmental matters.
- C. Changes to authorization. If an authorization under paragraph G2.B.2 above is no longer accurate because a different individual or position has responsibility for the overall operation of the facility, a new authorization satisfying the requirements of paragraph G2.B.2 above must be submitted to Ecology prior to or together with any reports, information, or applications to be signed by an authorized representative.
- D. Certification. Any person signing a document under this section must make the following certification:

I certify under penalty of law, that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gathered and evaluated the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.

G3. RIGHT OF INSPECTION AND ENTRY

The Permittee must allow an authorized representative of Ecology, upon the presentation of credentials and such other documents as may be required by law:

- A.** To enter upon the premises where a discharge is located or where any records are kept under the terms and conditions of this permit.
- B.** To have access to and copy, at reasonable times and at reasonable cost, any records required to be kept under the terms and conditions of this permit.
- C.** To inspect, at reasonable times, any facilities, equipment (including monitoring and control equipment), practices, methods, or operations regulated or required under this permit.
- D.** To sample or monitor, at reasonable times, any substances or parameters at any location for purposes of assuring permit compliance or as otherwise authorized by the Clean Water Act.

G4. GENERAL PERMIT MODIFICATION AND REVOCATION

This permit may be modified, revoked and reissued, or terminated in accordance with the provisions of Chapter 173-226 WAC. Grounds for modification, revocation and reissuance, or termination include, but are not limited to, the following:

- A.** When a change occurs in the technology or practices for control or abatement of pollutants applicable to the category of dischargers covered under this permit.
- B.** When effluent limitation guidelines or standards are promulgated pursuant to the CWA or Chapter 90.48 RCW, for the category of dischargers covered under this permit.
- C.** When a water quality management plan containing requirements applicable to the category of dischargers covered under this permit is approved, or
- D.** When information is obtained that indicates cumulative effects on the environment from dischargers covered under this permit are unacceptable.

G5. REVOCATION OF COVERAGE UNDER THE PERMIT

Pursuant to Chapter 43.21B RCW and Chapter 173-226 WAC, the Director may terminate coverage for any discharger under this permit for cause. Cases where coverage may be terminated include, but are not limited to, the following:

- A.** Violation of any term or condition of this permit.
- B.** Obtaining coverage under this permit by misrepresentation or failure to disclose fully all relevant facts.
- C.** A change in any condition that requires either a temporary or permanent reduction or elimination of the permitted discharge.
- D.** Failure or refusal of the Permittee to allow entry as required in RCW 90.48.090.
- E.** A determination that the permitted activity endangers human health or the environment, or contributes to water quality standards violations.
- F.** Nonpayment of permit fees or penalties assessed pursuant to RCW 90.48.465 and Chapter 173-224 WAC.

- G.** Failure of the Permittee to satisfy the public notice requirements of WAC 173-226-130(5), when applicable.

The Director may require any discharger under this permit to apply for and obtain coverage under an individual permit or another more specific general permit. Permittees who have their coverage revoked for cause according to WAC 173-226-240 may request temporary coverage under this permit during the time an individual permit is being developed, provided the request is made within ninety (90) days from the time of revocation and is submitted along with a complete individual permit application form.

G6. REPORTING A CAUSE FOR MODIFICATION

The Permittee must submit a new application, or a supplement to the previous application, whenever a material change to the construction activity or in the quantity or type of discharge is anticipated which is not specifically authorized by this permit. This application must be submitted at least sixty (60) days prior to any proposed changes. Filing a request for a permit modification, revocation and reissuance, or termination, or a notification of planned changes or anticipated noncompliance does not relieve the Permittee of the duty to comply with the existing permit until it is modified or reissued.

G7. COMPLIANCE WITH OTHER LAWS AND STATUTES

Nothing in this permit will be construed as excusing the Permittee from compliance with any applicable federal, state, or local statutes, ordinances, or regulations.

G8. DUTY TO REAPPLY

The Permittee must apply for permit renewal at least 180 days prior to the specified expiration date of this permit. The Permittee must reapply using the electronic application form (NOI) available on Ecology's website. Permittees unable to submit electronically (for example, those who do not have an internet connection) must contact Ecology to request a waiver and obtain instructions on how to obtain a paper NOI.

Department of Ecology
Water Quality Program - Construction Stormwater
PO Box 47696
Olympia, WA 98504-7696

G9. REMOVED SUBSTANCE

The Permittee must not re-suspend or reintroduce collected screenings, grit, solids, sludges, filter backwash, or other pollutants removed in the course of treatment or control of stormwater to the final effluent stream for discharge to state waters.

G10. DUTY TO PROVIDE INFORMATION

The Permittee must submit to Ecology, within a reasonable time, all information that Ecology may request to determine whether cause exists for modifying, revoking and reissuing, or terminating this permit or to determine compliance with this permit. The Permittee must also submit to Ecology, upon request, copies of records required to be kept by this permit [40 CFR 122.41(h)].

G11. OTHER REQUIREMENTS OF 40 CFR

All other requirements of 40 CFR 122.41 and 122.42 are incorporated in this permit by reference.

G12. ADDITIONAL MONITORING

Ecology may establish specific monitoring requirements in addition to those contained in this permit by administrative order or permit modification.

G13. PENALTIES FOR VIOLATING PERMIT CONDITIONS

Any person who is found guilty of willfully violating the terms and conditions of this permit shall be deemed guilty of a crime, and upon conviction thereof shall be punished by a fine of up to ten thousand dollars (\$10,000) and costs of prosecution, or by imprisonment at the discretion of the court. Each day upon which a willful violation occurs may be deemed a separate and additional violation.

Any person who violates the terms and conditions of a waste discharge permit shall incur, in addition to any other penalty as provided by law, a civil penalty in the amount of up to ten thousand dollars (\$10,000) for every such violation. Each and every such violation shall be a separate and distinct offense, and in case of a continuing violation, every day's continuance shall be deemed to be a separate and distinct violation.

G14. UPSET

Definition – "Upset" means an exceptional incident in which there is unintentional and temporary noncompliance with technology-based permit effluent limitations because of factors beyond the reasonable control of the Permittee. An upset does not include noncompliance to the extent caused by operational error, improperly designed treatment facilities, inadequate treatment facilities, lack of preventive maintenance, or careless or improper operation.

An upset constitutes an affirmative defense to an action brought for noncompliance with such technology-based permit effluent limitations if the requirements of the following paragraph are met.

A Permittee who wishes to establish the affirmative defense of upset must demonstrate, through properly signed, contemporaneous operating logs or other relevant evidence that: 1) an upset occurred and that the Permittee can identify the cause(s) of the upset; 2) the permitted facility was being properly operated at the time of the upset; 3) the Permittee submitted notice of the upset as required in Special Condition S5.F, and; 4) the Permittee complied with any remedial measures required under this permit.

In any enforcement proceeding, the Permittee seeking to establish the occurrence of an upset has the burden of proof.

G15. PROPERTY RIGHTS

This permit does not convey any property rights of any sort, or any exclusive privilege.

G16. DUTY TO COMPLY

The Permittee must comply with all conditions of this permit. Any permit noncompliance constitutes a violation of the Clean Water Act and is grounds for enforcement action; for permit termination, revocation and reissuance, or modification; or denial of a permit renewal application.

G17. TOXIC POLLUTANTS

The Permittee must comply with effluent standards or prohibitions established under Section 307(a) of the Clean Water Act for toxic pollutants within the time provided in the regulations that establish those standards or prohibitions, even if this permit has not yet been modified to incorporate the requirement.

G18. PENALTIES FOR TAMPERING

The Clean Water Act provides that any person who falsifies, tampers with, or knowingly renders inaccurate any monitoring device or method required to be maintained under this permit shall, upon conviction, be punished by a fine of not more than \$10,000 per violation, or by imprisonment for not more than two years per violation, or by both. If a conviction of a person is for a violation committed after a first conviction of such person under this condition, punishment shall be a fine of not more than \$20,000 per day of violation, or imprisonment of not more than four (4) years, or both.

G19. REPORTING PLANNED CHANGES

The Permittee must, as soon as possible, give notice to Ecology of planned physical alterations, modifications or additions to the permitted construction activity. The Permittee should be aware that, depending on the nature and size of the changes to the original permit, a new public notice and other permit process requirements may be required. Changes in activities that require reporting to Ecology include those that will result in:

- A.** The permitted facility being determined to be a new source pursuant to 40 CFR 122.29(b).
- B.** A significant change in the nature or an increase in quantity of pollutants discharged, including but not limited to: a 20% or greater increase in acreage disturbed by construction activity.
- C.** A change in or addition of surface water(s) receiving stormwater or non-stormwater from the construction activity.
- D.** A change in the construction plans and/or activity that affects the Permittee's monitoring requirements in Special Condition S4.

Following such notice, permit coverage may be modified, or revoked and reissued pursuant to 40 CFR 122.62(a) to specify and limit any pollutants not previously limited. Until such modification is effective, any new or increased discharge in excess of permit limits or not specifically authorized by this permit constitutes a violation.

G20. REPORTING OTHER INFORMATION

Where the Permittee becomes aware that it failed to submit any relevant facts in a permit application, or submitted incorrect information in a permit application or in any report to Ecology, it must promptly submit such facts or information.

G21. REPORTING ANTICIPATED NON-COMPLIANCE

The Permittee must give advance notice to Ecology by submission of a new application or supplement thereto at least forty-five (45) days prior to commencement of such discharges, of any facility expansions, production increases, or other planned changes, such as process modifications, in the permitted facility or activity which may result in noncompliance with permit limits or conditions. Any maintenance of facilities, which might necessitate unavoidable interruption of

operation and degradation of effluent quality, must be scheduled during non-critical water quality periods and carried out in a manner approved by Ecology.

G22. REQUESTS TO BE EXCLUDED FROM COVERAGE UNDER THE PERMIT

Any discharger authorized by this permit may request to be excluded from coverage under the general permit by applying for an individual permit. The discharger must submit to the Director an application as described in WAC 173-220-040 or WAC 173-216-070, whichever is applicable, with reasons supporting the request. These reasons will fully document how an individual permit will apply to the applicant in a way that the general permit cannot. Ecology may make specific requests for information to support the request. The Director will either issue an individual permit or deny the request with a statement explaining the reason for the denial. When an individual permit is issued to a discharger otherwise subject to the construction stormwater general permit, the applicability of the construction stormwater general permit to that Permittee is automatically terminated on the effective date of the individual permit.

G23. APPEALS

- A.** The terms and conditions of this general permit, as they apply to the appropriate class of dischargers, are subject to appeal by any person within 30 days of issuance of this general permit, in accordance with Chapter 43.21B RCW, and Chapter 173-226 WAC.
- B.** The terms and conditions of this general permit, as they apply to an individual discharger, are appealable in accordance with Chapter 43.21B RCW within 30 days of the effective date of coverage of that discharger. Consideration of an appeal of general permit coverage of an individual discharger is limited to the general permit's applicability or nonapplicability to that individual discharger.
- C.** The appeal of general permit coverage of an individual discharger does not affect any other dischargers covered under this general permit. If the terms and conditions of this general permit are found to be inapplicable to any individual discharger(s), the matter shall be remanded to Ecology for consideration of issuance of an individual permit or permits.

G24. SEVERABILITY

The provisions of this permit are severable, and if any provision of this permit, or application of any provision of this permit to any circumstance, is held invalid, the application of such provision to other circumstances, and the remainder of this permit shall not be affected thereby.

G25. BYPASS PROHIBITED

A. Bypass Procedures

Bypass, which is the intentional diversion of waste streams from any portion of a treatment facility, is prohibited for stormwater events below the design criteria for stormwater management. Ecology may take enforcement action against a Permittee for bypass unless one of the following circumstances (1, 2, 3 or 4) is applicable.

- 1. Bypass of stormwater is consistent with the design criteria and part of an approved management practice in the applicable stormwater management manual.
- 2. Bypass for essential maintenance without the potential to cause violation of permit limits or conditions.

Bypass is authorized if it is for essential maintenance and does not have the potential to cause violations of limitations or other conditions of this permit, or adversely impact public health.

3. Bypass of stormwater is unavoidable, unanticipated, and results in noncompliance of this permit.

This bypass is permitted only if:

- a. Bypass is unavoidable to prevent loss of life, personal injury, or severe property damage. "Severe property damage" means substantial physical damage to property, damage to the treatment facilities which would cause them to become inoperable, or substantial and permanent loss of natural resources which can reasonably be expected to occur in the absence of a bypass.
 - b. There are no feasible alternatives to the bypass, such as the use of auxiliary treatment facilities, retention of untreated wastes, maintenance during normal periods of equipment downtime (but not if adequate backup equipment should have been installed in the exercise of reasonable engineering judgment to prevent a bypass which occurred during normal periods of equipment downtime or preventative maintenance), or transport of untreated wastes to another treatment facility.
 - c. Ecology is properly notified of the bypass as required in Special Condition S5.F of this permit.
4. A planned action that would cause bypass of stormwater and has the potential to result in noncompliance of this permit during a storm event.

The Permittee must notify Ecology at least thirty (30) days before the planned date of bypass. The notice must contain:

- a. A description of the bypass and its cause
 - b. An analysis of all known alternatives which would eliminate, reduce, or mitigate the need for bypassing.
 - c. A cost-effectiveness analysis of alternatives including comparative resource damage assessment.
 - d. The minimum and maximum duration of bypass under each alternative.
 - e. A recommendation as to the preferred alternative for conducting the bypass.
 - f. The projected date of bypass initiation.
 - g. A statement of compliance with SEPA.
 - h. A request for modification of water quality standards as provided for in WAC 173-201A-110, if an exceedance of any water quality standard is anticipated.
 - i. Steps taken or planned to reduce, eliminate, and prevent reoccurrence of the bypass.
5. For probable construction bypasses, the need to bypass is to be identified as early in the planning process as possible. The analysis required above must be considered during

preparation of the Stormwater Pollution Prevention Plan (SWPPP) and must be included to the extent practical. In cases where the probable need to bypass is determined early, continued analysis is necessary up to and including the construction period in an effort to minimize or eliminate the bypass.

Ecology will consider the following before issuing an administrative order for this type bypass:

- a. If the bypass is necessary to perform construction or maintenance-related activities essential to meet the requirements of this permit.
- b. If there are feasible alternatives to bypass, such as the use of auxiliary treatment facilities, retention of untreated wastes, stopping production, maintenance during normal periods of equipment down time, or transport of untreated wastes to another treatment facility.
- c. If the bypass is planned and scheduled to minimize adverse effects on the public and the environment.

After consideration of the above and the adverse effects of the proposed bypass and any other relevant factors, Ecology will approve, conditionally approve, or deny the request. The public must be notified and given an opportunity to comment on bypass incidents of significant duration, to the extent feasible. Approval of a request to bypass will be by administrative order issued by Ecology under RCW 90.48.120.

B. Duty to Mitigate

The Permittee is required to take all reasonable steps to minimize or prevent any discharge or sludge use or disposal in violation of this permit that has a reasonable likelihood of adversely affecting human health or the environment.

APPENDIX A – DEFINITIONS

AKART is an acronym for “**All Known, Available, and Reasonable** methods of prevention, control, and Treatment.” AKART represents the most current methodology that can be reasonably required for preventing, controlling, or abating the pollutants and controlling pollution associated with a discharge.

Applicable TMDL means a TMDL for turbidity, fine sediment, high pH, or phosphorus, which was completed and approved by EPA before January 1, 2021, or before the date the operator’s complete permit application is received by Ecology, whichever is later. TMDLs completed after a complete permit application is received by Ecology become applicable to the Permittee only if they are imposed through an administrative order by Ecology, or through a modification of permit coverage.

Applicant means an *operator* seeking coverage under this permit.

Benchmark means a pollutant concentration used as a permit threshold, below which a pollutant is considered unlikely to cause a water quality violation, and above which it may. When pollutant concentrations exceed benchmarks, corrective action requirements take effect. Benchmark values are not water quality standards and are not numeric effluent limitations; they are indicator values.

Best Management Practices (BMPs) means schedules of activities, prohibitions of practices, maintenance procedures, and other physical, structural and/or managerial practices to prevent or reduce the pollution of waters of the State. BMPs include treatment systems, operating procedures, and practices to control stormwater associated with construction activity, spillage or leaks, sludge or waste disposal, or drainage from raw material storage.

Buffer means an area designated by a local jurisdiction that is contiguous to and intended to protect a sensitive area.

Bypass means the intentional diversion of waste streams from any portion of a treatment facility.

Calendar Day A period of 24 consecutive hours starting at 12:00 midnight and ending the following 12:00 midnight.

Calendar Week (same as **Week**) means a period of seven consecutive days starting at 12:01 a.m. (0:01 hours) on Sunday.

Certified Erosion and Sediment Control Lead (CESCL) means a person who has current certification through an approved erosion and sediment control training program that meets the minimum training standards established by Ecology (See BMP C160 in the SWMM).

Chemical Treatment means the addition of chemicals to stormwater and/or authorized non-stormwater prior to filtration and discharge to surface waters.

Clean Water Act (CWA) means the Federal Water Pollution Control Act enacted by Public Law 92-500, as amended by Public Laws 95-217, 95-576, 96-483, and 97-117; USC 1251 et seq.

Combined Sewer means a sewer which has been designed to serve as a sanitary sewer and a storm sewer, and into which inflow is allowed by local ordinance.

Common Plan of Development or Sale means a site where multiple separate and distinct construction activities may be taking place at different times on different schedules and/or by different contractors, but still under a single plan. Examples include: 1) phased projects and projects with multiple filings or lots, even if the separate phases or filings/lots will be constructed under separate contract or by separate owners (e.g., a development where lots are sold to separate builders); 2) a development plan that may be phased over multiple years, but is still under a consistent plan for long-term development; 3) projects in a contiguous area that may be unrelated but still under the same contract, such as construction of a building extension and a new parking lot at the same facility; and 4) linear projects such as roads, pipelines, or utilities. If the project is part of a common plan of development or sale, the disturbed area of the entire plan must be used in determining permit requirements.

Composite Sample means a mixture of grab samples collected at the same sampling point at different times, formed either by continuous sampling or by mixing discrete samples. May be "time-composite" (collected at constant time intervals) or "flow-proportional" (collected either as a constant sample volume at time intervals proportional to stream flow, or collected by increasing the volume of each aliquot as the flow increases while maintaining a constant time interval between the aliquots).

Concrete Wastewater means any water used in the production, pouring and/or clean-up of concrete or concrete products, and any water used to cut, grind, wash, or otherwise modify concrete or concrete products. Examples include water used for or resulting from concrete truck/mixer/pumper/tool/chute rinsing or washing, concrete saw cutting and surfacing (sawing, coring, grinding, roughening, hydro-demolition, bridge and road surfacing). When stormwater comes in contact with concrete wastewater, the resulting water is considered concrete wastewater and must be managed to prevent discharge to waters of the State, including groundwater.

Construction Activity means land disturbing operations including clearing, grading or excavation which disturbs the surface of the land (including off-site disturbance acreage related to construction-support activity). Such activities may include road construction, construction of residential houses, office buildings, or industrial buildings, site preparation, soil compaction, movement and stockpiling of topsoils, and demolition activity.

Construction Support Activity means off-site acreage that will be disturbed as a direct result of the construction project and will discharge stormwater. For example, off-site equipment staging yards, material storage areas, borrow areas, and parking areas.

Contaminant means any hazardous substance that does not occur naturally or occurs at greater than natural background levels. See definition of "hazardous substance" and WAC 173-340-200.

Contaminated soil means soil which contains contaminants, pollutants, or hazardous substances that do not occur naturally or occur at levels greater than natural background.

Contaminated groundwater means groundwater which contains contaminants, pollutants, or hazardous substances that do not occur naturally or occur at levels greater than natural background.

Demonstrably Equivalent means that the technical basis for the selection of all stormwater BMPs is documented within a SWPPP, including:

1. The method and reasons for choosing the stormwater BMPs selected.
2. The pollutant removal performance expected from the BMPs selected.

3. The technical basis supporting the performance claims for the BMPs selected, including any available data concerning field performance of the BMPs selected.
4. An assessment of how the selected BMPs will comply with state water quality standards.
5. An assessment of how the selected BMPs will satisfy both applicable federal technology-based treatment requirements and state requirements to use all known, available, and reasonable methods of prevention, control, and treatment (AKART).

Department means the Washington State Department of Ecology.

Detention means the temporary storage of stormwater to improve quality and/or to reduce the mass flow rate of discharge.

Dewatering means the act of pumping groundwater or stormwater away from an active construction site.

Director means the Director of the Washington State Department of Ecology or his/her authorized representative.

Discharger means an owner or operator of any facility or activity subject to regulation under Chapter 90.48 RCW or the Federal Clean Water Act.

Domestic Wastewater means water carrying human wastes, including kitchen, bath, and laundry wastes from residences, buildings, industrial establishments, or other places, together with such groundwater infiltration or surface waters as may be present.

Ecology means the Washington State Department of Ecology.

Engineered Soils means the use of soil amendments including, but not limited, to Portland cement treated base (CTB), cement kiln dust (CKD), or fly ash to achieve certain desirable soil characteristics.

Equivalent BMPs means operational, source control, treatment, or innovative BMPs which result in equal or better quality of stormwater discharge to surface water or to groundwater than BMPs selected from the SWMM.

Erosion means the wearing away of the land surface by running water, wind, ice, or other geological agents, including such processes as gravitational creep.

Erosion and Sediment Control BMPs means BMPs intended to prevent erosion and sedimentation, such as preserving natural vegetation, seeding, mulching and matting, plastic covering, filter fences, sediment traps, and ponds. Erosion and sediment control BMPs are synonymous with stabilization and structural BMPs.

Federal Operator is an entity that meets the definition of "Operator" in this permit and is either any department, agency or instrumentality of the executive, legislative, and judicial branches of the Federal government of the United States, or another entity, such as a private contractor, performing construction activity for any such department, agency, or instrumentality.

Final Stabilization (same as **fully stabilized** or **full stabilization**) means the completion of all soil disturbing activities at the site and the establishment of permanent vegetative cover, or equivalent permanent stabilization measures (such as pavement, riprap, gabions, or geotextiles) which will prevent erosion. See the applicable Stormwater Management Manual for more information on vegetative cover expectations and equivalent permanent stabilization measures.

Groundwater means water in a saturated zone or stratum beneath the land surface or a surface waterbody.

Hazardous Substance means any dangerous or extremely hazardous waste as defined in RCW 70.105.010 (5) and (6), or any dangerous or extremely dangerous waste as designated by rule under chapter 70.105 RCW; any hazardous sub-stance as defined in RCW 70.105.010(14) or any hazardous substance as defined by rule under chapter 70.105 RCW; any substance that, on the effective date of this section, is a hazardous substance under section 101(14) of the federal cleanup law, 42U.S.C., Sec. 9601(14); petroleum or petroleum products; and any substance or category of substances, including solid waste decomposition products, determined by the director by rule to present a threat to human health or the environment if released into the environment. The term hazardous substance does not include any of the following when contained in an underground storage tank from which there is not a release: crude oil or any fraction thereof or petroleum, if the tank is in compliance with all applicable federal, state, and local law.

Injection Well means a well that is used for the subsurface emplacement of fluids. (See **Well**.)

Jurisdiction means a political unit such as a city, town or county; incorporated for local self-government.

National Pollutant Discharge Elimination System (NPDES) means the national program for issuing, modifying, revoking and reissuing, terminating, monitoring, and enforcing permits, and imposing and enforcing pretreatment requirements, under sections 307, 402, 318, and 405 of the Federal Clean Water Act, for the discharge of pollutants to surface waters of the State from point sources. These permits are referred to as NPDES permits and, in Washington State, are administered by the Washington State Department of Ecology.

Notice of Intent (NOI) means the application for, or a request for coverage under this general permit pursuant to WAC 173-226-200.

Notice of Termination (NOT) means a request for termination of coverage under this general permit as specified by Special Condition S10 of this permit.

Operator means any party associated with a construction project that meets either of the following two criteria:

- The party has operational control over construction plans and specifications, including the ability to make modifications to those plans and specifications; or
- The party has day-to-day operational control of those activities at a project that are necessary to ensure compliance with a SWPPP for the site or other permit conditions (e.g., they are authorized to direct workers at a site to carry out activities required by the SWPPP or comply with other permit conditions).

Permittee means individual or entity that receives notice of coverage under this general permit.

pH means a liquid's measure of acidity or alkalinity. A pH of 7 is defined as neutral. Large variations above or below this value are considered harmful to most aquatic life.

pH Monitoring Period means the time period in which the pH of stormwater runoff from a site must be tested a minimum of once every seven days to determine if stormwater pH is between 6.5 and 8.5.

Point Source means any discernible, confined, and discrete conveyance, including but not limited to, any pipe, ditch, channel, tunnel, conduit, well, discrete fissure, and container from which pollutants are or may be discharged to surface waters of the State. This term does not include return flows from irrigated agriculture. (See the Fact Sheet for further explanation)

Pollutant means dredged spoil, solid waste, incinerator residue, filter backwash, sewage, garbage, domestic sewage sludge (biosolids), munitions, chemical wastes, biological materials, radioactive materials, heat, wrecked or discarded equipment, rock, sand, cellar dirt, and industrial, municipal, and agricultural waste. This term does not include sewage from vessels within the meaning of section 312 of the CWA, nor does it include dredged or fill material discharged in accordance with a permit issued under section 404 of the CWA.

Pollution means contamination or other alteration of the physical, chemical, or biological properties of waters of the State; including change in temperature, taste, color, turbidity, or odor of the waters; or such discharge of any liquid, gaseous, solid, radioactive or other substance into any waters of the State as will or is likely to create a nuisance or render such waters harmful, detrimental or injurious to the public health, safety or welfare; or to domestic, commercial, industrial, agricultural, recreational, or other legitimate beneficial uses; or to livestock, wild animals, birds, fish or other aquatic life.

Process Wastewater means any non-stormwater which, during manufacturing or processing, comes into direct contact with or results from the production or use of any raw material, intermediate product, finished product, byproduct, or waste product. If stormwater commingles with process wastewater, the commingled water is considered process wastewater.

Receiving Water means the waterbody at the point of discharge. If the discharge is to a storm sewer system, either surface or subsurface, the receiving water is the waterbody to which the storm system discharges. Systems designed primarily for other purposes such as for groundwater drainage, redirecting stream natural flows, or for conveyance of irrigation water/return flows that coincidentally convey stormwater are considered the receiving water.

Representative means a stormwater or wastewater sample which represents the flow and characteristics of the discharge. Representative samples may be a grab sample, a time-proportionate *composite sample*, or a flow proportionate sample. Ecology's Construction Stormwater Monitoring Manual provides guidance on representative sampling.

Responsible Corporate Officer for the purpose of signatory authority means: (i) a president, secretary, treasurer, or vice-president of the corporation in charge of a principal business function, or any other person who performs similar policy- or decision-making functions for the corporation, or (ii) the manager of one or more manufacturing, production, or operating facilities, provided, the manager is authorized to make management decisions which govern the operation of the regulated facility including having the explicit or implicit duty of making major capital investment recommendations, and initiating and directing other comprehensive measures to assure long term environmental compliance with environmental laws and regulations; the manager can ensure that the necessary systems are established or actions taken to gather complete and accurate information for permit application requirements; and where authority to sign documents has been assigned or delegated to the manager in accordance with corporate procedures (40 CFR 122.22).

Sanitary Sewer means a sewer which is designed to convey domestic wastewater.

Sediment means the fragmented material that originates from the weathering and erosion of rocks or unconsolidated deposits, and is transported by, suspended in, or deposited by water.

Sedimentation means the depositing or formation of sediment.

Sensitive Area means a waterbody, wetland, stream, aquifer recharge area, or channel migration zone.

SEPA (State Environmental Policy Act) means the Washington State Law, RCW 43.21C.020, intended to prevent or eliminate damage to the environment.

Significant Amount means an amount of a pollutant in a discharge that is amenable to available and reasonable methods of prevention or treatment; or an amount of a pollutant that has a reasonable potential to cause a violation of surface or groundwater quality or sediment management standards.

Significant Concrete Work means greater than 1000 cubic yards placed or poured concrete or recycled concrete used over the life of a project.

Significant Contributor of Pollutants means a facility determined by Ecology to be a contributor of a significant amount(s) of a pollutant(s) to waters of the State of Washington.

Site means the land or water area where any "facility or activity" is physically located or conducted.

Source Control BMPs means physical, structural or mechanical devices or facilities that are intended to prevent pollutants from entering stormwater. A few examples of source control BMPs are erosion control practices, maintenance of stormwater facilities, constructing roofs over storage and working areas, and directing wash water and similar discharges to the sanitary sewer or a dead end sump.

Stabilization means the application of appropriate BMPs to prevent the erosion of soils, such as, temporary and permanent seeding, vegetative covers, mulching and matting, plastic covering and sodding. See also the definition of Erosion and Sediment Control BMPs.

Storm Drain means any drain which drains directly into a *storm sewer system*, usually found along roadways or in parking lots.

Storm Sewer System means a means a conveyance, or system of conveyances (including roads with drainage systems, municipal streets, catch basins, curbs, gutters, ditches, manmade channels, or storm drains designed or used for collecting or conveying stormwater. This does not include systems which are part of a *combined sewer* or Publicly Owned Treatment Works (POTW), as defined at 40 CFR 122.2.

Stormwater means that portion of precipitation that does not naturally percolate into the ground or evaporate, but flows via overland flow, interflow, pipes, and other features of a stormwater drainage system into a defined surface waterbody, or a constructed infiltration facility.

Stormwater Management Manual (SWMM) or Manual means the technical Manual published by Ecology for use by local governments that contain descriptions of and design criteria for BMPs to prevent, control, or treat pollutants in stormwater.

Stormwater Pollution Prevention Plan (SWPPP) means a documented plan to implement measures to identify, prevent, and control the contamination of point source discharges of stormwater.

Surface Waters of the State includes lakes, rivers, ponds, streams, inland waters, salt waters, and all other surface waters and water courses within the jurisdiction of the state of Washington.

Temporary Stabilization means the exposed ground surface has been covered with appropriate materials to provide temporary stabilization of the surface from water or wind erosion. Materials include, but are not limited to, mulch, riprap, erosion control mats or blankets and temporary cover crops. Seeding alone is not considered stabilization. Temporary stabilization is not a substitute for the more permanent “final stabilization.”

Total Maximum Daily Load (TMDL) means a calculation of the maximum amount of a pollutant that a waterbody can receive and still meet state water quality standards. Percentages of the total maximum daily load are allocated to the various pollutant sources. A TMDL is the sum of the allowable loads of a single pollutant from all contributing point and nonpoint sources. The TMDL calculations must include a "margin of safety" to ensure that the waterbody can be protected in case there are unforeseen events or unknown sources of the pollutant. The calculation must also account for seasonable variation in water quality.

Transfer of Coverage (TOC) means a request for transfer of coverage under this general permit as specified by Special Condition S2.A of this permit.

Treatment BMPs means BMPs that are intended to remove pollutants from stormwater. A few examples of treatment BMPs are detention ponds, oil/water separators, biofiltration, and constructed wetlands.

Transparency means a measurement of water clarity in centimeters (cm), using a 60 cm transparency tube. The transparency tube is used to estimate the relative clarity or transparency of water by noting the depth at which a black and white Secchi disc becomes visible when water is released from a value in the bottom of the tube. A transparency tube is sometimes referred to as a “turbidity tube.”

Turbidity means the clarity of water expressed as nephelometric turbidity units (NTUs) and measured with a calibrated turbidimeter.

Uncontaminated means free from any contaminant. See definition of “contaminant” and WAC 173-340-200.

Upset means an exceptional incident in which there is unintentional and temporary noncompliance with technology-based permit effluent limitations because of factors beyond the reasonable control of the Permittee. An upset does not include noncompliance to the extent caused by operational error, improperly designed treatment facilities, inadequate treatment facilities, lack of preventive maintenance, or careless or improper operation.

Waste Load Allocation (WLA) means the portion of a receiving water’s loading capacity that is allocated to one of its existing or future point sources of pollution. WLAs constitute a type of water quality based effluent limitation (40 CFR 130.2[h]).

Water-Only Based Shaft Drilling is a shaft drilling process that uses water only and no additives are involved in the drilling of shafts for construction of building, road, or bridge foundations.

Water Quality means the chemical, physical, and biological characteristics of water, usually with respect to its suitability for a particular purpose.

Waters of the State includes those waters as defined as "waters of the United States" in 40 CFR Subpart 122.2 within the geographic boundaries of Washington State and "waters of the State" as defined in Chapter 90.48 RCW, which include lakes, rivers, ponds, streams, inland waters, underground waters, salt

waters, and all other surface waters and water courses within the jurisdiction of the state of Washington.

Well means a bored, drilled or driven shaft, or dug hole whose depth is greater than the largest surface dimension. (See **Injection Well**.)

Wheel Wash Wastewater means any water used in, or resulting from the operation of, a tire bath or wheel wash (BMP C106: Wheel Wash), or other structure or practice that uses water to physically remove mud and debris from vehicles leaving a construction site and prevent track-out onto roads. When stormwater comes in contact with wheel wash wastewater, the resulting water is considered wheel wash wastewater and must be managed according to Special Condition S9.D.9.

APPENDIX B – ACRONYMS

AKART	All Known, Available, and Reasonable Methods of Prevention, Control, and Treatment
BMP	Best Management Practice
CESCL	Certified Erosion and Sediment Control Lead
CFR	Code of Federal Regulations
CKD	Cement Kiln Dust
cm	Centimeters
CPD	Common Plan of Development
CTB	Cement-Treated Base
CWA	Clean Water Act
DMR	Discharge Monitoring Report
EPA	Environmental Protection Agency
ERTS	Environmental Report Tracking System
ESC	Erosion and Sediment Control
FR	Federal Register
LID	Low Impact Development
NOI	Notice of Intent
NOT	Notice of Termination
NPDES	National Pollutant Discharge Elimination System
NTU	Nephelometric Turbidity Unit
RCW	Revised Code of Washington
SEPA	State Environmental Policy Act
SWMM	Stormwater Management Manual
SWPPP	Stormwater Pollution Prevention Plan
TMDL	Total Maximum Daily Load
UIC	Underground Injection Control
USC	United States Code
USEPA	United States Environmental Protection Agency
WAC	Washington Administrative Code
WQ	Water Quality
WWHM	Western Washington Hydrology Model

THIS PAGE INTENTIONALLY LEFT BLANK

APPENDIX G

ADDENDA

THIS PAGE INTENTIONALLY LEFT BLANK